


CULTURE-HOUSE

Located within a developing Transit-Oriented Area, the project is tasked with delivering a high-density, mixed-use development while embracing the rich local and Indigenous culture. Our proposal seeks collective efforts to address this design challenge. From housing providers, Indigenous artist groups, and local residents to design professionals, prefabrication specialists, and government agencies, the collaboration extends from neighbourhood planning to site-specific operations.

The project includes residential and cultural spaces that work together to create a hybrid, vibrant, and inclusive community. It is a place that celebrates local and Indigenous culture, prefabricated building technologies, and sustainability. The project challenges current building codes and policies to unlock the full potential of mass timber construction, proposes alternative prefabrication methods to reduce construction time and costs, and provides a healthy living environment as well as community cultural spaces.




HYBRID CONSTRUCTION AND SHARED NEIGHBOURHOOD PLANNING


We propose a hybrid construction approach that combines panelized and volumetric prefabrication to balance efficiency, cost-effectiveness, and quality. Panelized construction offers lower transportation costs and greater design flexibility, while volumetric construction enables faster on-site installation with higher precision. By integrating both methods, developments can reduce overall construction time, lower costs, and minimize the carbon footprint.


This hybrid approach is realized by **identifying and establishing temporary site-adjacent factories** on select parcels to support production for neighbouring projects with earlier development timelines. These facilities would assemble panelized prefabricated components and other building elements into completed volumetric modules before lifting them into place on nearby sites. This strategy reduces transportation logistics while maintaining high construction quality in a controlled factory environment. Incentives could be

introduced for hosting parcels, such as reduced Community Amenity Contribution charges when the hosting site transitions to its development phase.

As sites across the Transit-Oriented Area come to development, further collaboration among projects can reduce construction costs and unlock mixed-use potential. For example, developments could implement shared parking infrastructure, consolidating vehicular access to fewer entry points. This would free the ground plane for safe and pedestrian-friendly laneways, creating vibrant public spaces connecting to transit stations. An interconnected parking network and reduced access ramps would improve land efficiency, lower construction costs, and reduce overall parking requirements. Similarly, amenity programming can be coordinated to diversify shared resources, avoid redundancy, and enrich the neighbourhood fabric. Instead of replicating standard amenity spaces in every building, each development could host distinct facilities - such as fitness centres, co-working spaces, childcare, or cultural venues - made accessible to all residents through shared-use agreements.







HYBRID STRUCTURAL STRATEGY


The building utilizes different structural systems for different components, each selected for its specific advantages.

For the lower three levels, which house artist programs, a mass timber post-and-beam system is used to achieve the larger spans required for open public spaces. Additional cross-bracing provides lateral stability and helps transfer loads from the upper floors to the foundation.

The upper residential levels employ volumetric mass timber modules for efficient, standardized assembly. While each student housing unit consists of a single module, rental housing units ranging from one to three-bedroom contain multiple modules to maintain standardization on panel sizes and streamline installation workflows.

These modules rest on the post-and-beam structure below and are tied together through continuous load paths. Concrete building cores run the full height of the building, providing vertical circulation, connecting all components, and acting as the primary lateral force-resisting system.

The project incorporates two balcony systems: an enclosed balcony with a CLT floor integrated into the volumetric construction, providing protected and spacious outdoor areas for rental units; and a prefabricated clip-on balcony system, enabling quick installation and durable, individual outdoor spaces for student housing units.



Rental Housing - Consist of multiple prefabricated volumetric construction modules assembled together, with enclosed balconies installed on site.



 Enclosed balcony is used to protect CLT floor and provide usable outdoor space all year

around.

CLT floor and walls


DTT-A-01

- Exposed CLT floor provides natural wood finish to indoor and outdoor living spaces, while additional CLT bulkhead contains horizontal services and enhances fire separation.
- Post-and-beam structure is used above the art school and workshop for open space and to transfer load from the floors above.
- A reinforced concrete topping is applied over the CLT floor to increase the fire-resistance rating and to act compositely with the timber in carrying compressive forces as part of an integrated floor system.
- A combination of louver screens and canopies is used to diffuse daylight and control solar heat gain.

DECODING BUILDING POLICIES

1. Align Building Height with Provincial TOA Policy Reference: TOA Policy, BC Building Code 3.2.2.93

The BC Building Code currently permits mass timber buildings up to 18 storeys, yet the Provincial Transit-Oriented Areas (TOA) Policy sets a *minimum* allowable building height of 20 storeys within Tier 1. This misalignment represents a missed opportunity for mass timber to reach its full development potential in TOA-designated areas. Mass timber buildings exceeding 20 storeys have already been proven achievable around the world. With established structural and fire safety precedents, **updating the BC Building Code to align with TOA policy** is both feasible and advantageous.



2. City-wide Zoning and Development Framework Update Reference: TOA Policy, Municipal Zoning Bylaw

A city-wide zoning change for TOA areas that align with provincial policy can **eliminate the need for site-specific rezoning**, significantly reducing permitting time and development costs.

Currently, some municipal frameworks impose both height and density limits, with developments triggering rezoning if either threshold is exceeded. Recent TOA project examples


have shown that while a 20-storey building complies with the height requirement, it often exceeds the 5.0 FSR density set out under zoning policy — resulting in unintended rezoning. We propose **unifying the development framework** by either:

- a. Increasing the allowable density to support 20-storey or more developments, or
- b. Adopting a single regulatory metric either height or density to simplify the approval process.

3. Alternative Approaches to Encapsulation Requirements Reference: BC Building Code 3.1.6.4 & 3.2.2.93

We suggest alleviating encapsulation requirements to both reduce construction costs and highlight the exposed mass timber aesthetic. Reducing the use of gypsum boards also contributes to lower carbon emissions. To maintain fire safety, we propose several alternative approaches that are appropriate for mass timber construction.

For volumetric construction modules consisting of CLT floor and ceiling panels, the ceiling of the lower module can act as the fire-protective layer for the floor of module above, eliminating the need for additional encapsulation. Horizontal plenums between modules units can replace dropped ceilings for mechanical systems, further minimizing gypsum use. Additionally, sprinklers within concealed spaces can provide further fire protection.



On lower levels constructed with post-and beam systems,

we propose combining enhanced fire separation floor assembly with active suppression systems in place of rated encapsulation. The thicker CLT slabs — used for larger spans — also naturally provide an higher rating for fire separation.

4. Standardize and Implement CSA A277 Reference: CSA A277

Although CSA A277 provides standards for off-site construction, its implementation remains inconsistent. Many stakeholders are unaware of the standard or unsure of their roles during off-site fabrication. This ambiguity often leads to confusion and rejection of prefabricated components at the construction site. To address this, we recommend clear assignment of responsibilities within the CSA A277 framework and broader education across the construction industry to support effective and consistent application.



5. Enable Use of Enclosed Balconies Reference: Municipal Zoning Bylaw


Not all municipalities permit enclosed balconies, and some impose limits on their maximum allowable area. Enclosed balconies enhance year-round usability, particularly for mass timber buildings, where standard **CLT balconies**

benefit from added weather protection. We believe

accessible, weather-protected outdoor space is essential for all residents. A modest revision to zoning bylaws to permit enclosed balconies could deliver meaningful improvements in both quality of life and building performance.

6. Introduce Prefabrication Building Permit Reference: Municipal Building Permit Requirements

Prefabricated construction requires intricate coordination and often a longer design cycle. Currently, there is a significant lag between full building permit submission and the start of off-site fabrication. To address this, we propose introducing a **Prefabrication Building Permit**. Similar to how excavation permits allow for early site work, **this permit would specifically cover prefabricated structural components and authorize off-site construction** to begin before the full building permit is finalized. The additional building permit phase can align overall permitting process well with design and prefabrication workflows, reduce overall project timelines, and enhance construction efficiency.





SUSTAINABLE BUILDING PRO FORMA

The building is designed on a 12' by 12' grid system to unify various program spaces into a clear modular and structural layout. The housing components include a mix of student housing and one to three bedroom units, allowing for different housing mixes and ready for adaptable configurations.

The project aims to reduce its carbon footprint by using mass timber construction combined with a siteadjacent factory, which lowers carbon emissions typically associated with transporting volumetric modules. A shared parking network and fewer parking entrances across the neighborhood increase parking and mechanical service space efficiency, while minimizing excavation needs at all Transit-Oriented Area sites further reducing both carbon footprint and construction costs.


Additional carbon reductions are achieved through the use of lowcarbon concrete for underground structures and lateral reinforcement, and by minimizing gypsum board use with alternative approaches to encapsulation requirement.

The project also benefits from a streamlined construction schedule, supported by a new prefabrication building permit that aligns with the prefabrication design and construction cycle. This approach shortens the total construction time and effectively lowers overall costs.


- 1 Artist Live Work
- 2 Residential Lobby
- 3 Performance Space
- 4 Gallery / Event Space
- 5 Art School
- 6 Workshop
- 7 Student housing 8 Common Space
- 9 Rental 1 Bed
- 10 Rental 2 Bed
- 11 Rental 3 Bed
- 12 Rental Studio







Level 4 to 8 - Student Housing and Rental




Level 2 - Living for Artist Live/Work



Level 9 to 20 - Typical Rental with 1-2 Bedroom Mix



Level 3 - Workshop, Art School



Level 9 to 20 - Typical Rental with Studio-3 Bedroom Mix



FSR	8
LOT SIZE	18,300 s
BUILDING SQ FT ABOVE GRADE	146,450 s
BUILDING EFFICIENCY (%)	
NON RENTABLE	29,935 s
RENTABLE	116,515 s
TOTAL STORIES ABOVE GRADE	
TOTAL STORIES	
BASE FLOOR	
ABOVE 1ST STOREY	
STORIES BELOW GRADE	
UNITS	
BEDROOMS	
AMENITY SPACE	6,540 s
NON DECIDENTIAL	0.000

PROJECT DATA	
FSR	8.0
LOT SIZE	18,300 sq.
BUILDING SQ FT ABOVE GRADE	146,450 sq.
BUILDING EFFICIENCY (%)	80
NON RENTABLE	29,935 sq.
RENTABLE	116,515 sq.
TOTAL STORIES ABOVE GRADE	2
TOTAL STORIES	2
BASE FLOOR	
ABOVE 1ST STOREY	1
STORIES BELOW GRADE	
UNITS	14
BEDROOMS	23
AMENITY SPACE	6,540 sq.
NON-RESIDENTIAL	9,020 sq.

CONSTRUCTION COST		CONCRETE (I	BASE CASE)	SUBMI	SSION	
	SF	COST/SF	COST	COST/SF	COST	
BELOW GRADE	18,300 sq.ft.	\$315	\$5,764,500	\$378	\$6,917,400	LOW-CARBON CONCRETE FOR BELOW GRADE CONSTRUCTION
BASE FLOOR	12,353 sq.ft.	\$360	\$4,447,080	\$398	\$4,916,494	REDUCE GYPSUM BOARD COST THROUGH ALTERNATIVE APPROACHES (SEE PAGE 5)
ABOVE 1ST STOREY	134,097 sq.ft.	\$385	\$51,627,345	\$426	\$57,125,322	REDUCE GYPSUM BOARD COST THROUGH ALTERNATIVE APPROACHES (SEE PAGE 5)
BALCONIES	18,360 sq.ft.	\$500	\$9,180,000	\$450	\$8,262,000	CLT AND MODULAR BALCONIES ARE USED. COST CALCULATED BY AREA FOR COMPARISON
	COST/MONTH	# MONTH	COST	# MONTH	COST	
SCHEDULE COSTS	\$50,000	18	\$900,000	10	\$500,000	SUBMISSION FOLLOWS STREAMLINED CONSTRUCTION SCHEDULE (SEE PAGE 5)
TOTAL			\$71,918,925		\$77,721,216	
EMBODIED CARBON		CONCRETE (I	BASE CASE)	SUBMI	SSION	
	SF	EMBODIED CARBON	TOTAL CARBON	EMBODIED CARBON	TOTAL CARBON	
BELOW GRADE	18,300 sq.ft.	6.69 kg/sq.ft.	122,409 kg	4.01 kg/sq.ft.	73,445 kg	LOW-CARBON CONCRETE YIELDS 40% REDUCTION IN CARBON FOOTPRINT
ABOVE GRADE	164,810 sq.ft.	6.69 kg/sq.ft.	1,102,417 kg	2.39 kg/sq.ft.	394,586 kg	REDUCE CARBON FOOTPRINT THROUGH MINIMIZED GYPSUM BOARD USE
ΤΟΤΔΙ		6 60 kg/eg ft	1 224 826 kg	2 56 kg/eg ft	468 032 kg	








The original "Kapla" blocks are a toy construction set of identical wood planks measuring 11.7cm x 2.34cm x 0.78cm. It is a fun and simple modular system for children and adults.

Mass timber towers are not quite so simple, but our design is grounded in this modularity.

The building is a rectangle, optimized to the typical dimension of a 10' (3.05m) CLT panel width. The unit layouts align carefully with the glulam column grid and the facade is panelized accordingly. This is not sculptural architecture, there are no structural gymnastics. The beauty is in the material itself and the sustainable industry it supports.

That's why Kapla's proudest moment is during construction.



Student Housing 8 Storeys 40 Suites

Residential Tower 20 Storeys 80 Dwellings

20 storeys (63.2m) Building Height
525m² Building Area
10.140m² Gross Floor Area

10,140m² Gross Floor Area 8,500m² Residential GFA

5.0 Density (FSI)

80 Dwellings200 Bedrooms2 Elevators

4 Car Parking

160 Bike Parking

Kapla has a much smaller floorplate than typical high-rise projects, made possible by the compact vertical circulation core commonly known as a "Point Access Block" with a single exit stair and two elevators.


Rather than a dozen or more units along a long hallway, this compact tower has 4 to 6 dwellings per storey, so that most of the homes get a large corner balcony and living space as well as daylight and fresh air from multiple sides.

The skinny building also means smaller shadows on adjacent properties and is in keeping with the rhythm of narrower mixed-use buildings on 50' lot widths along the street. The simple structural grid also avoids costly and carbon-intensive load transfers over the long-span space of the theatre.

The result is a highly efficient tower that unlocks more outdoor space for the public at street level.



KAPLA TOWER
"POINT ACCESS BLOCK"





750m² residential floorplate 95% lot coverage

510m² residential floorplate 67% lot coverage

A HYBRID STRUCTURE ACHIEVES HEIGHT & SAFETY

The BC Building Code prescribes a maximum building height for encapsulated mass timber (EMTC) buildings up to 18 storeys, exposed mass timber up to 8 storeys and light woodframe construction up to 6 storeys. However, the current limit of 18 storeys is a risk threshold established by the height of UBC Brock Commons and can be exceeded through performance-based design.

We propose to achieve the same risk tolerance by providing a 2-storey concrete podium and 18 storeys of mass timber above, aligned with the permitted building height of 20 storey in the TOA Tier 1 Policy Area. This noncombustible podium also inherently addresses other risks such as floods, explosions and electric vehicle fires.

Although an entirely mass timber building is conceptually simpler and maximizes carbon sequestration, Kapla also has a hybrid structural design with a noncombustible vertical circulation core (exit stair, elevator shafts) to address fire and seismic risks in the lower BC mainland.

78.6 kgCO₂eq/m²

emissions factor, concrete structure of typical towers same building height and 10x10 column grid

MORE CARBON SEQUESTRATION THAN CONCRETE EMISSIONS

Emissions have been calculated using the Fast+Epp Embodied Carbon Calculator. The scope is limited to the structural system of the 20-storey residential tower only and does not include below-grade basement or foundation systems. Kapla uses 72% less concrete than a typical tower and achieves a net negative carbon balance if carbon sequestration in wood products is included in the calculation.






-0.98 kgCO₂eq/m² The current estimated social cost of carbon emissions is \$271 per tonne 1!!

175,894 CLT Slabs (175mm, 5-Ply, 10ft wide) 24,873 Glulam Beams (260 x 336mm Douglas Fir) kgCO_seq 35.752 Glulam Posts (305x315mm Douglas Fir) 260.6m 158,099 Concrete Core (35 MPa + 100kg rebar/m3) kgCO,eq 295.9 kgCO,eq/m3 Concrete Podium (35 MPa +125kg rebar/m³) 68,371 kgCO_eq 370.3 kgCO,eq/m3 236,519 total mass timber embodied carbon 226,470 total upfront concrete emissions (10,049)net balance with carbon sequestration

emissions factor, hybrid structure of KAPLA tower incl. sequestration (45.3 kgCO_.eq/m² excl. sequestration)

ADAPTABLE & ACCESSIBLE LAYOUTS

The typical floor plan is a diverse mix of one to four-bedroom units. Each of the corner units has a barrier-free adaptable bathroom, bedroom and living space. The symmetry of the design also makes it easy to merge two of the units to create a co-housing arrangement of up to 7 bedrooms. The non-structural stud partitions allow for new openings to interconnect or reconfigure the layouts for a variety of family structures and help families stay in their community as they grow or contract during different stages of life.





REVEALING THE BEAUTY OF MASS TIMBER

Exposed Ceilings: Whereas the BCBC allows a maximum of 25% of the ceiling in each suite to be exposed, we have exposed 50 to 100% of the ceiling, beams and posts in the living areas. The slabs are increased from 3-ply to 5-ply thickness to achieve the required 2-hour char time. This province should adopt proposed changes to the national model building code² based on fire testing that demonstrates the existing code is "now conservative in nature and can be safely expanded to provide additional options..."


²CBHCC, Proposed Change 1870, https://cbhcc-cchcc.ca

SAFETY FOR PEOPLE WITH REDUCED MOBILITY

In spite of 1 in 10 Canadians having a mobility disability, the code assumes people are able to use stairs to leave buildings in an emergency. KAPLA's design makes sure no one is left behind.

Egressibility: We have provided an occupant evacuation elevator (OEE) in addition to the firefighter's elevator so that persons with disabilities are able to independently and safely evacuate the building without assistance. This means updating building codes and technical standards to accommodate OEE options.

Single Exit Stair (SES): British Columbia limits SES to 6 storeys in height, whereas the 20-storey KAPLA building has a single exit stair based on examples in Sweden, Switzerland, Austria and Germany. The stair width is significantly increased, the elevator lobby is a separate area of refuge from the corridors, and a mechanical smoke control system is provided to achieve a better level of safety than the prescriptive code.



Community Theatre

The 'Kapla Playhouse' is a small theatre for local events. The warmth of the glulam structure and nail-laminated timber ceiling creates a welcoming glow visible from the street. All the back-of-house areas are at the basement level. The fire alarm system is customized for the bypass of smoke detector activation during indigenous smudging ceremonies.

Teaching Gardens

The buildings frame an outdoor space landscaped with plantings that are significant to the Musqueam, Squamish, and Tsleil-Waututh Nations. Native species such as Sitka Spruce, Pacific Crabapple and Vine Maple trees are arranged around a circular reflecting pool. The landscape extends up onto the roof of the community theatre as a garden of sage, cedar, sweetgrass and other native herbs. The deep glulam beams of the theatre are sized to handle the weight of the green roof and the edge of the basement is pulled back from the root balls of street trees.

Cars and Bicycles

Given the location of the site near transit and the cost/carbon intensity of parking garages, the building does not have resident parking. There are four visitor parking spots and 160 bicycle parking spaces (two per dwelling). 45 short-term spaces are on the ground floor and the remaining 115 long-term spaces can be accessed by stair and elevator on the mezzanine level. Additional storage space is in the basement.


Off-Street Loading Space Regulations

Different cities in the lower BC mainland and across Canada have different size requirements for garbage pick-up and loading bay areas. Smaller garbage trucks have a smaller turning radius, making a lot more space available for other uses on the ground floor.

Student Housing


The smaller mid-rise building provides 40 rooms of student housing for a nearby trades college. This includes a kitchen and dining hall beside the rooftop amenity terrace and ground floor lounge with adjacent cafe. At 8 storeys in height, the building code (BCBC 3.2.2.93) allows the mass timber posts and ceiling to be fully exposed.





UNITIZED FACADE PANELS & CAREFUL USE OF COMBUSTIBLE CLADDING

The facade is mostly required to be noncombustible, however combustible cladding is permitted for 100% of the first storey within 15m of a street and on small portions of the upper storeys if it is not contiguous over multipe storeys and is separated horizontally by a distance of at least 2.4m from any adjacent portions. The arrangement of the wood cladding panels is defined by these conditions.



Painted Metal Exterior Shutter & Planter Box (finish to match windows)

Anodized Aluminum Window Frame (bronze finish on exterior)

Fire-Retardant Treated Wood (FRTW) Cladding (max. 10% of facade area)

••••• Matte Green ACM Panel (noncombustible core)

Water Mist Systems

The use of water mist

systems (NFPA 750) is

subject to alternative solutions compliance

because Canadian

building codes only reference NFPA 13.

Water mist systems reduce post-fire water

damage and mold risks.

INVENTORY OF REPETITION


(residential tower only)

- **792** 5-PLY (175mm) CLT Slabs 440 linear ft per storey (10' spans, 20' to 40' panels)
- **504** Glulam Beams (260x336mm Douglas Fir) 28 beams per storey (2.75m span)
- 972 Glulam Posts (305x315mm Douglas Fir) 54 posts per storey (2.95m height)
- 396 Facade Panels (ACM Panel on Steel Stud)
 (3 variations of window and inset cladding details)
- 72 Corner Balconies (Prefabricated Steel Frame)
 4 per storey
- 144 Sliding Glass Door Wall Panels at Balconies
 8 per storey
- 80 Linear Kitchens 5 per storey (semi-modular, shorter run in 1-bed units)
- 160 Modular Bathroom Pods (two variations, barrier-free/adaptable and regular)
- 64 Window Sill Planter Boxes on lower storey windows only
- **1,200** Sprinklerhead Count (NFPA 750 Water Mist Type) average of 60 per storey (pipefitter to install)



Noncombustible Sidewalls

The BCBC requires any exposed building face in close proximity to a property line to be of - noncombustible construction. The code should be updated to allow mass timber and wood-frame options with increased fire-resistance ratings to achieve the same level of performance.




Public Spiral Stairs
This convenience stair is
not an exit, but the BCBC
requires it to be designed
like an exit, such that this
beautiful spiral geometry
is not allowed.



SITKA

SPRUCE

PACIFIC CRABAPPLE VINE MAPLE



LOWER CONSTRUCTION COST PER BEDROOM

PRO FORMA ANALYSIS


Kapla is situated on a smaller site than the Urbanarium's mass timber base case, reducing land costs. Our design has less dwellings but more bedrooms and bigger balconies. The small basement, compact core and exposed ceilings compensate for the complexity of hybrid construction.

KAPLA

NOTES

BASE CASE

PRO FORMA ANALYSIS	BAS	E CASE	KA	PLA	NOTES
Building Type	18 Storey	EMTC Tower	20 Storey H	Hybrid Tower	hotel and theatre excluded
FSR	5.0		5.0		incl. permitted GFA exclusions
Lot Size	25,540	sq.ft.	18,300	sq.ft.	
Building Area	7,094	sq.ft.	5500	sq.ft.	Kapla residential tower only
Lot Coverage	28%		30%		Kapla residential tower only
Building Height	18 storeys	above grade	20 storeys	above grade	
	2 storeys	below grade	1 storey	below grade	
GFA (above grade)	127,700	sq.ft	110,000	sq.ft.	Kapla residential tower only
Efficiency	85%		89%		SES compact circulation
Residential Area	108,545	sq.ft.	88,110	sq.ft.	
Non-Residential Area	19,155	sq.ft.	20,390	sq.ft.	incl. circulation, amenity, etc.
Amenity Area	850	sq.ft.	1,500	sq.ft.	
Basement Area	14,189	sq.ft.	5,500	sq.ft.	
Dwellings (#)	86		80		
Average Unit Size	1,262	sq.ft.	1,101	sq.ft.	
Bedrooms (#)	178	(2.07 beds/unit)	200	(2.5 beds/unit)	
CONSTRUCTION COST	\$/sq.ft.	Total Cost	\$/sq.ft.	Total Cost	
Basement	\$299	\$4,242,478	\$299	9 \$1,644,500	smaller basement area in Kapla
Ground and Mezzanine	\$403	3 \$2,859,061	\$360	\$3,690,000	concrete podium in Kapla
Upper Storeys	\$431	\$51,980,994	\$450	\$44,550,000	exposed ceilings, concrete core
	\$/balcony		\$/balcony		in Kapla
Balconies (1x per dwelling)	\$25,000 (small)	\$2,150,000	\$45,000 (big)	\$3,600,000	larger prefabricated balconies
	# of months		# of months		in Kapla (80 sq. ft. each)
Overhead (\$50,000 monthly)	16	\$800,000	14	\$700,000	smaller basement, repetitive structure and plan in Kapla
CONSTRUCTION ONLY		\$62,032,533		\$54,454,500	smaller overall GFA in Kapla
SOFT COSTS (design, approva	ls lenal)				
25% of construction cost		\$15,508,133		\$13,613,625	
LAND COSTS	property area		property area		
assume \$250/sq.ft.	25540 sq.ft.	\$6,385,000	18300 sq.ft.	\$4,575,000	smaller site for Kapla
DEVELOPMENT CHARGES	\$/unit		\$/unit		
avg. DCC in lower BC mainland	\$31,645	\$2,721,470	\$31,645	5 \$2,531,600	applicable for apartments 5+ storeys (Vancouver)
TOTAL PROJECT COST		\$86,647,137		\$75,174,725	Δ \$11,472,412
cost per sq.ft.	127,700 sq.ft.	\$788	110,000 sq.ft.	\$683	Δ \$104
cost per dwelling	86 dwellings	\$1,083,089	80 dwellings	\$939,684	Δ \$143,405
cost per bed	178 beds	\$486,782	200 beds	\$375,874	Δ \$110,908



LIMITED EQUITY HOUSING CO-OPERATIVE

Kapla will be developed by a non-profit developer supported by low-cost loans and mortgage insurance from the CMHC and BC Housing. The homes will be sold at-cost without typical developer profit (12-20%) and marketing expenses (3-5%). Some of the units will be sold to a "scattered" community land trust, others will be sold to the market under a restrictive covenant known as an LEHC (limited equity housing co-operative).

The purchaser benefits from buying the home at-cost, but the LEHC means that the future market value of the home is indexed to inflation and cannot be resold above this assessed value.


The units that are purchased by the community land trust are rented out at-cost. As the mortgages held by the land trust are paid down, the rents remain constant and subsidize future acquisitions of the land trust, while also becoming lower rents relative to the market over time.


This particular model recognizes that new construction is very expensive and it is very difficult to build new affordable housing without major government subsidies. The benefits of an LEHC, land trust and non-profit development model are combined to remove the project from speculation and focus on making Kapla increasingly affordable over time.











Residence Design, and Community

The residential levels are conceived as a non-profit, affordable housing development that responds to the urgent need for inclusive and equitable living spaces. The angled parallelogram layout is a formal gesture and a strategy to optimize natural light, privacy, and views, offering residents a stronger sense of connection to their surroundings.

Units are thoughtfully arranged to accommodate various household types, from singles and seniors to young families, supporting a diverse and resilient community. Shared amenities, such as laundry facilities and multipurpose lounge rooms, are positioned to encourage daily interaction, reduce isolation, and create opportunities for collective activities like shared meals, workshops, and childcare.


Outdoor terraces and courtyards serve as social anchors, offering safe and welcoming spaces for relaxation, gardening, and play. Circulation areas are treated as extensions of the home, with wide corridors and stairwells that encourage informal gatherings and casual interaction among residents. At the rear of the building, near the residential entrance, a flexible multi-use space is tucked away to provide added functionality. This space can serve as a children's playground, a secure transition zone to the outdoors, or a small performance and gathering area, adapting to the evolving needs of the community.

By combining affordability with high-quality design, the project challenges the stigma around subsidized housing and demonstrates that non-profit developments can be both socially impactful and architecturally ambitious. The ultimate goal is to create housing that fosters pride, strengthens neighbourly ties, and builds a supportive community where residents can thrive long term.





Decoding System



Construction Cost + Embodied Carbon Calculations

The modular mass timber design greatly improves efficiency and cost-effectiveness. By prefabricating units off-site, construction time on-site is significantly reduced, allowing the building to be assembled more quickly than traditional methods. Using mass timber not only lowers the embodied carbon but also reduces the need for heavy equipment and labor-intensive processes, cutting construction costs by nearly half.









Building Information	
FSR	4.9
Lot size (sq ft)	18,300
Building sq ft Above Grade	90,100
Building efficiency (%)	85
non saleable / rentalable (sq ft)	13,515
saleable / rentable (sq ft)	76,585
Total Stories above grade (#)	13
Total Stories (#)	13
Base floor (#)	1
Above 1st storey (#)	12
Stories below grade (#)	0
Units (#)	54
Bedrooms (#)	109
Amenity space (sq ft)	13,700
Non-residential (sq ft)	13,900

Construction Costs								
		Concrete		Mass Timber				
	Square footage	\$/sqft	Cost	\$/sqft	Cost			
Below grade	0.0	\$75	n/a	\$150	n/a			
Base floor	6800.0	\$75	\$510,000	\$150	\$1,020,000			
Above 1st storey	83300.0	\$75	\$6,247,500	\$150	\$12,485,000			
	Quantity	\$/unit		\$/unit				
Balconies	60	\$10,000	\$600,000	\$12,000	\$720,000			
	Cost per month	#Months	Cost	#Months	Cost			
Schedule Cost (Monthly)	\$50,000	18	\$900,000	-11	\$550,000			
TOTAL			\$8,257,500		\$14,785,000			

Embodied Carbon							
		Concrete		Mass Timber			
	Sqft	Embodied	Total	Embodied	Total		
Total Building Sq Footage	90100.0	6.69	602,680.70	2.69	242,369		

Economical

The modular mass timber design offers significant economic advantages, making the building both cost-effective and efficient to construct.

Prefabricated modules are produced off-site with precision, reducing on-site labor requirements and minimizing delays, which directly lowers overall construction costs. The modular system also reduces material waste and streamlines logistics, further contributing to savings. With a cost per square foot of approximately \$150, the 13-floor building on an 18,300 sq. ft. lot was completed for around \$14 million, demonstrating that multi-story mass timber construction can be achieved at a fraction of the expense of traditional concrete or steel methods.

Beyond initial construction costs, the design's energy-efficient systems and sustainable material choices help reduce long-term operating expenses, making the building more affordable for both developers and residents. This approach showcases how innovative design strategies can combine financial prudence with environmental responsibility, providing high-quality, multi-family housing that is both economically viable and socially beneficial.

Sustainability

The building incorporates multiple strategies to reduce its environmental impact while enhancing comfort for residents. With a Floor Space Ratio (FSR) of 4.9, the design efficiently uses the lot and maximizes light and airflow.

Natural ventilation is encouraged through wind circulation and strategically placed openings, reducing reliance on mechanical systems. Modular balconies provide outdoor space and passive shading for interior units.

The primary use of mass timber as a structural material lowers embodied carbon compared to steel or concrete, and careful material selection further supports environmental performance. Together, these strategies create a high-density residential building that balances efficiency, sustainability, and occupant comfort.


Social and Culture

The residential program prioritizes inclusivity, community, and shared experiences. The building contains 54 units with 109 bedrooms, ranging from studios and one-bedroom units to larger two- and three-bedroom apartments, accommodating diverse household types.

Each floor features shared gathering areas to encourage interaction and neighborly connections, while large communal spaces on the ground floor and rooftop provide opportunities for collective activities, events, and relaxation. Green spaces are integrated throughout the building, including landscaped terraces and courtyards, fostering a connection to nature and promoting well-being.

By combining private living with generous communal amenities, the design cultivates a strong sense of community, creating a supportive and engaging environment for all residents.





Code & Policy Timberline is located in a TOA tier 1 zone which requires a "minimum" allowable density of 5.0. It is instead an FSR of 4.7 to serve as a more transitional building in the area. Its ensures that any future structures can meet and exceed the FSR 5.0 rating without appearing too out of place in the local context. Stringent encapsulation requirements limit the viability of mass timber. This building is sprinklered, and utilizes timber of sufficient thickness to charr in the event of a fire. Encapsulation requirements limit the adoption of timber when there's already many safety measures that exist.

Two Bedroom 800 SF

Building Blocks

The Product:

The crux of this design is the low carbon module and an exploration of delivery at scale.

The Problem:

Shelter is one of the barest necessities for human survival, and yet the current market has <u>priced many out of homes</u> that would have been perfectly affordable in the past.

The Scope:

The Canadian Mortgage and Housing Corporation states that 460,000 units of housing need to be produced annually for the next decade in order to achieve affordability. Canada requires the production of 1,260 housing units every day. For the next ten years.

The Solution:

The only way for modularity to assist in this effort is for a standard module to work in a variety of residential applications. The modules need to be modular themselves. Our module designs lend themselves to this required variety, not just vertical stacks in dense cities. Core components of a home can be mass produced as modules for use everywhere. A modular kitchen and toilet room can be a part of a non-modular structure to accelerate construction.

In Timberline, spaces are comprised of multiple chunks for ease of transportation and assembly.




Three Bedroom 930 SF





Site, Sunlight, and Wind

Vancouver's location in the northern hemisphere limits the direct daylight hours the northern face of the building. Opening the building with an atrium allows interior apartment units get daylight through their south walls. As the tallest building in the neighborhood it has unobstructed views and unlimited direct sunlight. The large central atrium also allows for the strong westerly winds in Vancouver to circulate are throughout the building.



Massing

Our team took a few simple steps to achieve the form of the Timberline.

Stairs:

For optimal egress opportunities, and to help support the structure, stair towers were placed at three of the four corners of the site. A central elevator within the atrium provides vertical circulation & views of the expansive open space.

Volume:


Filling in the space between the vertical circulation creates space to maximize the number of residential units as possible on the site.

Light:

Carving out a central atrium permits light penetrate deeper into the structure creating a welcoming environment and a large open public space.

Lift:

Lifting the building mass serves to minimize its impact on the site at a human level while creating more opportunities at the human level for connections to the community.





Efficiency of space: Maintaining an efficient footprint allows for the amount of units to be maximized. This space is returned in the form of communal spaces.

Typical Residential Floor



Adaptability in amenities: Four multipurpose rooms can be used to fit the particular needs of the residents. A place to exercise, daycare, an event space, or even a library are just a few options available.



Ground Floor






Creation of community:
An open forum has been the thriving heart of communities all over the world for millennia. It will be the heart of Timberline too. With cafes, seating, and versatile open spaces, the ground floor can become whatever is needed, whenever it is needed.




A common criticism of dense apartment living is a lack of green space.

The rooftop provides a park, a garden, and a private escape from the city to residents. It serves as a personal yard to those that live here.

Rooftop Park DTT-A-04





The Plenum:

This space allows for a variety of mechanical systems to be viable within the structure. Keeping this space large and accessible allows Timberline to evolve with time and adopt more efficient systems as they become available.

Third Place:

The bottom 1/5 of Timberline is dominated by communal spaces. A bright atrium, cafes, and mixed use spaces enable a versatile space that can be utilized year-round.



Cost Base Case Analysis

Building Size	Base Case	Timberline
FSR	5	4.69
Lot Size (sq ft)	25,540	18,300
Building sq ft Above Grade	127,700	85,835
Building Efficiency %	85%	74%
Total Stories #	21	8
Units #	86	82
Bedrooms #	178	135
Amenity Space (sq ft)	850	3,707 Multipurpose Rooms
Non-Residential (sq ft)	3,000	15,555 Atrium+Cafes

Construction Cost \$/sqft (timber)	Base Case	Timberline
Below Grade \$	\$299	\$315
Base Floor \$	\$403	\$452
Above 1st Storey	\$431	\$527
Balconies	\$25,000	- 1
Schedule Costs	\$800,000	\$700,000
Cost/Bedroom	\$450,393	\$333,243
Total	\$80,170,100	\$44,987,885

Estimates made using timberx.ca & the Canadian Wood Council (CWC) Carbon Calculator

At a glance, these apartments are far from affordability, thankfully there are less tangible benefits that serve to offset that cost. It is also possible that the benefits of mass production exceed expectations and lower costs further. This building has a first floor entirely dominated by communal spaces. It serves to create a place for people in both home and leisure. Regardless of costs, the value of this structure is in creating community and showcasing modular mass timber within the region.

Embodied Carbon

Base Case	Concrete		Mass Timber	
	Embodied	Total	Embodied	Total
	6.69	1,355,864	2.69	546,112

Timberline	Concrete		Mass Timber		
	Embodied	Total	Embodied	Total	
	6.69	580,346	3.81	330,559	

Put simply, wood is good. It's a wondrous material that acts as a form of carbon sequestration. While a design with an excessive amount of wood products does have a greater amount of embodied carbon, it also represents a large amount of carbon removed from the atmosphere. This building contains 33,085 cubic feet of wood of various types. According to The CWC this equates to 817 metric tons of carbon stored within the wood. If harvested sustainably, wood is an excellent means of storing carbon, and can more than offset the concrete use required in a space like this.





System_Eco(n) is conceived as a tree-to-tower process-based solution to affordable tall timber apartments. Leveraging modularity to accelerate construction timelines and unlock economies of scale with the use of public funds and industry innovation. The tower is fully modular, each mass-timber volumetric unit is sized to fit standard North American semi-truck trailers, allowing rapid factory production and on-site assembly. A highly efficient typical floor plate is designed around those exact dimensions with the human experience remaining the primary design driver. The result is spacious, corner-focused family homes flooded with daylight to compliment the natural warmth of the exposed wood interiors. To address a key issue of high-rise wood construction, lateral stability is achieved through a robust concrete core supplemented by perimeter bracing in the form of the project's signature corner trusses. It is estimated that this combination of lateral bracing will be sufficient to allow for optimizations of the interior mass timber elements, in particular it is proposed that nail-laminated timber (NLT) can be strategically specified in low-risk areas to lower barriers to entry for fabricators and harness regional wood expertise. As a provocation to The City of Vancouver, the design proposes unlocking density bonuses and eliminating parking minimums in exchange for sustainable and affordable family-oriented units.

This project is gratefully situated on the shared and unceded territories of the Musqueam, Squamish, and Tsleil-Waututh Nations


FOREST TO FACTORY


Current political momentum to invest in home manufacturing processes should be leveraged towards establishing capacity building assembly lines, both human and automated, for producing a high volume of mass customizable timber living modules.

LOADING ASSEMBLY PANELIZATION SORTING CUTTING

Kickstarting supply for low carbon buildings will generate the technical capabilities, skilled manpower, facilities, and equipment needed to manufacture mass timber panels and assemble them in truck sized modules at scale.

SHIPPED TO SITE





To overcome the evergrowing burden of urban land costs and other economic hurdles that drive home prices higher and higher, this proposal calls on the city to unlock density in transit oriented neighbourhoods in exchange for tangible commitments from developers to provide affordable and sustainable family units. Site A's prominent corner in Vancouver's Tier 1 Transit-Oriented Area is a prime location for the city to commit to climate and housing goals, allowing people more options to live a walkable, car-free lifestyle, increasing transit ridership and ultimately generating a virtuous cycle of smart urban intensification and improvement.


ECONOMIC MINIMUM

164,700 sf (FSI 9.0)


CHALLENGING DENSITY CAPS

The proposal is a 42 Storey tower which is determined to be the maximum feasible height for this construction system with current testing data globally. It would also be feasible at 29 ST or 17 but the additional density is where the efficiency is found. Well in excess of the zoning envelope for this site but arguably necessary for TOA Tier 1 areas.

REGULATORY MAXIMUM 91,500 sf (FSI 5.0)



ECONOMIC OPTIMUM 237,900 sf (FSI 13.0) +



Below the "Economic Minimum" public subsidy is increasingly necessary for timber to compete with concrete



ACCESS TO DAYLIGHT




ACCESS TO OUTDOORS



EFFICIENT LAYOUTS



The proposal pushes against Vancouver's maximum tower floor plate slightly while respecting that building widths and separations need to be sensitively balanced with the rights of neighbouring sites to daylight and privacy. The unit count also pushes gently on industry norms for elevator counts at slightly more than 100 units per car, a standard which is being challenged increasingly in markets with the worst affordability crises. Ample closet space is provided in every unit but this proposal suggests that storage rooms are better situated below grade where costs per square foot are more reasonable. In fact, this proposal calls for the entirety of the below grade levels to be devoted to storage of more than just personal motor vehicles, parking minimums must also be challenged



The units are based on a modular grid determined by the dimensions of a typical shipping tractor trailer. However, the design of the unit layouts goes beyond this utilitarian starting point with a focus on the occupants that will live in them.

Five key drivers were used to guide the layout exercise in order to keep the human experience centered throughout the process, these were the objectives chosen to balance the needs of the users with the economical and ecological optimization of the project.

FAMILY ORIENTED UNITS

The unit mix is adapted from the developer driven status quo that skews towards small average unit sizes and a predominance of studios and one bedrooms catering to investor demand. Instead, it is proposed that more family sized units be provided to address the actual needs of end users in exchange for density bonuses and rebates from various levels of government.

ACCESS TO DAYLIGHT

Though interior bedrooms with indirect daylight are becoming increasingly common in contemporary apartment design this floor plate shows that even a building constrained by modular dimensions can secure real windows for all living spaces.

ACCESS TO OUTDOORS

The building is designed with generous wraparound balconies for all residential levels ensuring that all inhabitants can step outside for fresh air when needed. An outdoor amenity space is accessible to everyone on the podium roof.

EFFICIENT LAYOUTS

Each modular unit achieves all of these livability goals while being no bigger than necessary, each unit is equipped with standardized washrooms and kitchens to achieve economies of scale through repetition.

ROOM FOR LIVING

Levels 2 is devoted to indoor amenity

with access to the rooftop above the

Community Theatre. This space could

children's playground.

also be made accessible for community activities such as a shared garden or

Every unit, the family units in particular, are provided with adequate space for living room seating and a full dining table, full size closets in all bedrooms and foyers as well as flexible spaces for desk work or hobbies.

GROUND FLOOR PLAN

IVPICAL TOWER FLOOR PLATE

STRUCTURAL CONCEPT: S Α C FOUR MODULAR Κ MIDRISE BUILDINGS Ε D

SUPPORTING MODULAR TALL TIMBER

A ROBUST CONCRETE CORE PROVIDES A SOLID BACKBONE FOR THE WOOD FRAME, IT IS A KEY COMPONENT OF THE LATERAL LOAD RESISTING SYSTEM WHILE PROVIDING A HIGHLY STABLE VERTICAL ALIGNMENT FOR ALL MEP AND CIRCULATION SHAFTS

TO OVERCOME THE HEIGHT LIMITATIONS OF MODULAR WOOD CONSTRUCTION A TRANSFER LEVEL IS PROPOSED AT APPROXIMATELY EVERY TENTH FLOOR BRIDGINF FROM THE MEGAFRAME TO THE CORE, THUS ISOLATING THE COMPARTMENT OF MODULES ABOVE FROM THOSE BELOW AND AVOIDING CONCERNS OF COMPOUNDING DRIFT WHILE SIMULTANEOUSLY LINKING THE CORE AND PERIMETER TO ACT AS A COHESIVE SYSTEM

EACH LEVEL OF MODULES IS SIMULTANEOUSLY SUPPORTED BY THE PLATFORM BELOW AND SUSPENDED WITH TENSION MEMBERS FROM THE PLATFORM ABOVE IN A BELT AND SUSPENDERS APPROACH TO INTRODUCE REDUNDANCY AND RESILIENCY TO THE SYSTEM

A THICK CONCRETE TRANSFER SLAB PROVIDES A SOLID AND STABLE BASE FOR THE STACKED ELEMENTS ABOVE, AN INDEPENDENT STRUCTURAL GRID CAN BE EMPLOYED FOR THE MINIMAL PARKING, STORAGE AND SERVICE REQUIREMENTS **BELOW GRADE**

A PROTECTED EXTERNAL MEGAFRAME OF PERIMETER BRACING EXPANDS THE SECTIONAL DEPTH OF THE FLOOR PLATE TO ELIMINATE THE NEED FOR INTERIOR SHEAR WALLS THAT ARE INCOMPATIBLE WITH THE MODULAR CONTRUCTION METHOD

> RIGID VOLUMETRIC MODULES HELD BY THE FRAME ARE REINFORCED WITH STEEL CONNECTORS INTERNALLY AND FROM ONE MODULE TO THE NEXT TO ENSURE PRECISE ALIGNMENT AND AVOID UNWANTED DEFORMATION

EFFICIENT TRUSS FORMS TRANSFER AND DISTRIBUTE LOADS, MINIMIZING MATERIAL USE BY ALIGNING LIGHTWEIGHT LINEAR ELEMENTS WITH THE LOAD VECTORS WHERE THEY ARE MOST EFFECTIVE

LONG SPAN WOOD BEAMS ABOVE THE DOUBLE HEIGHT GROUND FLOOR LEVEL TO ACCOMODATE A PERFORMANCE SPACE IN THE COMMUNITY COMPONENT OF THE PROGRAM, PLACED OUTSIDE OF THE TOWER FOOTPRINT TO AVOID POINT LOADS ON THE LONG SPANNING ELEMENTS

International case studies and parametric analysis tools like Alpaca4D for Grasshopper provide ever increasing confidence that a timber structure could safely reach 150 m (140m proposed), but careful simulation of this specific system would need to continue as the project develops.

The real barrier to tall timber construction is the cost premium relative to concrete which exploits economic externalities (untaxed emissions) that cost society more than a timber subsidy would.


MODULAR CONCRETE

MODULAR WOOD

17,760 m3 of CONCRETE 5.700m3 of CONCRETE

12.455m3 of WOOD

TOTAL CARBON REDUCTION = 15,273 Tons of CO,



A MULTIPRONGED SOLUTION




A SPACE EFFICIENT SCISSOR STAIR ALLOWS FOR TWO EXITS FROM ALL LEVELS WITH NO DEAD-END CORRIDORS, THE LENGTH OF THE STAIRS AND A THREE BAY ELEVATOR GIVES THE KEY DIMENSION THAT THE MODULES ARE DESIGNED AROUND

MECHANICAL, ELECTRICAL AND PLUMBIN EQUIPMENT CAN BE PREINSTALLED IN THE FACTORY TO SAVE TIME ON SITE, ALIGNMENT BETWEEN MODULES IS ACCOMODATED THROUGH MANUFACTURING PRECISION AND FLEXIBLE CONNECTORS AT JOINTS

LOW-COST WINDOW WALL AND HIGH-EFFICIENCY INSULATED PANEL CLADDING IS INSTALLED IN-SITU TO ALLOW CONTINUITY IN THE ENVELOPE LAYERS ACROSS MODULES AND TO MAXIMIZE THE SIZE OF EACH MODULE WITHIN SHIPPING CONSTRAINTS

CANTILEVERED BALCONIES
ARE AVOIDED THROUGH SUPPORT
FROM THE PREIMETER FRAME,
REDUCING BENDING MOMENTS
AND THERMAL BRIDGING, WOOD
BALCONIES ARE PROTECTED BY A
WATER-RESISTANT MEMBRANE
AND FLASHING THAT TIES INTO
THE WALL ASSEMBLY





Base Case Cost Comparison

		CONCRE	TE		TIMBER	
	Square footage	\$/sq ft	Cost	\$/sq ft	Cost	\$/UNIT
17 ST BASE CASE	202,700	\$373.07	\$75,622,000	\$395.51	\$80,170,000	\$932,210
42 ST PROPOSAL	329,073	\$406.15	\$133,655,000	\$529.39	\$174,207,000	\$558,357
						Savings: \$374 000 / Unit

Savings: \$374,000 / Unit

Given the scale and complexity of this proposal a cost per square foot premium of 20% has been built into the proforma. Performing a sensitivity analysis on the estimate shows that even if the system entails a 100% cost premium compared to the 17 storey Base Case (\$862/ft²) the cost savings would still be approximately 1.5%, or \$14,000 per unit. The key to feasibility here is volume of product in a single project resulting in massive economies of scale, while costs may be double in the end compared to the base case, the number of units achieved is increased by a factor of 3.5 resulting in a 75% higher return on investment if costs are kept under control, before even factoring in the benefits of expediting construction through modular prefabrication.

These savings are only possible if density bonuses are approved by the city with the condition that units provided are sustainable, affordable and family oriented, these targeted conditions are essential, it is important to note that blanket approvals of increased density in TOA Tiers will result in tall concrete buildings and erase the affordability gains because land value/costs will increase proportionally. Conditional approvals will allow land values to remain low and will instead tilt the economic advantage from mid-rise concrete buildings to high-rise wood buildings, an outcome that will significantly contribute to social and cultural goals.

Material Analysis & Embodied Carbon Results

Volume of wood products used (m³): 12,455 m³ (439,842 ft³)

U.S. + Canadian forests grow this in: 34 minutes

Carbon stored in the wood: **11,012** metric tons of CO₂

Avoided greenhouse gas emissions: **4,261** metric tons of CO₂


Total potential carbon benefit: **15,273** metric tons of CO₂

Equivalent of: 3,229 cars removed for a year


1,613 homes powered for a year

System_Eco(n) strives to be reminiscent of the forests that once blanketed this beautiful landscape and the trees from which the building is made. Both the green patina cladding and the branching triangular frames were composed with the form of a mighty douglas fir as inspiration. One could imagine a forest of dendritic towers regreening the skyline around this transit node, honouring the natural world that birthed this city and beginning to tread lighter on the world with efficient timber structures that reduce waste, purify the air, and nourish the soil, all while providing homes for people that are not just places to live but places where people love to live.







The **Timber Commons** leverages an innovative, low-carbon construction system to deliver affordable housing with efficiency and adaptability. On Site A, the design responds to its context by maximizing density and eliminating parking, creating a visible timber landmark that capitalizes on transit access and the walkable fabric to reduce car reliance. Within, community is fostered through a hierarchy of shared spaces and services. Practical functions like laundry are paired with areas for gathering, play, and performance, cultivating a true vertical village. Built from a flexible kit of prefabricated mass timber components, every decision was guided by three objectives — **affordability**, **sustainability**, and **community**. The result is both a site-specific solution and a replicable framework that confronts the affordable housing and climate crises with a unified approach.



2



TIMBER COMMONS



COST & SCHEDULE REDUCTIONS — Our approach combines mass timber elements such as prefabrication slab cassettes, factory-built modular wet spaces, and prefabricated exterior wall panels to reduce costs, shorten schedules, and increase construction certainty in comparison to concrete construction. By shifting critical work into controlled factory environments, we minimize risks tied to site conditions, improve quality, and allow parallel workflows. Mass timber's lighter weight reduces the need for concrete and rebar in foundations and footings, yielding roughly 5% savings below grade and another 5% from the first floor upward. Overall, we predict our strategy could achieve up to a **5% global cost reduction** and a **10% schedule saving**, due to the quality control and efficiencies in prefabrication.

EMBODIED CARBON REDUCTIONS — On average, mass timber provides a 30% reduction on embodied carbon in comparison to concrete. We project that the introduction of prefabricated and modular units could reduce the Embodied Carbon by an additional 5% (**35% total** over concrete) due to reduced waste on site and shipping logistics efficiencies.

STATS		
FSR	4.90	
Lot size (sq ft)	18,300	
Building sq ft Above Grade	89582	
Building efficiency (%)	85	
non saleable/rentable (sq ft)	13437.3	
saleable/rentable (sq ft)	76144.7	
Total Stories above grade (#)	16	
Total Stories (#)	16	
Base floor (#)	1	
Above 1st storey (#)	#) 15	
Stories below grade (#)	0	
Units (#)	86	
Bedrooms (#)	138	
Amenity space (sq ft)	7,340	
Non-residential (sq ft)	9,348	

CONSTRUCTION COSTS						
		Concrete		Submission		
	Sq ft	\$/sq ft	Cost	\$/sq ft	Cost	
Below grade	0	\$315	\$0	\$315	\$0	
Base floor	10,187	\$360	\$3,667,320	\$362	\$3,687,694	
Above 1st storey	79,395	\$405	\$32,154,975	\$384	\$30,487,680	
	Quantity	\$/unit		\$/unit		
Balconies	0	\$25,000	\$0	\$25,000	\$0	
	Cost per	# Months	Cost	# Months	Cost	
Schedule Costs	\$50,000	16	\$800,000	12	\$600,000	
TOTAL			\$36,622,295		\$34,775,374	
EMBODIED CARBON						
		Concrete		Submission		
	Sq ft	E. Carbon kg/sq ft	Total Carbon	E. Carbon kg/sq ft	Total Carbon	
Total Building Sq ft	89582	6.69	599215.79	4.37	391473.34	











SPLAYED


TERRACED MIDRISE




While we have opted for a point tower as a response to this project's site constraints, the modular system allows for assembly in varied typologies. Using the same cost- and time-effective kit of parts and sequencing, we can create radically different results that respond to context and need.

HOUSING TYPOLOGIES

TIMBER COMMONS 3



TYPICAL FLOOR PLAN 1










TYPICAL FLOOR PLAN 2

Using the **standard grid module** of 3.05m by 7.6m, we designed 1-, 2-, and 3-bedroom units that assemble into complete floor plates in varied configurations. **Mass timber elements remain exposed**, providing the biophilic warmth of natural wood. Kitchen/washroom modules align with service cores, opening the perimeter to light and air in all living and bedroom spaces. Each home incorporates a Juliet balcony, while private balconies are deliberately omitted. Instead, **exterior space is consolidated into shared terraces**, fostering social connection and ensuring equitable access to outdoor amenity for all residents.




TYPICAL 1-BEDROOM UNIT 530 sq. ft.



TYPICAL 2-BEDROOM UNIT 785 sq. ft.




TYPICAL 3-BEDROOM UNIT 990 sq. ft.




PRIVATE LIVING

TIMBER COMMONS




DISTRIBUTION

Alternative 1



COMMUNAL SPACES
DISTRIBUTION
Alternative 2

Generous communal spaces are the heart of the **Timber Commons**. Using the same modular grid, the system supports both interior and exterior gathering areas that can be arranged in many configurations. In this design, **amenities are distributed** vertically in six zones, each pairing interior and exterior functions. These zones combine pragmatic uses, such as laundry, with spaces dedicated to socializing, recreation, and play. Together, they create a true vertical village, offering variety from floor to floor and encouraging frequent, casual encounters between neighbors. The richness of these shared environments allows unit floorplans to be efficiently compressed and private balconies to be eliminated, helping reduce per-unit costs. From the outside, these common spaces are expressed as luminous openings within the otherwise ordered grid of the façade, celebrating the social life at the core of the project.



OUTDOOR AMENITY

OUTDOOR AMENITY





COMMUNAL SPACES DISTRIBUTION

COMMUNAL SPACE OPTIONS



BARBECUE & KITCHEN

A communal indoor and outdoor space with a kitchenette, grills, and tables. Neighbors can cook, share meals, and build connections through food in this shared cooking and dining space.



DOG WASH & HOTDESK

A pet-friendly hub combining a dog wash station and flexible hotdesks, supporting pet and pet-owner needs while offering residents a place to work or rest.



PARTY & GAME ROOM

A playful gathering space with tables, various games, and a bathroom. A lively shared space for celebrations, casual fun, and bonding with friends and neighbours alike.



LAUNDRY & WORK STATIONS

A functional laundry space paired with working stations, allowing residents to read, study, or work productively while waiting for their laundry cycle to complete.



LAUNDRY & TABLE TENNIS

A social space where laundry meets leisure, encouraging neighbourly interaction and fun as residents complete their everyday household chores.

COMMUNAL LIVING





While the modular system establishes a **replicable framework** adaptable to many sites, it is equally important that it allow **bespoke responses to each context**. At **Site A**, this meant shaping a tall urban form tight to the prominent corner, creating **a density-appropriate landmark** visible from multiple view corridors while clearing a sheltered area for ground-level connection. Along the north and west edges, **stepped performance terraces** and an **elevated gathering space** animate the public realm while concealing servicing and bike parking. The roof restores green space otherwise lost to the footprint, providing allotment gardens and terraces for residents. **Cladding** becomes another site-specific gesture: a **prefabricated wood system** that celebrates BC's timber industry, reduces embodied carbon, and weathers gracefully into a silvered patina. Though fire-treated to European precedent standards, this system would currently challenge BC's building code, positioning the project as both **a model and a provocation for regulatory evolution**.




SITE-SPECIFIC FEATURES

Design competition ECODING TIMBER TOWERS

The New-wood Roots

"The design fosters social connection..."



The varied configurations of modular blocks combined with random arrangement of panels create a dynamic and visually compelling façade that transcends mere structure to become a vibrant expression of the community's diversity and layered history. This interplay of forms and patterns evokes a sense of movement and vitality, much like the flow of cultural narratives. Architecturally, this approach breaks away from monotonous uniformity, embracing complexity. Artistically, the mosaic-like composition invites viewers to read the building as a embodiment of community spirit, resilience, and the beautiful coexistence of difference.

The block-based design approach embodies a harmonious balance between simplicity and versatility—streamlining building science fabrication processes while unlocking a rich diversity of architectural expression. Each modular block acts as a fundamental building unit, crafted with precision to ensure structural efficiency, fire rating, and ease of assembly. The result is a dynamic interplay of shadow, texture, and volume transforming functional simplicity into a canvas for diverse spatial experiences and aesthetic narratives conforming to the needs of the community.

"... Simplicity and Versatility"

finelinedesigners

The penthouse units elevate living standards, featuring generous spatial balconies that extend the indoor experience outward. The upper residential levels are designed with flexibility in mind,


The upper residential levels are designed with flexibility in mind, offering a diverse range of unit types to accommodate varying lifestyles—from compact studio units for individuals to expansive multilevel family residences.

The third floor is designed as a mixed-use level, combining residential units with dedicated open space exclusively for residents. This floor integrates semi-private recreational areas—such as landscaped terraces, seating zones, or communal lounges

The first two floors of the building are dedicated to commercial and retail functions, strategically programmed to serve both residents and the surrounding community.

The basement level serves a dual function, acting as both the structural foundation of the building and a strategically integrated parking facility. The concrete basement is connected to a structural shaft housing all services and elevators.

"Floor plans that respond to evolving residential needs."



Building Zoning

finelinedesigners



The top levels of a building incorporating a *terrace effect* or *stepped massing* create visual and functional articulation in the overall form. This design approach allows for a diversified unit typology, enabling the integration of *private terraces*, *green roofs*, *balconies*, and *multi-level penthouse units*. Such stepped configurations break down the building's scale, enhancing urban form while maximizing access to natural light, ventilation, and outdoor living spaces. Additionally, this strategy increases the desirability of upper-level units by offering expanded spatial experiences, thereby enhancing both the livability and market value.

"a diversified unit typology ... enhancing both the livability and market value."

The third level functions as a semi-private communal terrace or podium deck, designed to foster social interaction and a sense of community among residents. This elevated common area offers shared amenities such as gardens, seating, or recreational spaces, promoting commonality and a secure environment, physically separated from public access. Strategically located above ground level, it enhances safety, privacy, and visual openness —strategically positioned to encourage social interaction and foster a sense of community among occupants. Additionally, the building's form creates a wind tunnel effect—an aerodynamic phenomenon that can be harnessed for sustainable energy.

"... encourage social interaction and foster a sense of community among occupants."

Ground-level pathways and sidewalks encroaches beneath a building's footprint. These transitional spaces serve as semi-covered pedestrian routes, blending exterior and interior zones. By encroaching under the structure, these elements offer shelter, visual interest, and a welcoming approach, enhancing the human scale of the architecture. These podium-level spaces are designed with flexibility and permeability, accommodating a mix of daily-use services—such as grocery, pharmacy, and convenience retail—alongside specialty shops that reflect the cultural and economic diversity of the neighborhood.


"...designed with flexibility..., accommodating a mix of daily-use services..."

COST BASE CASE ANALYSIS	BASE CASE	THE NEW-WOOD ROOTS
FSR	5.00	6.7
Lot size (sq ft)	25,540.00	18299.0
Building sq ft Above Grade	127,700.00	122708.7
Building efficiency (%)	85.00	85.0
non saleable/rentable (sq ft)	19,155.00	18406.3
saleable/rentable (sq ft)	108,545.00	104302.4
Total Stories above grade (#)	18.00	13.0
Total Stories (#)	21.00	16.0
Base floor (#)	1.00	1.0
Above 1st storey (#)	17.00	12.0
Stories below grade (#)	3.00	3.0
Units (#)	86.00	95.0
Bedrooms (#)	178.00	193.0
Amenity space (sq ft)	850.00	1500.0
Non-residential (sq ft)	3,000.00	18298.6

D	COST BASE CASE ANALYSIS	AREA	CON	CRETE	MASS	TIMBER
_	Description	Square footage	\$/sq ft	Cost	\$/sq ft	Cost
.71	Below grade	75000.0	\$315	\$23,625,000	\$299	\$22,425,000
.00	Base floor	8700.0	\$360	\$3,132,000	\$403	\$3,506,100
.74	Above 1st storey	119000.0	\$385	\$45,815,000	\$431	\$51,289,000
.00		Quantity	\$/unit		\$/unit	
.31	Balconies	86	\$25,000	\$2,150,000	\$25,000	\$2,150,000
		Cost per month	# Months		#	
.43	(Overhead/Construction	\$50,000	18	\$900,000	16	\$800,000
.00	TOTAL			\$75,622,000		\$80,170,100
.00						

000,	Above 1st storey	115174.0	\$385	\$44,341,990	\$433.00	\$49,870,342
		Quantity	\$/unit		\$/unit	
000,0	Balconies	0	\$25,000	\$0	\$25,000	\$0
		Cost per month	# Months	Cost	# Months	Cost
,000	(Monthly	\$50,000	18	\$900,000	16	\$800,000
,100	TOTAL			\$64,891,038		\$70,635,849
,100	TOTAL			\$64,891,038		\$70,635,849
MICO	TOTAL	E	MBODIED (\$70,635,849
ALL	TOTAL	E Area				\$70,635,849

SAMPLE UNIT TYPES











2-BLOCK UNIT: STUDIO or 1 BEDROOM UNIT



"...supporting evolving community dynamics and promoting longterm sustainability."



4-BLOCK UNIT: 2 BEDROOM

UNIT


6-BLOCK UNIT: **3 BEDROOM UNIT**



8-BLOCK UNIT: 4-5 BEDROOM UNIT -LOFT TYPE











Their inherent modularity supports a 'kit-of-parts' approach, enabling designers to compose complex structures through simple, repeatable units. This mix-and-match capability allows the architecture to respond fluidly to different site conditions, programmatic needs, or aesthetic intentions, without compromising structural integrity.



...enabling designers to compose complex structures through simple, repeatable units.



The modular design approach elegantly addresses the logistical challenges of transporting raw materials, both to the fabrication facility and ultimately to the construction site. Each component is meticulously designed with transportability in mind, streamlining the journey from origin to assembly. Engineered timber elements, such as glulam (glued-laminated timber), are dimensioned with precision—not only for structural integrity but also to ensure ease of handling during transit and assembly. These glulam beams are sized to fit standard transportation vehicles, 2-hour fire rating, stackable, and practical deployment on site. To optimize the strength of glulam, joints are fabricated single pieces. Joints of pieces are structurally calculated along areas where stress is less and easier to connect which along straight components.

"Design supports not only logistical efficiency but also regional economic resilience."


TYPICAL EXTERIOR WALLS

The wall systems are envisioned as a series of pre-insulated, pre-assembled panels—highly adaptable components that respond thoughtfully to the typical structural rhythm and dimensions of the building. Each panel is conceived as capable of being tailored in material, finish, and detailing to suit diverse architectural expressions and environmental conditions. Their geometry and construction are intentionally kept within a standardized framework, allowing ease of replication without compromising functionality.

This strategic simplicity opens the doors to local and small-scale fabricators, who can engage in the production of these panels without the need for highly specialized machinery or large facilities. Design supports not only logistical efficiency but also regional economic resilience.

This localization not only minimizes carbon emissions but also gives option of affordability of the construction. This design choice strategically addresses market vulnerability by decentralizing production: small and mid-sized workshops can fabricate the panels using accessible tools and conventional techniques

"...addresses market vulnerability by decentralizing production:"



fine **line** designers

The customizable nature of the design allows it to fluidly adapt to evolving building codes, zoning requirements, and sustainability standards—ensuring long-term relevance and regulatory compliance without the need for major structural overhauls. This inherent flexibility is not only a technical advantage but a future-forward design principle, making the architecture resilient in the face of shifting environmental policies and construction norms.

At the heart of the system is timber which acts as both a primary structural element and a climate-conscious material choice. Timber's ability to sequester carbon makes it a critical tool in the push for low-impact construction, effectively resulting in a negative carbon footprint when sourced and managed responsibly. As global building codes increasingly prioritize sustainability, emissions reduction, and renewable materials, this approach positions the structure at the forefront of progressive architectural practice.

By harmonizing modular flexibility with ecological responsibility, the design doesn't just meet standards—it anticipates them. It stands as a living framework that evolves with its context, all while embodying the warmth, authenticity, and regenerative potential of wood.

finelinedesigners



The project site is within the unceded, ancestral, and traditional territories of the xmnəθkmy'əm (Musqueam), Skwx wu7mesh (Squamish), and səlilwəta?t (Tsleil-Waututh) peoples.

Ancient forests once covered this land which was shared by Indigenous peoples, salmon, black bear, and the Pacific tree frog. The frog is a powerful cultural symbol to Indigenous groups in British Columbia. They are believed to cleanse spaces and spirits through their recognizable croak and projecting tongue.

In accordance with this belief, an Indigenous housing provider, the *Frog Hollow Neighbourhood House*, will develop 80 units of affordable housing for the community. The proposed tower is to be constructed of locally sourced timber and to be known as the *Tree Frog Tower*.



SITE

Site A is a consolidated 1700 sq m (18 300 sf) south-facing corner lot. It is located within Tier 1 of a Transit-Oriented Development Area with rapid transit and a bus exchange within a five minute walk. Shops, services, and extensive green space are all nearby in this historic neighbourhood.

URBAN DESIGN

The adjacent local street will be closed to traffic and converted into a pedestrian mall with an arcade (covered walkway). The mall will link the existing transit hub to a new urban plaza paved with wooden 'bricks'. Directly below this plaza is a underground bicycle garage that will accommodate 800+ bicycles to encourage other modes of transportation.

These urban interventions are intended to re-invigorate the neighbourhood and foster a more vibrant street culture.

ARCADE

The two-storey timber arcade offers shelter from rain and sun and will run the entire length of the block. Along the northside of the plaza the arcade is attached to the tower. It extends beyond the property line blending the public realm with private spaces.

The arcade's design is inspired by the wood rail trestles constructed in British Columbia and used to transport timber in the previous century. Borrowing from the Howe Truss structure, a glulam framework of diagonal and vertical members wraps around the tower perimeter.

- loading bay
- electric vehicle car share
- garbage/recycling
- garden
- commercial/retail unit
- mechanical/electrical/utilities
- residential lobby
- dumbwaiters
- community kitchen
- 10 residential entry 11 public elevator
- 12 take-out window
- 13 house post
- 14 arcade
- 15 arcaded pedestrian mall
- 16 wooden 'brick' plaza 17 lily pond
- 18 bicycle garage entry and ramp
- 19 bioswale
- 20 underground bicycle garage



PROGRAMME

The proposed 12 storey timber tower is anchored by a community kitchen and take-out window at the ground floor. Entrance to the tower residences is through the arcade. Smaller scaled retail spaces intended to encourage more local shops and businesses are also found at grade.

The second storey social centre shares outdoor space with a public picnic shelter with views to the plaza.

Levels 3 -12 provide 80 units of housing and a private rooftop amenity space.

SOCIAL CENTRE


The social centre at second floor is to be operated by the *Frog Hollow Neighbourhood House*. This semi-private space is intended to encourage social interaction between building residents, family, friends, and the larger community.

The centerpiece of the social centre is the grand dining hall which is designed for hosting feasts, banquets, and other special occasions focused on sharing a meal. Dumbwaiters and interior stairs connect the second floor servery with the ground floor community kitchen. Tables and chairs can be stored away so that the large gathering space can also function as a theatre or performance space.


Lounge areas, bar, gallery, and multi purpose rooms support the dining hall. The east multi purpose room with its small enclosed outdoor patio is scheduled to double as a daycare.

The social centre is accessed by shared stairs or a public elevator. The adjacent picnic shelter also functions as spill-out space for the dining hall. Tower residents have direct entry to the social centre by private elevators with restricted access.









- 1 multi purpose room
- 2 gallery
- 3 dumbwaite
- 4 servery 5 dining hall
- 6 bar
- 7 lounge 8 entrance
- 9 public elevator
- 10 picnic shelter
- 11 retail mezzanine

TIMBER TOWER DESIGN

The asymmetrical typical floor plan accommodates 8 studio, one bedroom, two bedroom, and three bedroom units per floor. The wider than average corridor is welcoming and provides ample space for wheelchairs and other mobility devices.

The unit layouts are designed to be adaptable offering occupants greater comfort and accessibility. A knock-out panel at the party walls between the studio and north-facing two and three bedroom units enables opportunities for multi generational living and other options. Suspended balconies provide access to private outdoor spaces.


A rootop outdoor amenity space provides respite for residents. Planter boxes, a children's playground, and a barbecue area are proposed. Circular openings in the rooftop enclosure provide framed views to the mountains, river, and city beyond.

Due to the close proximity of the transit hub no underground parking is provided on site. An EV car share program located at the lane is proposed. As well, there is easy access to the underground bicycle garage.

PROJECT STATISTICS

FSR	5
Lot size (sq ft)	18 300
Building sq ft Above Grade	91 500
Building efficiency (%)	83
non saleable/rentable (sq ft)	87 295
saleable/rentable (sq ft)	4 205
Total Stories above grade (#)	12
Total Stories (#)	12
Base floor (#)	1
Above 1st storey (#)	11
Stories below grade (#)	0
Units (#)	80
Bedrooms (#)	140
Amenity space (sq ft)	0
Non-residential (sq ft)	14854





- 1 studio
- 43 sq m (463 sf) 2 one bedroom
- 52 sq m (560 sf)
- 3 two bedroom
- 81 sq m (872 sf)
- 4 three bedroom 107 sq m (1 152 sf)

CONSTRUCTION

The proposed 12 storey timber tower emphasizes prefabrication to address housing unaffordability and climate change.

CLT Floor Panels

Prefabricated cross-laminated timber floor panels used in multi-storey applications are very cost effective. Standard panel width, length and thickness available in British
Columbia is proposed and determined the
extent of a typical floor. Combined with a
concrete topping for improved fire protection and acoustics the underside of the panels are left exposed for visual interest.

CLT Wall Panels

An elongated rectangular building core constructed of encapsulated CLT wall panels centers the structure. These shear wall assemblies capture the elevator and stair cores. Additional shear walls at demising and end wall locations run perpendicular to the building core.

CLT walls and floors at all common areas are covered with a non-combustible gypsum board to enhance fire resistance and address building code requirements. Non-load bearing interior walls are also to be constructed of CLT panels.

Glulam Posts and Beams

Between the encapsulated CLT walls, a network of exposed glulam posts and beams enables spacial flexibility. Located along a 3.3 m (11'-0") module east-west grid, the beams and columns with steel connections are stacked vertically down to the concrete foundation slab.

North and south-facing curtain walls are also constructed of prefabricated CLT panels. Deep punched windows are featured at end shear walls locations cladded in black green metal panels.

CONSTRUCTION COSTS

		Concrete		Submission	
	Square footage	\$/sqft	Cost	\$/sqft	Cost
Below grade	0.0	\$315	\$0	\$0	\$0
Base floor	9149.0	\$41	\$375,109	\$403	\$3,687,047
Above 1st storey	82351.0	\$13	\$1,070,563	\$431	\$35,493,281
	Quantity	\$/unit		\$/unit	
Balconies	120	\$0	\$0	\$25,000	\$3,000,000
	Cost per month	# Months	Cost	# Months	Cost
Schedule Costs					
(Monthly Overhead)	\$50,000	18	\$900,000	16	\$800,000
TOTAL			\$2.24E 672		£42 000 220

Note: concrete slab-on-grade including reinforcement and concrete topping are factored costs


- 1 CLT floor panels 10 EV car share parking
- CLT wall panels 11 garden
- 12 residential elevator lobby glulam post and beam
- structural grid system 13 retail space

picnic shelter


- 14 portico rooftop amenity typical studio unit 15 urban plaza
- social centre 17 bioswale
- typical one bedroom unit 16 underground bicycle garage

В В











2





PREFABRICATION

Prefabrication improves affordability. Faster construction times reduces costs while increasing environmental benefits. Improved quality control in a factory settings results in fewer errors and less waste. British Columbia's mass timber market offers a range of prefabricated wood products.

CLT panels for floors, roofs, interior, and exterior walls as well as glulam columns and beams.

The proposed suspended balconies are manufactured off-site. Their cost efficient and flexible design includes a CLT panel floor that is visible from below.


Modular options such as the family washroom pods are dropped into place between beams. Kitchen units and standardized plywood storage cabinets that replace fixed closet spaces are also manufactured off-site. Specialties such as the deep windows are customizable with tailored finishes.

- 1 suspended balcony
- 2 CLT wall (encapsulated)
- 3 family washroom pod
- 4 CLT exterior wall panel
- 5 CLT floor panel (with concrete topping)
- 6 window box
- 7 CLT interior wall panel
- 8 glulam post and beam
- 9 plywood storage cabinets

EMBODIED CARBON

		Concrete		Submission	
	Sq ft	Embodied Carbon kg/sq ft	Carbon		Total Carbon
Total Building Sq Footage	91500.0	6.69	612045.33	2.69	246135


The strategy to focus of prefabrication and ocally-sourced timber products aids in reducing embodied carbon. The potential re-use and recyclability of CLT walls and floor panels as well as glulam posts and beams furthers that goal.



A Timber Tower Wearing a Greenhouse Coat

Current timber towers strike a hard line between interior and exterior. In fact, it is often difficult to tell that a tower is made of mass timber from the outside. We propose a timber tower that wears a greenhouse coat. On one hand, this coat offers residents a third space between mechanically conditioned space and exterior unconditioned space: adaptable for different seasons and living configurations. On the other hand, this coat unveils the mass timber structure of the building while sheltering it from the elements. The result is a tower with a timber structure that can be *experienced and seen*. The tower becomes a billboard for a city reimagined and rebuilt through mass timber.

Location: Site A, TOA Tier 1 Total Stories: 12 Total SF: 89,303 sf FSR: 4.88






Systemization and Standardization: A Kit-of-Parts Design

Rather than a fixed design, the tower is a system of architectural parts that uses off-site factory fabrication to reduce cost, material waste, and construction time. Nearly all of the timber structure is made from a single repeated structural bay, sized for shipment on a flatbed truck. The facade of the building utilizes kit-of-parts greenhouse components that mirrors the structural grid. While highly standardized, the structure in the greenhouse is freed from fixed walls and offers maximum possibility of use.





Climate Change Mitigation and Adaptation: Reducing Embodied Carbon and Operational Carbon

The adoption of mass timber in tower construction is critical to mitigating climate change as the world's population continues to grow and urbanize. While mass timber construction aids by reducing embodied carbon, our proposal also reduces operational carbon by balancing active and passive conditioned living spaces. This approach can greatly reduce the energy consumption of the building over its lifespan. The addition of greenhouses as living spaces also allows residents to take advantage of British Columbia's mild year-round climate, adjusting their homes to differing comfort levels.



- Covered, semi-enclosed circulatio atrium with balconies for gathering. Enclosed and conditioned units.
- Unconditioned greenhouses living spaces.
- Folding and awning windows allow for individualized climate control.





Summer: Units can fully open for cross-ventilation, passively cooling each home.



Winter: Both conditioned spaces and greenhouses can be closed off separately, creating



Fall/Spring: Residents can open and close off spaces according to their desired comfort.






View inside a greenhouse living space, which reveals the mass timber structure while sheltering it from the elements.

Site Integration and Social Interaction: A Porous Tower Open to All Sides

Located in Site A and TOA Tier 1, our proposal fully embraces the proximity to transit and retail by merging with the life of the city at ground level. The tower meets the groundnot as a single mass, but as a series of smaller volumes that allow visitors, air, and light to flow in from all sides. Visitors can walk through the center of the building and see the soaring residential arrium and balconies overhead. The different orientations and positions of the volumes at ground level allow for multiple facades. Public-facing programs, including community meeting rooms, performance spaces, and a cafe meet the busy street intersection, while more intimate programs including a daycare faces the quieter alleyway and opens up to ample outdoor play area.







- A Spaces facing the busy street corner are programmed as community meeting rooms that can be combined into a larger performance space.
- **B** Operable facades allow for retail programs such as a cafe to spill out into the adjacent sidewalk and landscaped areas.
- **C** A covered outdoor arcade can be used for temporary gatherings such as a farmer's market.
- D The quieter, alley-facing side of the building provides a more sheltered space for a daycare that opens into ample outdoor play areas.

upper left: ground floor plan lower left: view into the daycare space upper right: view into the atrium lower right: view into the coffee shop




A semi-enclosed and covered atrium space replaces the dark interior hallways of the typical tower. Balconies cantilever off the hallways over the atrium creating additional shared living spaces that are naturally lit from above and from the open ends of the building.



The ground floor of the tower is porous and approachable from all sides. Visitors can walk through the center of the building without having to go inside.

Quality of Life: Flexible Units Surrounded by Light, Air, Greenery, and Timber

Each of the tower's units are surrounded by greenhouses that extend living space into the threshold between indoors and outdoors. Every single room can be opened up to a greenhouse space, creating a connection to the outdoors and bringing in light and air. Curtains, sliding doors, folding windows, and awning windows allow residents to adapt these spaces to their desired levels of comfort and privacy. The exposed timber structure of the greenhouses frames every view looking out from the interior to the exterior. While each unit is fully private, the greenhouse spaces create room for possible shared uses, and can be opened up or divided by residents as desired.





- **B** Each room opens up to a greenhouse space that can be used as private or shared living spaces.
- C Circulation space in the tower is oriented around a light-filled atrium, lined with cantilevered balconies that create additional flexible uses and amenity spaces for residents.

upper left: typical floor plan lower left: peripheral space diagram upper right: view into the bedroom lower right: view into the living room



Greenhouse used as separate balcony.

Greenhouse used as extension of living space.

Greenhouse used as shared gathering space.




 $The \ exposed \ timber \ structure \ of \ the \ greenhouses \ frames \ every \ view \ from \ an \ interior \ room \ looking \ outwards.$




While each unit is fully private, the greenhouse spaces create room for possible shared uses, and can be opened up or divided by residents as desired.

Impact: A Template for Diversifying Mass Timber Housing Typologies

As a modular structural system based on the standard shipping size of a CLT panel, our design can be adapted for sites across the city zoned for different residential densities. In addition to high-rise towers, our kit-of-parts approach can be used for other recently legalized typologies that can create huge impact, such as mid-rise single-stair buildings. Our proposal is a tool for aligning mass timber construction with recent zoning and building code reform allowing for denser and taller timber residential buildings.





High-rise single-bar type for narrow lots in high-density neighborhoods.

High-rise offset double-bar type for larger lots and combined lots in high-density neighborhoods.

above: replicability diagram left: view from southeast corner

Industry and Policy Recommendations

Maximize Off-Site Manufacturing

Mass timber is well-suited for offsite prefabrication, where panels, beams, and columns are manufactured in a controlled factory environment. Combined with a fully pre-fabricated facade, our proposal reduces on-site construction time, labor costs, and noise pollution, which is particularly beneficial for high-density urban infill projects. Optimize Project Timelines

By embracing prefabrication and modular construction techniques, developers can achieve a faster "speed to market," leading to quicker returns on investment. Our proposal further reduces project timelines by sizing CLT panels for optimized transport and maximizing repetitive construction elements.

Total Building SF kg/sq ft

2.69

97,403 sf

Showcase Mass Timber

Conduct testing and reform building code to allow more exposed mass timber in high rise towers. Educate the wider community on the benefits of mass timber buildings, such as the positive health impacts of biophilic design. This can help generate market demand. Our design celebrates the beauty of the mass timber structure from both inside and outside. Design with Adaptability

Produce standardized mass timber components with adaptable structures in mind. These structures should be suited both for a range of site conditions and zoning envelopes, as well as for different interior layouts and uses. Our proposal demonstrates how a standardized structural system can still create variation in implementation.

Proforma

Embodied Carbon

	Base Case	Our Proposal	Rationale
FSR	5	4.88	
Lot Size	25,540 sf	18,300 sf	
Building SF (Above Grade)	127,700 sf	89,303 sf	
Building Efficiency	85%	83%	Larger circulation spaces also double as flexible, shared living spaces in the building.
Total Stories (Above Grade)	18	12	
Total Units	86	66	
Total Bedrooms	178	110	The floorplan layouts can adapt to different unit mixes of 1, 2, and 3 bed units.
Amenity Space	850 sf	3,740 sf	Each floor has amenity spaces for residents.
Non-Residential Space	3,000 sf	6,672 sf	The entire ground floor is designated for retail and/or community use.
Building SF (Below Grade)	75,000 sf	8,100 sf	
Construction Costs	Base Case	Our Proposal	
Below Grade/Parking	\$22,425,000	\$2,421,900	Reduced parking to only one below grade level with accessible parking.
Base Floor	\$3,506,100	\$2,890,316	
Above 1st Storey	\$51,289,000	\$35,398,461	
Balconies	\$2,150,000	\$990,000	Balcony costs reduced since they are fully covered, and part of prefab structure.
Schedule Costs	\$800,000	\$700,000	Reduced construction schedule due to highly repetitive structure and prefab façade.
Total	\$80,170,100	\$42,400,677	

262,014

Total Embodied Carbon



Mass timber construction has become increasingly popular for being sustainable, fast to build, and aesthetically appealing. It also presents a unique opportunity to develop a holistic building system, streamlining project delivery from concept through to completion.

While this building typology continues to evolve, it remains vulnerable to regulatory challenges and market risks, resulting in cost premiums that are exempt from more traditional wood frame and concrete construction methodologies. To overcome these hurdles and maximize mass timber's potential, we are proposing a provincially mandated pre-fabrication corporation, partnering with public and private companies in delivering a regionally-focused mass timber strategy for improved design development, procurement, fabrication, and construction.

BC Prefab (BCPF) will benefit project stakeholders, designers, and contractors alike, providing design-assisted software, integrated online pricing, and pre-regulated fabrication facilities. Collectively, BCPF will help reduce risk and expedite timelines, opening up opportunities for increased economies of scale and wider diversity of building typologies.

We have identified the following six problems that BCPF provides solutions for to help us deliver Mass Timber for the masses!





INCONSISTENCY ACROSS INDUSTRY PROFESSIONALS

Mass timber is poorly understood by professionals, requiring specialized fabrication and construction



DEVELOP A TOOLKIT OF PRE-APPROVED COMPONENTS

Integrate design-for-assembly principles to meet code standards





LOGISTICAL CHALLENGES IN SHIPPING COMPONENTS

Although prefabrication offers speed, larger components are constrained by transportation limitations and crane capacities



USE BC TIMBER AND EXPAND PREFAB FACTORIES

Support local industry, reduce transportation-related complications, and optimize shipping and packing of components





PROTRACTED PERMITTING APPROVALS

Complex zoning, permitting, procurement, and construction processes add risk, cost, and delays



STANDARDIZE PRE-APPROVED BUILDING COMPONENTS

Streamline the design process and design approvals, allowing for accelerating permitting





INCONSISTENT APPROVAL STANDARDS

Mass timber and prefabrication face restrictive regulations not fit for the factory-based fabrication process



COMPONENT INSPECTION DURING FABRICATION PROCESS

Reduce construction time, improve quality control, and lower on-site





HIGH UPFRONT COSTS CREATE RISK

 Mass timber is subject to market vulnerability, and remains too expensive for wide adoption without standardized systems



PROVINCIALLY SUPPORTED INITIATIVE TO OFFSET RISKS

Incentivize public/private partnerships, allowing collaborations to work within a provincially standardized system





LIMITED DESIGN CREATIVITY AND ADAPTABILITY

Restrictive fabrication opportunities lead to overly uniform buildings limiting design flexibility and site compatibility



EMBED ADAPTABILITY WITHIN BUILDING SYSTEMS

Establish a building system to accommodate varied unit types, building forms, and ever-changing rough policies

DTT-A-10

THE STEPS



1 PROJECT SETUP

Design team accesses the BC-PREFAB website to download the plug-in software



2 CONCEPTUAL DESIGN

Utilize the software to help establish the base building structure within the site parameters



3 DESIGN DEVELOPMENT

Refine and reinforce the design identity through customized detailing and component integration



PRICING / TENDER

As the design evolves, a real-time pricing summary is generated on the website, providing convenient reference for clients and contractors



5 FABRICATION + TRANSPORTATION

Fabrication of components and transportation logistics are managed by the company to ensure safe and timely deliveries



6 CONSTRUCTION


On site, components are installed with sequenced simplicity and efficiency




ADAPTIVE REUSE

Once built, the modular, stacked design enables buildings to adapt and evolve with minimal disruption and without compromising structural integrity

STEP 1 + 2:







PROJECT SETUP

The BCPF+ Plugin is designed for seamless integration into standard architectural workflows using typical software, ensuring that systematized prefab logic can be incorporated without disrupting existing design practices.

The project begins with the typical setup: importing the site, setting property lines, levels, and laying out the foundation (optionally with parking levels). The plugin supports early-stage decisions by anchoring the structural grid to a standardized 12'x12' column spacing, optimized for prefabricated mass timber assemblies while maintaining 6' spacing for hallways. Core placement and structural framing are generated with prefab compatibility in mind, establishing a clear spatial and structural rhythm from the outset.

This structural grid allows for the building footprint to easily align with zoning guidelines, allowing for simple and efficient layouts within conventional site geometries. The volumetric form can be quickly manipulated in response to prescribed building setbacks, stepping, and maximum permitted building heights.

"We need to optimize our project proforma within the constraints of the existing site geometry. How quickly can we establish a structural grid layout to help determine our overall unit mix and yield?"






CONCEPTUAL DESIGN

With the concrete foundation and core elements placed, the BCPF+ plugin enables the creation of a massing model within the predefined structural grid. At this stage, the structural grid is an empty base for the tower layout, becoming the shell for future adaptive reuse purposes.

For this proposal, we have implemented a layout that focuses on maximizing unit efficiency as well as facilitating a community. The flexibility of the system allows us to customize the structural form to efficiently enable these programs. We can now assign spaces for units, amenities, and services while maintaining the fixed mass timber and concrete elements, with corridors serving as anchors

STEP 3a:





DESIGN DEVELOPMENT: UNIT PLACEMENT

Thanks to the standardized dimensions and prefabricated components within the BCPF+ plugin, unit layouts are pre-developed and automatically placed based on the selected module size, entry location, and window access. Each layout is pre-validated for compliance with the most up-to-date building codes, allowing for faster design coordination and streamlined approvals.

The system also adapts intelligently to constraints. For example, both a 3-bedroom unit and a 1-bedroom + den + lock-off suite occupy the same three-module footprint. However, if the module is positioned away from a corner, the 3-bedroom layout is excluded due to insufficient window frontage. The plug-in filters viable layouts based on orientation and access, reducing the risk of design conflicts later in the process.








DESIGN DEVELOPMENT: COMPONENTS

To save on cost and increase flexibility, components are broken down into smaller prefab parts and assembled on-site. The BCPF+ plugin functions as a within budget while optimizing design.



STEP 4:




PRICING / TENDER

After completing steps 1-3, a digital receipt is generated detailing all components, associated costs, availability from nearby BC Pre-Fab plants, delivery logistics, and recommended assembly sequencing. This package serves as both a permit-ready submittal and a construction-ready kit, streamlining the approval process and reducing uncertainty before fabrication begins.

This system enables contractors, consultants, clients, and other stakeholders to review and approve the project's proforma with transparency throughout the design process. It also facilitates easy reordering of components in the event of damage, future renovations, or building repurposing.


"The real-time cost calculator reduces pricing uncertainty, expedites tendering, and allows for a more proactive value engineering process."





FABRICATION + TRANSPORTATION

All timber materials are sourced from processing facilities across British Columbia to





ASSEMBLY + CONSTRUCTION

The concrete foundation and first floor are poured before the mass timber components arrive on site

Each component is designed for assembly workers to put together in a matter of minutes, while strategic sequencing and a comprehensive assembly checklist generated by the BCPF+ system ensures each piece is installed just-in-time.

Average assembly times for each floor cassette is 10 minutes; columns are 8 minutes; envelope panels are 22 minutes; and balconies are 2 hours. After approximately 30 days of structure and shell assembly, interior walls and pre-fab rooms are installed, bringing total assembly time to 150 days.



Components are packed strategically onto trucks to allow for the maximum parts transported while adhering to maximum dimensions. Delivery is planned so each set of parts arrives just in time to be assembled into each floor of the tower minimizing on site storage needed.



SUBMISSION PROFORMA FSR Lot size (sq ft) 18,300 **Building sq fr Above Grade** 91,500 Building efficiency (%) 85 non saleable/rentable (sq ft) 13,725 saleable/rentable (sq ft) 77,775 Total Stories above grade 14 Total Stories (#) 15 Base floor (#) 13 Above 1st storey (#) Stories below grade (#) 117 Units (#) Bedrooms (#) 179 5,016 Amenity space (sq ft) Non-residential (sq ft) 6,600

CONSTRUCTION COST

Total

		Concrete		Submission	
	Square	\$/sq ft	Cost	\$/sq ft	Cost
Below grade	18,300	\$315	\$5,764,500	\$299	\$5,471,700
Base floor	10,500	\$360	\$3,780,000	\$403	\$4,231,500
Above 1st storey	81,000	\$405	\$32,805,000	\$431	\$34,911,000
	Quantity	\$/unit		\$/Prefab Unit	
Balconies	100	\$25,000	\$2,500,000	\$15,000	\$1,500,000
Juliet Balconies	17	\$20,000	\$340,000	\$10,000	\$170,000
	Cost per	#Months	Cost	#Months	Cost
Schedule Costs	\$50,000	18	\$900,000	10	\$500,000

CARBON SUMMARY Produced by TimberX and WoodWorks calculator

\$46,218,700

		Concrete		Submission	
	Sq ft	Embodied	Total	Embodied	Total
Footage	109,800	6.69 kg/sq ft	734454	2.6 kg/sq ft	285480

Volume of wood products used: 96,355 ft³(2,728 m³)

U.S and Canadian forests grow this much wood in: 7 minutes

Carbon stored in the wood: 2453 metric tons

Greenhouse gas reductions: 949 metric tons

Total potential carbon benefit: 3403 metric tons

TIMELINE LEGEND

Conceptual Design Design Development

Fabrication + Transportation Construction

Pricing / Tender

The stacked structural grid allows for simple geometric building volumes that can be applied to a wide diversity of site configurations. The stacked floor plates mitigate the need for structural transfers and plumbing offsets.

The podium level adjoins the neighbouring side-yard property line, allowing for an appropriately scaled street wall transition. The west orientated podium roof presents an opportunity for common outdoor space with excellent solar exposure

Each building facade expression is uniquely defined by a composition of components that can be easily manipulated based on their contextual orientation, and interchanged for future adaptive re-use.

The community theatre and commercial edge activates the smaller scaled local street,

> The tower form anchors the site corner adjacent to the main street intersection, with the main building entry fronting onto the collector road for clear way-finding and convenient resident access.

> > 1 MONTH

12 MONTHS

12 MONTHS

10 MONTHS

3 Years COMPLETE!

BCPF TIMELINE

engagement.

promoting pedestrian interaction and public

6 MONTHS

24 MONTHS

2 MONTHS

24 MONTHS

4.6 Years

\$44,323,860


TRADITIONAL TIMELINE

'The pre-approved fabrication process pro-actively streamlines our

and approval^a

municipal occupancy review





HOUSE PRICES BROKE ABOVE THE CIMCH AFFORDABILITY THRESHOLD IN 1990, CONDOS FOLLOWED IN 2003. BY 2016 INDUSTRY INSIDERS REPORTED PRICES OUT OF CONTROL. TODAY, ADJUSTED FOR INFLATION, MEDIAN HOUSEHOLD INCOME IN THE GYRD IS 1.7% LOWER THAN IN 1896.

TheDensityFallacy

he false belief that by giving away density & height government will lower house prices is a fallacy. In fact, the opposite is true. Increasing building size "lifts faint values," irregering crises in housing affordability. Once developers overpay for land, everything else about the project goes up in price. Then, the point of sale, all costs are passed on to the consumer.

The right way to achieve affordability is to improve access to land by building highways and IRTS. Interregioral transit systems. In addition, along the new transit routes, government must deliver GAHP doors in sufficient quantity to meet or exceed demand. GAHP contracts on title restrict reside to 'purchase price + OCLA'. A published depreciation schedule is used to calculate the value of any home improvements. In every other way GAHP title is the same as free hold ownership.

In our view, re-imagining towers in heavy imber as a strategy to guarantee afforcibility is a chimera born of the Density Fallay. It contradicts the Urbananium's stated core mission in the competition brief: "demonstrating a part to nousing directability and a low-carbor future." "Seen the claim that mission in million homes are needed by 2000" must also be taken with a grain of salt.... It. sounds like more tower home.



THE 3 TOWERS APPROVED BY COUNCIL JULY 2025. TOWER URBANISM THROWS OUT THE BABY WITH THE BATH WATER: TOWERS ESCHEW BOTH AFFORDABILITY AND GOOD URBANISM.

At full build out, the IRTS strategy houses 2.8 million Canadians behind 1.3 million GAHP doors (IRTS is shown opposite; the range of housing types are the subject of this entry). Given the distorted conditions in the housing markets, we see GAHP as the only practical alternative.

IRTS: Four New Interregional Transit Lines


Regional transit will take people where the Skytrains cannot go—into the regional periphery, and into our neighboring regions. LRTIstreetcar will reach places where there is still land available for GAHP. Four new lines are envisioned complimenting the Skytrain's original three:


LINE 4: THE ORANGE LINE rides along the historic BC ELECTRIC R.O.W. still entirely under government ownership. It extends from North Vancouver to Chilliwack and beyond, a distance of 130 km, supporting 0.8 million people living behind 380,000 GAHP doors. The 'O' Line operates as subvay under the downtown section of Burard Street. The tunnel connecting Granville Island to Lonsdale Quay provides a third crossing of the Burard Irlet.

LINE 5: THE SNOW LINE, an extension of the Canada Line, it enters the Burrard Turnel before adding a Diesel Motor Unit (DMU) in North Vancouver. The DMU furnishes the power needed to climb alpine grades on the way to Whistler. The SNO Line delivers a one seat ride form YVR United the Company of the SNO Line delivers a one seat ride form YVR hill in North America. Future Winter Olympic Garnes can be hosted, building new transforms as Olympic Villages for the athletes.

LINE 6: THE UBC-SFU LINE will provide service between UBC and SFU, saving the costs of extending the Skytrain to UBC, and building a Gondola to SFU. The "U" Line will travel along historic streetcar alignments on W 4th Avenue, Granville Mail, Hastings Street, before riding on Galgardi Way and Como Lake Read. Riding on a second deck below the Lions Gate Bridge it will extend a a fourth crossing to the North Shore.

LINE 7: THE NORTH SHOPE | NORTH FRASER LINE will connect Horseshoe Bay and Hope. A new bridge will be built across (a renamed) Indian Arm, connecting the North Shore and North of Fraser communities. The service will replace the WCE, saving renting track space from the CPP. Many of the new GAPP doors served by the "IV Line will be built on the footbills of the Coast Mountains, continuing trends already in place.





Neighborhood Infill

The TOA legislation (more properly TOT—*Tower Oriented Transit*) borrows from the timeless urbanist principle of using a 5 minute walking distance as the radius describing a neighborhood (400 m | 0.25 m | 126 acres). Victoria's legislation then goes off the rails giving a free pass to the tower builders.

We use a 12.5 minute walking radius (1.200 m I) 0.75 m II 700 acres) as the Neighborhood brill Footprint (southerd above). We consider 12 minutes an 'easy walking distance' to rail transit service. In addition we see new towns building out into Squarrish-Whistler & the Fraser Valley, Both Tamtowns & Neighborhood Signer prominently in our strategy to End the Housing Criss. Each are planned to add 10,000 new residents at full buildout using the products we illustrate here: vernacular cottages, rows and courtyeard houses. Significantly, while the trantowns achieve 36 u/ac density, the rate of neighborhood full its spread over a larger footprint, pencling out at 5.75 u/ac to add the same number of units as a trantown. This will reduce another Tower Scourge—neighborhoods and matteated for over 3 years by construction activity spewing from every Frankenstein Tower site. Towers really only belong downtown. Human scale stok freme is for the neighborhoods and trantowns. It, completes in half the time of a tower or less, with many times less

THE COMPETITION STATION SITE 'T' AS GAHP

A bidding feature of our submission is that, by inflecting to LRTIStreetcar, and moving the stop to RTS Square, the station site is freed up and can develop as GAPP. LRTIStreetcar stops are really just so much lipstick on a pig. Not only does this add tremendous flexibility for their location, it saves a king's ransom for construction and maintenance of both underground and elevated stations. The Canada Line today is hamstrung by short station platforms. If it were riding on the sfreet the problem would not present.

Slytrain stations are a major contributor to the system's prohibitive construction cost (1 t-limes higher than LFISTreactor in humnels; 7-times higher in guideweys). Station maintenance and upkeep needlessly adds to operation costs. Because the stations are so costly, they end up being spaced too far apart forcing riders to take buses at both ends of a Skytrain tip. That

A tramstop only requires rain cover and and a data and electrical connection to power lights, a ticket machine, and read-outs announcing the next service. All of it can be accommodated curb-side at an infinitesimal cost of any Skytrain

The Skyrrain & Towers paradigm is a carbon & energy hog. Either in guideways or concrete, the Skyrrain—a gold-plated people mover developed for tairs and airports—underperforms every other comparable transit technology—and uses concrete by the truck load to complete stations, tunnels and guideways. The towers, as reported in the media, are high-proted chips for off-shore investors, spiking land prices to the point where Canadians can no longer afford to raise traillies (we detail the falling birth rate below), much less buy a place to call home. This in Canadia... the largest democracy by land mass. We have not run out of land, far from it. But government has run out of ideas.


OCCASIONAL STAGE, SUNDAY FARMER'S MARKET: RTS SQUARE, THE NEW 'URBAN ROOM'

Good urbanism is measured in terms of what the city gives for free... In our case, an 'urban room' is created by de-mapping part of one street and paving over part of another. Using bollards to regulate traffic in a manner that is transparent to pedustrians we have created a "full scale plaza" from otherwise left over space. Using the entire specially paved area—temporary closures support outdoor stages, and Sunday closures public farmer's markets. The produce can riche the LFIT [streetcar aswing on transportation costs."


artisanal | ax'tızən(ə)|

- [adjective] relating to or characteristic of an artisan: artisanal skills | artisanal workshops.
- (of a product, especially food or drink) made in a traditional or nonmechanized way; artisanal cheeses.


Transforms and a new Neighborhood inflit code specify arisanal and industrial uses that are non-toxic, non-polituring and low-desible, included in the mix are services, offices, retail & residential. We've added "Ron's RTS caté" to animate Ste As choice corner location... now fronting a new Village Square. Caté tables can spill into the square further entlancing this small-business into state State




regulating plan: site A



unit plans & schematic section







CONSERVATION IS (STILL) KEY

The competition misses an important opportunity by using a fictitious site. What opportunity? Historic preservation of our vernacular built culture. The extant built environment—including trees—are a 'sink' for affordable housing, local history (memory), first growth timber and carbon. All must be preserved.

Modern technology makes possible remaking old buildings into new ones. We would have preferred to revitable the buildings on the competition site rather than send them to the landfill and build new ones. The landfill option is being replayed in all our neighborhoods as human scale frame is destroyed to make way for the carbon & energy hogs: Slytrain & Towers.

Great profits for the 1%... Scorched earth for everyone else.

Pro Forma & Embedded Carbon

1. PRO FORMA

Stick frame construction can be delivered in the \$150 to \$200/SF range for construction, not including underground parking and 7% profit margin. GAHP contracts on title add land at the cost for \$1, guaranteeing affordability in perpetuity.

By making the assumption that the transit serving the competition site is LRTI streetcar, we have created an example of how a CAHP site can be born everyday. Rather than take up a full block in the neighborhood, LRTI|streetcar stops curb side, freeing up land for better (more affordable) uses.

In our case, the transit stop would be called "RTS Square" sharing the same name with the new 'heart' of the neighborhood. Smiles all around!

2. EMBODIED OR CAPTURED CARBON

By honoring the west coast vernacular, this design side-steps the embodied carbon sweepstakes, pivoting to capture carbon instead (just count the more than 200 new trees shown on the Regulating Plan).

Traditional west coast architecture, built from renewable, value-added, forestry products presents a very manageable burden to anthropogenic climate change. It also reinvigorates one of our most venerable industry sectors—the coastal forest.

We show 233 street respectable capturing carbon as leaves, branches, bark, wood and not systams. By boosting the urban forest, rather than boosting Tower profits, we can account for the last bits of GHGs that will never be completely eliminated. With one or two exceptions that prove the rule, all treas shorting that prove the completely eliminated. With one or two exceptions that prove the rule, all treas shorting carbon captures ratage, our designation are planted on public R.O.W. as part of a municipal CCS.

Towers growth machine and the respective claims are the declopy of the Skytrain & Towers growth machine, and growth fact, and supposition with expedient claims and prosition, switch expedient claims and prositions. Meanwhile, real growth fact, the birth rate plummets to half-replacement levels. If it keeps up this way, the science tells us it will all be over in seven oneractions.

How Towers Damage Lives, Economies & Neighbourhoods



THERE IS NO POSSIBLE WORLD WHERE BUILDING TOWERS NEXT TO MAKES FOR GOOD URBANISM, YET THIS IS NOW A COMMONPLACE IN VANCOUVER, WHERE THE PLANNING DEPARTMENT ISSUES PLANS BONUSING THESE CONDITIONS AND THEIR GUIDELINES ILLUSTRATE HOW TO CIRCLE THE TOWERS AROUND THE COTTAGES. THIS IS WHAT PASSES FOR PROFESSIONALISM?





THE CMHC GUIDELINE IS FOR HOUSING TO BE AVAILABLE AT 30% OF HOUSEHOLD INCOMES. TODAY, THESE PRICES HAVE MORE THAN DOUBLED, CUTTING DISPOSABLE INCOME IN HALF. WITH 50% LESS MONEY IN CIRCULATION, NEIGHBORHOOD BUSINESSES ARE CLOSING IN RECORD NUMBERS. THAT'S TOO BAD BECAUSE SMALL BUSINESSES LIKE 'ROIN'S CAFÉ' ARE THE BACKBONE OF FMPLOYMENT IN THE CANADIAN ECONOMY.



TOWER ZONES BREED ALENATION. LARGE POPULATIONS SHARE THE SAME NEIGHBORHOODS, YET LACK OF SUPPORT FOR SOCIAL FUNCTIONING IMPEDES NEIGHBORS INTERACTING WITH ONE ANOTHER. HALLWAYS AND ELEVATORS DO NOT SUPPORT HIGH LEVELS OF SOCIAL MIXING. IN OUR BUILDINGS ALL UNITS OPEN THEIR FRONT DOORS INTO A STREET, SQUARE OR COURTYARD. RON'S CAFÉ, THE WEEKLY FARMERS MARKET, AND THEATRE ON RTS SQUARE ARE ALL EXAMPLES OF HIGH-LEVEL SUPPORT FOR SOCIAL MIXING. SHUT INSIDE TINY, PUNY, CONDO APARTMENTS RESIDENTS WITHDRAW AND FALL VICTIM TO DOWNWARD SPIRALS OF ISOLATION.





UNIT SIZE IS NOT THE ONLY THING THAT IS SHRINKING. FAMILIES THAT WISH THEY COULD HAVE FOUR CHILDREN OPT FOR TWO. THOSE THAT MIGHT HAVE HAD TWO CAN ONLY AFFORD ONE IN THESE GOVERNMENT-INDICED ECONOMIC REALITIES.

CANADA'S FUTURE IS AT STAKE AT THE VERY SAME TIME THAT THE MENTAL AND PHYSICAL HEALTH OF OUR POPULATION IS BEING PUT AT RISK. GIVE YOUR HEAD A SHAKE, WHO'S REALLY PROFITING FROM THIS?



Fewer condo units coming to market in Metro Vancouver as presales slump

Nancouver Sun: Fewer Condo Units Coming to Market... 16 AUG 2025]

Michael Ferreira, Anthem Properties (photo); MLA Canada; Barrett Sprowson, Peterson Real Estate; Nathanael Lauster; David Ley...

Towers—heavy timber or carbon-heavy concrete, steel & glass—are loosing ground: "Not only has the volume of new projects shrunk but so has the scale... [Most] projects in the Fraser Valley are for smaller wood-frame."

Why? "... land prices went crazy... developers paid too much" The cause? "Reduced foreign investment [mostly from Communist China]." The proof is in the pudding." BC Developers wrote a plint letter to provincial and federal governments. Relax asking to relax "the rules on foreign buyers, foreign buyers taxes and hars?

People are asking for their money back, "Presale buyers of units at [a downtown' 60-storey tower have asked for their deposits back... Asking prices are between 25 and 30 per cent lower"

May 2016: This is not to deny that money flowing into Vancouver, guite often though not solely from China, is driving housing costs, especially at the luxury and of the market (which in the City of Vancouver, let's face it, includes all single-family houses). I don't think that is in dispute." Nathanael Lauster, inclustry expert witness at this and booster, [Crafting the nerrative: wealth migration, growth machines and the politics of housing affordability in Vancouver. Canada." David Lev et al. Downleaded 17 AUG 2025!.

October 2017: resales for condos "were rising by over 50 and nearly 60 percent in some areas." [Ferreira]



HAVE YOU HEARD THE NEWS? FEWER CONDOS ARE COMING TO MARKET, BUILDING IS MORE ROBUST IN THE FRASER VALLEY THAN DOWNTOWN; AND MOST (BUT NOT ALL) FOREIGN INVESTMENT IS FROM COMMUNIST CHINA. 'GOLDEN VISAS' ARE RESPONSIBLE FOR THE REGION'S POPULATION GROWTH AS LOCAL BUYER (CANADIANS) CAN'T AFFORD TO RAISE A FAMILY OR BUY A HOUSE. IS HEAVY TIMBER REALLY A REALISTIC SOLUTION? OR JUST MORE CONDO HYPE PROMOTING YET ANOTHER POTEMKIN SOLUTION?



THIS IS OUIR FUTURE UNLESS WE TAKE DECISIVE ACTION TO STOP THE PROFIT ENGINES. HUMAN SCALE URBANISM IS NOT AN ATOMIC BOMB, BUT IT CAN REVOLUTIONIZE CANADA'S FUTURE. THIS VIEW WAS CREATED BY THE YOUNGEST MEMBER OF OUR TEAM, A GRADE IS STUDENT USING CHAT OBT TO ENHANCE THE IMAGE OF WHAT COUNCIL APPROVED IN JULY 2025. THE CHAT GBT ENHANCEMENT UPDATS THE APPROVED PROJECT TO SHOW WHAT FUTURE HAS IN STORE. VIEW COMES CANNOT STOP THIS. GOVERNMENTS WILL APPROVE EVERY NEW TOWER PROPOSAL UNLESS AND UNTIL WE DO SOMETHING ABOUT IT.

building areas

SUMMARY			
SITE	122.5	150.0	18,375.0
15' SIDE ACCESS	122.5	15	1,837.50
BLDG I FSR			2.0
BLDG II FSR			0.25
BLDG III FSR			0.14
TOTAL FSR			2.42
AREA CALCULATIONS	L	W	
BLDG I FOOTPRINT	135.0	61.5	8,302.5
4.5 LEVELS			37,361.3
BLDG I FSR			2.0
BLDG II FOOTPRINT	42.0	43.3	1,816.5
2.5 LEVELS			4,541.3
BLDG II FSR			0.2
BLDG III FOOTPRINT	22.0	30.0	660.0
4 LEVELS			2,640.0
BLDG III FSR			0.1

density calculation

				SF
GROSS UP FACTOR	0.56			
6 Lots/Gross Acre	6.0	122.5	33	24,255
One Acre		66	660	43,560
SITE A		122.5	150.00	18,375
Total Building Area				44,542.50
Equivalent Acres				1.8
Dwelling Unit				800
Total Units				56
Density (u/ac)				102
Total Cars				39

COURTYARD BUILDING

This entry demonstrates the Density Fallacy, the belief that in order to lower house prices we must build towers, by achieving a remarkable gross density of 102 dwelling units per acre (FSR 2.4).


Every unit in this entry has its own street address, opening its own front door directly on the street, square or courtyard. A full


Type to enter text



BOSQUE HOUSING


BOSQUE HOUSING IS A MID-RISE TIMBER CONSTRUCTION BUILDING IN SEARCH OF IMPROVING NOT ONLY THE AFFORDABILITY OF HOUSING BUT THE QUALITY OF SPACES CREATED. THE WORD BOSQUE, MEANING FOREST, HIGHLIGHTS THESOURCE OF MATERIAL AS WELL AS THE INTEGRATIONS OF VARIOUS SYSTEMS AND PROGRAMS TO WORK TOGETHER.






UNIT	UNIT
Α	В


UNIT A + B



RESIDENTIAL DIAGRAM (LVLS 8 TO 9)



RESIDENTIAL DIAGRAM (LVLS 3 TO 7)



MEZZANINE DIAGRAM (LVL 2)



GROUND FLOOR DIAGRAM (LVL 1)

OPTIMIZIING MID-RISE TIMBER CONSTRUCTION

THE RESIDENTIAL PROGRAM COMPRISES OF 4 DIFFERENT UNIT TYPES- STUDIO, 1 BED, 2 BED, AND 3 BED APARTMENTS RANGING FROM 340 SF TO 860 SF. UNITS SIT WITHIN A GLULAM POST AND BEAM STRUCTURAL SYSTEM, WITH OPTIMAL SPANS OF 14-18 FEET. THE CENTRAL STAIR AND ELEVATOR CORE IS MADE UP OF CLT SHEAR WALL PANELS.


THE UNITS ARE LAID OUT TO BE ADAPTABLE, WHETHER CONVERTING UNITS INTO LARGER OR SMALLER SIZES PER THE TENANTS' NEEDS. ALL UNITS ARE PROVIDED WITH BALCONY ACCESS WITHIN THEIR UNITS, EITHER TOWARD THE COURTYARD OR STREETSCAPE.

STUDIO 1-BED


2-BED

RESIDENTIAL/ SHARED LOBBY


RESIDENTIAL **AMENTITIES**




BASE MASSING: MAINTAIN LOT LINE SEPARATION IN BUILDING DEVELOPMENT



COURTYARD: PROVIDE NATURAL LIGHT AND VENTILATION THROUGH UNITS



SETBACKS: CREATE VARIETY OF DIFFERENT UNIT TYPES AND **EXPAND SIDEWALK USAGE**



1 Middle Market and the second and t

PODIUM: ALLOCATE COMMERICAL AND INSTITUTIONAL USES FOR COMMUNITY



DTT-A-12

ECOLOGICAL SYSTEMS: REDUCE ENERGY USAGE AND STORM WATER RUNOFF

KEY LEGEND


3-BFD

COMMERCIAL


INSTITUTIONAL












CARVING GROUND USE PROGRAMS FOR COMMUNITY

- BOTH RESIDENTS AND VISITORS CAN ENJOY OUTDOOR SEATING ALONG THE COURTYARD AND TAKE IN THE WOODEN LANDSCAPE.
- 2 STOP BY THE CAFE TO ENJOY COFFEE AND PASTRIES ALONG THE MAIN TRANSIT STREET WITHIN A COMMERCIAL OVERLAY DISTRICT.
- 3 DOUBLE-HEIGHT GYMNASIUM PROVIDED FOR RESIDENTS TO EASILY ACCESS AT ALL HOURS OF THE DAY AND NIGHT.


- 4 COMMUNITY AND THEATRICAL GATHERINGS SET TO ENGAGE INTERACTION BETWEEN COMMUNITY AND VISITORS FOR CULTURAL VISIBILTY.
- PRACTICE ROOM AT THE MAIN STREET INTERSECTION INTRIGUE PEOPLE PASSING BY AND HIGHLIGHT MUSICAL EXPRESSION AND EDUCATION.
- LIMITED SET OF PARKING DUE TO TRANSIT ZONE LOCATION. AT THE VERY LEAST, ACCESSIBLE ROUTE PROVIED FOR ALL PARKING SPACES TO BUILDING.




- RESIDENTIAL LOUNGE PROVIDED AS AN AMENTITY IN MIXED USED BUILDING DEVELOPMENT WITH VISTA OF LIVELY PUBLIC ACTIVITY.
- B LOCAL BAR ADJOINED WITH THEATRICAL PROGRAM FOR EVENTS, CELEBRATIONS AND PERFORMANCES.
- ADMINISTRATIVE ROOMS BEHIND
 ASSEMBLY PROVIDE PERFORMERS,
 STAFF OR VOLUNTEERS SPACE FOR
 MEETINGS, DIRECTING, OR REST.
- OFFICES PROVIDED WITH LOTS OF NATURAL LIGHT AND OPEN SPACE IMPROVE WORK ENVIRONMENT EXPERIENCE.



GROUND FLOOR PLAN (LVL 1)





DEALING WITH LIMITATIONS

DTT-A-12



ZONING

INTERIORIZING SETBACKS TO ENABLE COURTYARD TYPOLOGIES IN LINE THE GOALS OF TRANSIT ZONING TO CREATE URBAN SPACES THAT ARE MORE DIVERSE AND ACCOMMO-DATING TO PEDESTRIANS AND COMMUTERS.



EGRESS

SINGLE STAIRWAY DESIGN TO ACCOMMODATE MORE EFFICIENT BUILDING TYPOLOGIES THOUGH PROXIMATE ACCESS TO THE CORE. THIS WILL MAXIMIZE HABITABLE AREAS AND PRODUCE MORE BEDROOMS TO INCENTIVIZE DEVELOPMENT.



DESIGN EXPERTISE

DEVELOPING BUILDING CODES ALONG WITH A MASS TIMBER CONSTRUCTION INDUSTRY WHICH HAS NOT YET FULLY INTEGRATED ITSELF YIELDS POTENTIAL FOR THE EXPANDED APPLICATION OF THE MATERIAL IN BUILDING CONSTRUCTION SUCH AS A FIRE RATED STRUCTURAL CORE WITH A CLT SHAFT.



ECONOMIC

ZONING INFO

Lot size (sq ft)

Total Stories (#)

Above 1st storey (#)

Amenity space (sq ft)

Non-residential (sq ft)

Stories below grade (#)

Base floor (#)

Bedrooms (#)

Units (#)

Building sq ft Above Grade

non saleable/rentable (sq ft)

Total Stories above grade (#)

saleable/rentable (sq ft)

Building efficiency (%)

FSR

INCENTIVES FOR THE USE OF MASS AS AN ALTERNATIVE CONSTRUCTION MATERIAL FOR IT SUSTAINABLE QUALITIES CAN YIELD IN THE LONG RUN AN INDUSTRIAL SECTOR WHICH WILL MAKE MASS TIMBER MORE AND MORE OF A VIABLE ALTERNATIVE





Volume of wood products used: 4,449 cubic meters (157,118 cubic feet)



U.S. and Canadian forests grow this much wood in: 12 minutes



4.89295082

18,300

25

9

10

2

7

1

74

168

5598

12029

89541

13431.15

76109.85

Carbon stored in the wood: 3472 metric tons of carbon dioxide



Avoided greenhouse gas emissions: 1664 metric tons of carbon dioxide



Total potential carbon benefit: 5136 metric tons of carbon dioxide



Equivalent to:




1086 cars off the road for a year



Energy to operate 542 homes for a year

CONSTRUCTION COSTS							
	Concrete			Submission			
	Square foo	tage	\$/sq ft		Cost	\$/sq ft	Cost
Below grade		10344.0		\$315	\$3,258,360	\$315	\$3,258,360
Base floor		11907.0		\$360	\$4,286,520	\$403	\$4,798,521
Above 1st storey		77634.0		\$385	\$29,889,090	\$431	\$33,460,254
	Quantity		;	\$/unit		\$/unit	
Balconies		144	\$2	5,000	\$3,600,000	\$25,000	\$3,600,000
	Cost per m	onth	# Months	3	Cost	# Months	Cost
Schedule Costs (Monthly	\$5	50,000		18	\$900,000	14	\$700,000
TOTAL					\$41,933,970		\$45,817,135

EMBODIED CARBON							
			Concrete		Submission		
			Embodied Carbon kg/sq		Embodied Carbon kg/sq		
	Sq ft		ft	Total Carbon	ft	Total Carbon	
Total Building Sq Footage		99885.0	6.69	668132.7627	3.44	343604.4	



CEDARWEAVE TOWER

HOW MIGHT TIMBER INNOVATION DELIVER REPEATABLE, CULTURALLY GROUNDED HOUSING FOR DIVERSE URBAN COMMUNITIES?

CONTEXT & VISION

Cedarweave Tower is a proposed Tier 1 Transit-Oriented Affordable (TOA) mass timber high-rise that advances the ambitions of the Decoding Timber Towers competition. The project seeks to "decode" tall timber design by integrating four interdependent pillars of design excellence—Liveability, Affordability, Sustainability, and Repeatability—into a replicable prototype for equitable urban housing. Situated on unceded Indigenous land in Metro Vancouver, the tower acknowledges the importance of cultural exchange while advancing modular and prefabricated construction methods.


The system employs cross-laminated timber (CLT) floor panels and glulam columns to form an 18-storey residential tower rising above a three-level podium. This podium acts as a civic and commercial commons, hosting spaces that extend the life of the building into the surrounding community. Residential modules are organized around a compact core, while cantilevered forms and interlaced podium programs create moments of shared gathering and cultural expression. The name Cedarweave embodies this vision: interlacing Coast Salish cultural motifs, modular timber construction, and the social threads of community belonging.

FOUR PILLARS (LASR)

The design is measured against four interrelated pillars of performance. *Liveability* prioritizes vibrant, culturally inclusive spaces that enrich everyday experience. *Affordability* ensures the project is financially viable while delivering a significant proportion of below-market homes. *Sustainability* emphasizes passive design strategies and low-carbon timber systems that reduce environmental impact across the building's lifecycle. *Repeatability* establishes standardized, modular systems that can be adapted and reproduced across future TOA sites.


By advancing each of these pillars, Cedarweave Tower proposes a new paradigm for transit-oriented affordable housing. Here, affordability is not only expressed in numbers but in the capacity to belong, to share daily rituals, and to weave new traditions into ancestral ground. In this spirit, the project is envisioned not as a singular gesture but as a prototype for future policy frameworks and industry standards. It responds directly to the TOA mandate for 8–20 storey density while setting a precedent for embedding mixed retail, civic, and cultural amenities within mid-rise developments.




















COMMUNITY-CENTRIC PODIUM

The podium of Cedarweave Tower is conceived as a cross-cultural gathering place that anchors the development in everyday community life. Spanning the first three levels with generous 4.5 m ceiling heights, it offers open, adaptable volumes for public use. A stepped form and transparent gallery blur the threshold between inside and out, inviting neighbors and visitors alike. Acting as a civic living room, the podium hosts Indigenous exhibitions, immigrant-run shops, cross-cultural performances, and daily amenities such as a theatre, grocery, café, and rooftop garden—programmed in collaboration with local residents and First Nations partners.

PROGRAM & USER EXPERIENCE

The ground floor opens with a public market hall and café that encourage daily interaction. Above, a flexible performance hall supports cultural events, meetings, and the arts, while a community kitchen and gallery enable workshops and exhibitions. Active uses are placed at street level, quieter communal spaces above, all connected by stairs, terraces, and local art. Outdoor terraces and the podium roof garden expand opportunities for gathering and urban agriculture. Architectural details reference Coast Salish weaving patterns, symbolically tying Indigenous and immigrant narratives together.

Residents pass through this civic commons daily, meeting familiar faces and sharing experiences. By uniting places to shop, dine, celebrate, and rest, Cedarweave Tower embeds social cohesion directly into the building's form and program.

CONCLUSION

A SYSTEM THAT PENCILS BY DESIGN.

Cedarweave dedicates 30% of homes at ~80% AMR and funds this without grants by (1) eliminating the underground parkade in favour of car-share and high-capacity bicycle parking, and (2) covenanted reinvestment of a share of podium NOI into housing operations. The Building Statistics table demonstrates how a compact core, stacked "wet bands," and a disciplined net-to-gross support this cross-subsidy with stable operating margins. This answers the brief's request for an affordability business case rooted in a base-case pro forma.

REPEATED PLATES. LOWER RISK.

The fourth and fifth plans illustrate an A/B pairing that alternates up the tower: the identical CLT slab outline (and façade module) repeats every floor, while unit layouts flip or mirror around a constant services spine. For delivery, this repeatability compresses detailing, approvals, shop-drawing cycles, and on-site coordination; for operations, it simplifies maintenance and turn-over. In short, the plates repeat so the process repeats—precisely the systemization the competition seeks.

TIME IS MONEY—WHERE TIMBER WINS.


The Construction Costs table sets our submission against the concrete benchmark: timber still carries a higher above-grade \$/ft² in many markets, but a shorter schedule from standardized parts (CLT cassettes, glulam posts, unitized façade) reduces general conditions and interest carry. Faster dry-in and earlier occupancy bring revenue forward, narrowing the apparent cost gap while meeting the brief's aim to streamline delivery of large-scale low-carbon housing.

AFFORDABILITY BEYOND RENT.


Savings for residents accrue monthly in three places: (1) rent (discounted units), (2) mobility (car-lite living enabled by transit and bike infrastructure), and (3) utilities (a passively tempered envelope and mixed-mode ventilation reduce operational loads). These household savings lower arrears risk and strengthen the project's long-term financial resilience—affordability as both a tenant benefit and a project-stability strategy. (The brief explicitly invites entrants to link building delivery to life-cycle costs and operations.)

CARBON THAT UNLOCKS FINANCE.

The Embodied Carbon table reports whole-building A1–A3 results using recognized tools (WoodWorks/EC3/BEAM): the timber scheme achieves $\approx\!4.28$ kgC02e/ft² versus $\approx\!6.69$ kgC02e/ft² for the concrete baseline—about a 36% reduction for the same above-grade area. Clear carbon accounting, as requested by the brief, positions the project for green-finance instruments and policy incentives that further improve affordability.









Building Statistics	Number
FSR	8.01027322
Lot size (sq ft)	18,300
Building sq ft Above Grade	146588
Building efficiency (%)	85
non saleable/rentable (sq ft)	21988.2
saleable/rentable (sq ft)	124599.8
Total Stories above grade (#)	18
Total Stories (#)	18
Base floor (#)	1
Above 1st storey (#)	17
Stories below grade (#)	0
Units (#)	180
Bedrooms (#)	261
Amenity space (sq ft)	2884
Non-residential (sq ft)	29678

CONSTRUCTION COSTS	;				
		Concrete		Submission	
	Square footage	\$/sq ft	Cost	\$/sq ft	Cost
Below grade	0.0	\$315	\$0		\$0
Base floor	11840.0	\$360	\$4,262,400	\$403	\$4,771,520
Above 1st storey	134748.0	\$405	\$54,572,940	\$431	\$58,076,388
	Quantity	\$/unit		\$/unit	
Balconies		\$25,000	\$0	\$25,000	\$0
	Cost per month	# Months	Cost	# Months	Cost
Schedule Costs (Monthly					
Overhead)	\$50,000	18	\$900,000	14	\$700,000
TOTAL			\$59,735,340		\$63,547,908
EMPODIED CAPRON					


EMBODIED CARBON					
		Concrete		Submission	
	Sq ft	Embodied Carbon kg/sq ft	Total Carbon	Embodied Carbon kg/sq ft	Total Carbon
Total Building Sq Footage	146588.0	6.69	980530.0638	146588	4.28

PODIUM-AS-CLIMATE-DEVICE.

Cedarweave's three-level podium concentrates everyday programs—market "grid" stalls, full-service grocery, café/restaurant, theatre/cinema, gallery, gym, and a secure bike hub—into an all-season civic living room. By pulling high-trip uses on site and stacking them under a shared shell, the project reduces resident travel demand, consolidates heating/cooling loads, and shares back-of-house infrastructure across tenants. The result is lower per-capita operational energy and a resilient neighbourhood anchor that functions year-round, not just in fair weather.

PASSIVE FIRST, SYSTEMS SECOND.

A repeatable 3×3 m structural grid organizes cantilevered balcony "boxes" as built-in brise-soleil, providing self-shading in summer and rain protection without mechanical complexity. Slender floor plates, generous operable windows, and exteriorized circulation where appropriate enable mixed-mode ventilation—natural ventilation on shoulder days, high-efficiency heat recovery in winter. The podium roof and terraces are planted to temper microclimate, manage stormwater, and create pleasant outdoor rooms that extend the life of the building into the public realm.



ALL-ELECTRIC AND FUTURE-PROOF.

The tower is designed around an all-electric services stack: centralized or distributed air-source heat pumps for space conditioning, HRVs for each residential riser, and heat-pump water heating with recirculation controls. Sub-metering for residential, commercial, and common areas supports performance-based operations and tenant transparency. Demand-response-ready controls (night set-back, pre-cool/heat, limited peak shedding) position the building to participate in utility incentive programs without sacrificing comfort.

WATER, LANDSCAPE, AND MATERIALS.

Blue-green roofs detain stormwater, support pollinator habitat, and host community plots with drought-tolerant planting. Indoors, low-flow fixtures and leak-detection on risers reduce potable demand. The structure employs CLT floor cassettes and glulam posts/beams with dry connections; exterior walls use unitized, demountable panels. This Design-for-Manufacture-and-Assembly (DfMA) approach minimizes waste, accelerates dry-in, and enables replacement at end-of-life—key steps toward a circular materials economy.

EMBODIED CARBON—MEASURED AND MANAGED.

As documented on Page 3, whole-building A1–A3 embodied carbon for the timber submission is significantly lower than the concrete baseline (\approx 36% reduction for the same abovegrade area). The project team specifies products with EPDs, prioritizes low-carbon concrete in the limited foundation work, and tracks assemblies in a bill-of-materials that can be verified with tools such as EC3/BEAM. The standardized kit produces repeatable quantities, improving carbon predictability across future TOA sites.

OPERATIONS THAT SUSTAIN AFFORDABILITY.

Sustainability is tied to household economics. The no-parkade, bike-first strategy lowers construction and operating costs while enabling car-lite living; the podium's on-site services further cut transport emissions and monthly expenses. A maintenance-light envelope and repeatable details reduce service calls and downtime, keeping strata/operating fees in check and extending component lifespans.

What the diagram shows.

POLICY SIGNAL.

By proving that a standardized timber kit can deliver lowenergy operations, verifiable embodied-carbon reductions, and a year-round civic commons, Cedarweave offers a template municipalities can adopt: encourage all-electric, car-lite podiums with on-site daily needs; recognize unenclosed climate buffers as performance features; and reward repeatable lowcarbon assemblies with predictable approvals.

ONE MODULE, MANY BUILDINGS.

Cedarweave is organized by a single, repeatable 3×3 m module that governs structure, services, and façade. CLT floor cassettes span between glulam posts on this grid; the same 3 m width defines unitized wall panels and balcony "box" elements. Because the geometry, connections, and tolerances are constant, the system scales cleanly—across floors, across sites, and across future TOA projects.

ONE SLAB; TWO FITS; ENDLESS STACKS.

The residential tower repeats an identical floor slab while alternating A/B unit fits (as seen in Levels 4–5). Kitchens and baths align within a vertical wet band, keeping risers, shafts, and exhausts in the same places on every level. The result is fewer unique parts, shorter coordination loops, and a learnable rhythm for trades—repeat the plate, repeat the process.

ASSEMBLY YOU CAN SCHEDULE TO THE DAY.


Components arrive pre-numbered and weather-protected: glulam columns and beams, CLT cassettes with preformed penetrations, and clip-on façade panels with windows pre-installed. Dry connections limit wet trades; balcony boxes slot into the grid as shading/rain devices without bespoke details. This DFMA workflow creates a predictable crane rhythm, quicker dry-in, and less site congestion—key to delivering affordable housing at speed.


ADAPTABLE WHERE IT COUNTS.

The module is fixed; the enclosure and program are flexible. Podium bays accept different community uses (market, theatre, café, daycare) without changing the frame. On the tower, the same plate supports multiple unit mixes and façade expressions. Jurisdictions can "tune" counted enclosure (e.g., open verandas vs. fully enclosed perimeter) to meet local FSR or energy targets without retooling the system.

OPERATIONS MADE SIMPLE.

Standardized, unitized façade panels are replaceable from a manlift; interior dry-fit timber linings are demountable for quick repairs and upgrades. Repetition creates a stable spares catalogue, clearer 0&M manuals, and fewer surprise details—lowering lifecycle costs while keeping homes in service.













WHAT THIS PROJECT CHANGES

POLICY RECOMMENDATIONS

- Civic-commons cross-subsidy. Require a fixed share of podium NOI to fund affordability in perpetuity.
- Car-lite standards. Reduce/waive parking minimums at transit and trade them for bike capacity and on-site services.
- Performance-based approvals. Provide a predictable path for standardized mass-timber kits (pre-reviewed details, clear fire/ egress pathways).
- 4. Recognize climate buffers. Treat unenclosed verandas/arcades as performance devices in area/FSR accounting.
- 5. Carbon disclosure. Mandate A1–A3 embodied-carbon reporting at permit, unlocking green-finance incentives.

INDUSTRY IMPACT

- Demand aggregation. Repeating one kit across sites stabilizes orders for CLT, glulam, and unitized façades—driving price normalization.
- Delivery playbook. Fewer part types, clearer logistics, and dry connections shorten shop-drawing cycles and site duration.
- Workforce upskilling. DFMA assembly and façade cassette replacement become standard practice, reducing maintenance risk for owners.


USER/TENANT BENEFIT


 Lower monthly costs: discounted rent for 30% of homes, carlite living, and mixed-mode comfort that trims utility bills.

- Daily convenience: groceries, childcare-friendly amenities, and cultural programs within a short walk of homes and transit.
- Belonging: Indigenous-led curation and local operators make the podium a familiar place, not just a lobby.

CLOSING STATEMENT

Cedarweave Tower is more than a single building; it is a policy-aligned, industry-ready prototype. By weaving cultural life with a standardized mass-timber system, it shows how cities can scale low-carbon housing without sacrificing dignity, affordability, or craft. Replicated across TOA sites, the approach shortens time-to-keys, lowers embodied carbon, and strengthens the social fabric—demonstrating a practical path for building higher, building smarter, and building together.





THE DESIGN OF THE HYBRID MASS TIMBER TOWER FOCUSES ON MULTIPLE OPTIMIZATIONS TO REDUCE MATERIAL USE, SPEED UP CONSTRUCTION, AND BALANCE THE USE OF MASS TIMBER AND CONCRETE COMPONENTS.

THE MAIN STRUCTURE CONSISTS OF CLT PANELS LOCATED AROUND THE PERIMETER OF THE TOWER. PLACING THE CLT PANELS AROUND THE PERIMETER IMPROVES STRUCTURAL EFFICIENCY AND ELIMINATES THE REQUIREMENT FOR A CONCRETE CORE.

THE PROPOSED DESIGN USES THE LARGEST CLT PANELS AVAILABLE IN NORTH AMERICA. A SINGLE PANEL WILL STRETCH THE WIDTH OF THE TOWER AND THE HEIGHT OF A SINGLE FLOOR.

EACH PANEL IS MODULAR FOR IMPROVED CONTRACTIBILITY AND HAS 8 WINDOW OPENING REDUCING THE VOLUME OF TIMBER REQUIRED. THE FLOOR SYSTEM UTILIZES SIMILARLY SIZED CLT PANELS THE SPAN THE WIDTH OF THE TOWER.

CLT PANELS CAN SPAN LARGE DISTANCES WHEN SUPPORTING THEIR SELF WEIGHT BUT ARE LIMITED TO ~20' SPANS WHEN SUPPORTING RESIDENTIAL LOADING. THIS DESIGN PROPOSES USING TEMPORARY SHORING OF THE CLT FLOOR PANELS DURING CONSTRUCTION AND THE PLACEMENT OF INTERNAL CONCRETE COLUMNS TO REDUCE SPAN DISTANCES.

THE GOAL OF THIS DESIGN IS TO USE THE PERIMETER CLT PANELS TO SUPPORT MOST OF THE SELF WEIGHT OF THE TOWER. THE CONCRETE COLUMNS WILL THEN MAINLY SUPPORT RESIDENTIAL LOADING. THE CONNECTIONS BETWEEN THE CLT PANELS AND THE CONCRETE COLUMNS WILL ALSO BE DESIGNED TO ALLOW CONSTRUCTION TO PROGRESS WHILE THE CONCRETE CURES.

THE RESULT OF THESE OPTIMIZATIONS IS A HYBRID MASS TIMBER CONCRETE STRUCTURE THAT IS MORE AFFORDABLE, FLEXIBLE, FASTER TO CONSTRUCT, AND MORE ENVIRONMENTALLY FRIENDLY THAN TRADITIONAL CONSTRUCTION METHODS

ROOTED IN RESILIENCE

decoding affordable Indigenous housing with mass timber

problem statement:

The City of Vancouver is facing the interconnected challenges of climate change, housing unaffordability, and a critical need for Indigenous housing rooted in cultural identity. Yet conventional construction remains carbon-intensive and inefficient, often failing to create inclusive and community-oriented places to live.

of Vancouver's unhoused are Indigenous BC Non Profit Housing

Association, 2023

Rework accounts for: ~12% of total construction value 27% of total construction time Becht & AXAXL

6/10 **Canadians** surveyed have little or no sense of community YMCA Canada

industry contributes 39% of global CO₂ emissions

The building

World Green Building

72% of BC construction company are reporting sever ICBA Independent

labour shortages



To create vibrant, sustainable communities where mass timber design celebrates nature, supports intergenerational living, and fosters connection through housing affordability, systemized construction, and Indigenous-led design approaches.



The study site is located in TOA Tier 2 where the surrounding context is primarily low-rise residential. It is within a five-minute walk of rapid transit, shops, services, and green space, making it highly accessible and well-connected.

The property consists of a large block-end assembly of six 50' x 122' lots, totalling 36,000 square feet. It is a north-facing site that fronts onto a local residential street, with lane access at the rear. The site lies on the shared territories of the Musqueam, Squamish, and Tsleil-Waututh Nations. It is situated in a seismic zone and experiences frequent rainfall, which are important considerations for design and construction.

existing site conditions

housing types: single-family homes, duplexes, townhouses, often with private yards

age groups: mix of children, middle-aged adults, and seniors

height limit: up to 2.5 storeys

density: 2.5 FSR

zoning: RT-4 (Two-Family Dwelling District)

households: primarily families, couples, and some retirees

This development is driven by the Seven Laws of Life-Health, Happiness, Humbleness, Generations, Generosity, Forgiveness, and Understanding. It ensures that the built environment reflects these values in the way homes are shaped, spaces are shared, and community is nurtured. The proposed "decodes" advocate for widespread applicability and repeatability of mass timber. With consideration of life cycle costs and operations of the building, it aims to fill in the gap between building code, zoning, & other regulations and the delivery of sustainable developments.

comparative advantages of mass timber

Highlighting how mass timber builds like Lego: fast, light, and green, while concrete is slow, heavy, and carbon hungry.

slow to build

concrete needs time on site to solidify before it can support the weight of floors above

non-renewable resource

mining for gravel, sand and cement use up valuable resources and can cause irreversible natural landscape damages

higher noise levels

dense concrete transfers noise, onsite construction will produce more noise for surrounding neighbours

higher labour costs

require larger crews over longer periods making the process labour intensive

fast to build

prefabricated modular mass timber is designed for assembly, making it fast to build, less labour-intensive, and cost-efficient

renewable resources

wood is harvested from sustainably managed forests where it also stores carbon

seismic resilience

mass timber's light weight and modular structure improve seismic performance and can facilitate rebuilding or repair post-quake

quieter homes/environment

CLT can dissipate impact sounds during assembly

fire resistance

mass timber chars and does not burn like conventional wood

timber components

A giant IKEA kit of beams, walls, and panels: prefabricated in factories and assembled with precision on site.

CI la la di uu

cross-laminated timber

large engineered wood panels layered and stacked in alternating directions and glued together to be used in floor, roof, load-bearing and core walls

38 mm thick concrete

gypsum-concrete topping

lightweight layer poured over CLT floors to improve fire resistance, sound insulation, and provide a smooth base for finishes

floors to lation, shes

glued-laminated timber

bonding layers of dimensioned lumber with durable adhesives to create strong, versatile beams and columns



DECODE: Maintaining character/heritage with specfic infill guidelines

PROPOSED SOLUTION: Extensive shadow and view cone studies ensure 8-12 storey buildings minimize community impact, with modular assembly reducing acoustic and construction disruptions. An exemption is sought for mass timber buildings to bypass infill regulations given their prefabricated modular nature.

guiding principles



sustainability/resilience

Prioritizing energy efficiency, renewable systems, and low-carbon materials to reduce emissions while ensuring long-term environmental & economic sustainability

Indigenous led design

We should build infrastructure to facilitate Indigenous practices

Indigenous design is..

Guided by Indigenous leadership to celebrate cultural identity and ancestral knowledge while shaping housing that reflects community self-determination


affordability

Streamlined building methods and supportive financing mechanisms ease upfront expenses, enabling broader access to high-quality housing



accessibility/inclusivity

Design features remove physical and social barriers, ensuring people of all ages and abilities can participate fully in community life




liveability/sociability

Thoughtful layouts and inviting common areas cultivate vibrant daily life, encouraging interaction and strengthening neighborhood bonds

building assembly

Mass timber is designed for assembly, not traditional construction. Prefabricated beams, walls, and façades are manufactured offsite, then quickly assembled on a slab foundation. This approach reduces labor, time, and disruption while delivering flexible, durable, and low-carbon buildings.



Mass timber buildings require protected connectors, durable envelopes, and careful detailing to meet safety and energy codes. This includes ensuring fire protection, weather resistance, and acoustic performance, while also addressing challenges like shrinkage, wood variability, and thermal bridging to deliver safe, efficient, and long-lasting multi-storey construction.


DECODE: Code complexity & Labour skills gap

BARRIER: Navigating fire ratings and exposed timber rules is challenging and there are few contractors are trained in CLT and glulam assembly.

PROPOSED SOLUTION: The BC Building Code 2024 now allows encapsulated mass timber construction (EMTC) up to 18 storeys for residential mixed-use.


Each building of this development will comply with the EMTC regulations for safety, ensuring adherence to structural, fire protection, and accessibility standards that safeguard both residents and the broader community.

ground floor floor plan



social rationale

This development offers a wide variety of unit types, ranging from studios and accessible suites to larger family units and cohousing pods, ensuring inclusivity across household needs. Cohousing elements including shared kitchens, dining and living areas, and resource-efficient communal spaces helps to promote collective energy management and reduce per-capita energy use. Complementing the diverse housing mix, Indigenous-owned local-serving retail and flexible community spaces will provide vital services and third spaces.




DTT-B-01

DECODE: Separation to neighbours/exposure protection

BARRIER: On RT lots, meeting exterior wall fire-resistance and unprotected opening limits next to low rise residential can pinch windows and push setbacks.

PROPOSED SOLUTION: Seeking flexibility in building separation requirements, as the design strategically pushes towards setbacks to create a more engaging and interactive streetscape. Direct proximity to neighbouring buildings is limited, minimizing potential impacts while complying with acoustic and fire code regulations.



development reflects Indigenous values of stewardship and kinship, where wood is more than a material but a living connection to land and culture.

day in the life

Designed as both housing and a space for cultural preservation and celebration, it welcomes Indigenous peoples from diverse nations across Canada. Here, mass timber nurtures not just the buildings, but a way of living together-grounded in care, belonging, and collective well-being.



elders share stories, connecting generations under one roof



in shared gardens framed by wood, the community grow food togetherbuilding self-sufficiency, resilience, and connection through urban agriculture



in the warm and bright ambience of mass timber, it caries the natural aroma of wood creating a sensory-rich community space

perfect for Indigenous-led practices ike drumming and Coast Salish weaving to fill the space with culture, teaching, and community



over a rooftop barbecue, neighbours share food, jokes, and plans for the upcoming community pop-up event



a sauna can serve as a modern way to honour the tradition of fire in urban Indigenous culture, echoing the role of sweat lodges as places of ceremony, healing, & connection



with an Indigenous-owned bike workshop (commercial use) right on the block, neighbors can fix and maintain their rides without leaving the community



easy and afforable daycare drop-off, right at home




DECODE: Mixed-use isn't generally permitted in low-density residential zones.

BARRIER: Current zoning RT-4 districts allow multiplex/duplex/infills; ground-floor retail is not a listed outright use.

PROPOSED SOLUTION: Rezoning to RM-8 district with exception of 8-12 storeys and increased density. Seeking allowances for mass timber buildings in off-arterial mixed-use locations, supporting revenue diversification and enhancing the potential for higher development returns.





priotizing infrastructure to

promote active modes of travel

while reducing reliance on cars,

50 ft 15 0 ft 30



pro forma

FSR	4.79	# of storeys	8-12 storeys
lot size	36,600 sf	# of residential units	171
net building size	175,447 sf	# of bedrooms	307
efficiency	85%	amenity space	11081 sf
non saleable/rentable	26317 sf	non-residential	14280 sf

		cor	concrete cost mass ti		
below grade	0	\$315/sf	\$0	-	\$0
based floor	18,468 sf	\$360/sf	\$6,648,480	\$300/sf	\$5,540,400
above 1st storey	156,979 sf	\$405/sf	\$63,576,495	\$250/sf	\$39,244,750
exterior hallway (2 nd &3 rd floor)	1200 sf	\$250/sf	\$300,000	\$200/sf	\$240,000
labour	175,447sf	\$29/sf	\$5,087,964	\$18/sf	\$3,158,046
schedule costs	\$50,000	18 months	\$900,000	16 months	\$800,000
			\$76,512,93		\$48,983,196


DECODE: Material premium, insurance & finance

BARRIER: Conservative risk pricing for mass timber increases builder's risk premiums and financing.

PROPOSED SOLUTION: Expand actuarial data from Canadian and international mass timber projects to demonstrate performance parity in fire and water risk, and partner with CMHC and provincial insurers to pilot reduced premiums for projects meeting enhanced moisture and fire protection protocols. Demonstrate lower lifecycle risk to help lenders price more competitively.

economic rationale

An 8-12 storey mixed-use mass timber development in Vancouver shows clear economic advantages, with total costs nearly 36% lower than concrete construction (\$48.9M vs \$76.5M), largely due to reduced labour, faster schedules, and lighter structural systems. While mass timber currently faces higher material premiums and specialized labour costs, these can be offset through Indigenous funds, government initiatives, and industry standardization.





Our Vision:

Our vision for Lalp is not only to raise the bar for affordable, and livable government provided housing, but to do so by utilizing innovative, yet proven mass timber prefabrication strategies. Guided by core industrial engineering and lean construction principles, the project will be constructed very efficiently. Furthermore, the project aims for holistic financial and environmental sustainability by facilitating residents' economic participation. Finally, the residence's inclusion of Indigenous-inspired spaces thoughtfully recognizes and honors the local First Nations communities and their land.

Key Goals:

- Easily built point supported CLT prefab design
- Quick organized construction with zero delays
- Provide all needs for the lower and middle classes
- Enhance land with native spaces

Construction Process

Lean Construction:

Just-in-Time (JIT) Delivery

JIT Relies on factory supplied construction material, such as mass timber being delivered only when ready for asembly. For Lalp House construction, timber will only be ordered/delivered at the time the next floor is ready to be assembled. This will prevent excess inventory on the construction site, an important consideration since both buildings will be under construction simultaneously.


Slot & Tab Assembly

A method from the metal assembly playbook, reimagined with prefab mass-timber. Slot and tab assembly reduces incorrect part installation instances and reduces assembly time on site. It is also easily achievable with modern timber CNC milling machinery.

CEDAR HAUS (Square)		FIR HAU		
FSR	4.1		FSR	3.6
Lot size (sq ft)	18,300		Lot size (sq ft)	18,300
Building sq ft Above Grade	74400		Building sq ft Above Grade	65600
Building efficiency (%)	85		Building efficiency (%)	85
non saleable/rentable (sq ft)	11160		non saleable/rentable (sq ft)	9840
saleable/rentable (sq ft)	63240		saleable/rentable (sq ft)	55760
Total Stories (#)	11		Total Stories (#)	12
Stories below grade (#)	0		Stories below grade (#)	6
Base floor (#)	1		Base floor (#)	1
Above 1st storey (#)	10		Above 1st storey (#)	5
Units (#)	84		Units (#)	75
Bedrooms (#)	144		Bedrooms (#)	60
Amenity space (sq ft)	3100		Amenity space (sq ft)	4400
Non-residential (sq ft)	2700		Non-residential (sq ft)	4800

CONSTRUCTION COSTS						CONSTRUCTION COSTS					
		Concrete		Submission	1			Concrete		Submission	1
	Square						Square				
	footage	\$/sq ft	Cost	\$/sq ft	Cost	<u> </u>	footage	\$/sq ft	Cost	\$/sq ft	Cost
Below grade	0.0	\$315	\$0	\$45	\$0	Below grade	38400.0	\$315	\$12,096,000	\$45	\$1,728,000
Base floor	6400.0	\$360	\$2,304,000	\$45	\$288,000	Base floor	9600.0	\$360	\$3,456,000	\$45	\$432,000
Above 1st storey	68000.0	\$405	\$27,540,000	\$45	\$3,060,000	Above 1st storey	56000.0	\$405	\$22,680,000	\$45	\$2,520,000
	Quantity	\$/unit		\$/unit			Quantity	\$/unit		\$/unit	
Balconies	0	\$25,000	\$0	\$25,000	\$0	Balconies	0	\$25,000	\$0	\$25,000	\$0
	Cost per						Cost per				
	month	# Months	Cost	# Months	Cost		month	# Months	Cost	# Months	Cost
Schedule Costs (Monthly						Schedule Costs (Monthly					
Overhead)	\$50,000	18	\$900,000	12	\$600,000	Overhead)	\$50,000	18	\$900,000	12	\$600,000
TOTAL			\$30,744,000		\$3,948,000	TOTAL			\$39,132,000		\$5,280,000


EMBODIED CARBON	BODIED CARBON EMBODIED CARBON										
		Concrete		Submission				Concrete		Submission	
		Embodied		Embodied				Embodied		Embodied	
		Carbon kg/sq	Total	Carbon	Total			Carbon		Carbon	Total
	Sq ft	ft	Carbon	kg/sq ft	Carbon		Sq ft	kg/sq ft	Total Carbon	kg/sq ft	Carbon
otal Building Sq Footage	74400.0	6.69	497663.088	2.5	186000	Total Building Sq Footage	104000.0	6.69	695658.08	2.5	260000




Zoning

Relationship to existing building code: where is it compliant and where does it challenge BC building code and why are these changes proposed: The two units fit under new zoning regulation, but the hybrid building is new with two buildings on one site plan.

The existing zoning is commercial MX which fits within: "Within residential zones, additional nonresidential uses beyond the minimum street front requirement are allowed, provided residential uses comprise at least 50% of the total building square footage. Within nonresidential zones, there are no additional mixing requirements beyond ground floor requirements." This however, challenges the single structure. It is proposed to allow for two or more buildings when sites have the appropriate setbacks.




This graph shows the change over the next 30 years with renters. Because the tax base will remain at the same rate (roughly estmated to be 300,000 C\$ per 6 lots = 1,800,000 C\$). This will be the tax rate over the next 30 years. It is estimated that it will be at a minimum valuation of 18 million after the 30 years.




The property will buy land for a bike lane in the street and convert it to a one way, smaller street from 10 to 9.5 foot width. This will be a traffic calming measure and increase biking safety for residents.




Floor Plans | Pricing | Liveability



Two Bed (750 sq. ft.): 70 units, 1875C\$



One Bed (500 sq. ft.): 55 units, 1500C\$



Studio (400 sq. ft.): 20 units, 1125C\$

A tax increment area (TIA) or tax increment financing (TIF) is a way for the BC government to fill in gaps of manufacturing the more expensive mass timber units. Due to high demand for affordable housing, it will take more time to fill all of the units and turn them into profits. To speed up this process, this and subsequent units will be financed with TIF to freeze current rates for the next 30 years, or until 2055. This would need to be overseen by government appointed board.



Championing Change Through Sustainability

Socioeconomic:

The following building amenities and commercial locations will help contribute to both social stability and economic growth by providing all needs in a quick-to-access location, within the mass timber prefab setting.



Bike Storage



Bike Repair Shop



Cafe





Environmental:

This project will have less upfront carbon emissions than traditional rebar and construction-based techniques. The trees sequester and will contain carbon. Furthermore, timber isn't toxic, so PPE will still have to be worn by workers on site but will have less long lasting consequences compared to concerns on inhaling when concrete dust is present. Those working on Spruce unit will need extra precautions given the inherent nature of digging and pouring concrete below grade for the underground parking garage.

This building is environmentally sustainable and LEED Gold certfied with electricity from solar, wind, and other renewables.



MOVING WOODS

Resource - Community - Variation

The theme *Decoding Timber* and its relationship to the broader district is explored through spatial, architectural, and ecological ideas. Landscapes and environments become exemplars of timber construction and mid-scale building typologies. The concept of an archipelago shapes the urban fabric: clusters of buildings dispersed among open, ravine-like corridors that cut across streets and public spaces, offering an alternative to the dominance of the abstract grid. Instead of rigid order, this approach proposes a system of expandable and interconnected forest fragments, neighbourhoods, and communities. This integration suggests a deeper relationship between forests and forest products, beyond material specification, by linking ecological, economic, and cultural values back to the forest itself.


Varied patch clusters, each with distinct scales, typologies, and open-space conditions, establish a dynamic framework of limits, proximities, and contrasts. Transformation within and between clusters encourages creative competition, fosters ownership, and reinforces social identity. Courtyard typologies, in particular, generate strategies of community-making: deck-access housing and neighbourhoods are strongly tied to pedestrian-oriented courtyards, where streets become shared social spaces. The courtyards themselves create instant communities.

At the city's transit hub, boundaries between interior and exterior space are pushed to an extreme. Defined by three concentric circular forms—including a tree library—the hub becomes both an infrastructural node and a celebration of timber architecture.

Ultimately, this urban vision situates resource, industry, and community locally, with mass timber as its central medium. Timber here is more than material: it is an essential resource that moves from forest to manufacturer to people, reconnecting the city to its environment. Through housing, affordability, climate action, and design, timber becomes the framework for a new kind of city - *Moving Woods*.



Goals + Key Moves // Low-Carbon, Standard Construction, Local, Variations




Construction

Mass Manufacturing

Easy + Quick Timber/Steel

Hybrid Constrction // Lower

Carbon Emissions



5.

Modular + Endless Structure Configurations // Quick Expansion + Program Variety





Site B - Whole Block - Plan


FSR	4.59214318
Lot size (sq ft)	13,186
Building sq ft Above Grade	60552
Building efficiency (%)	85
non saleable/rentable (sq ft)	9082.8
saleable/rentable (sq ft)	51469.2
Total Stories above grade (#)	12
Total Stories (#)	12
Base floor (#)	1
Above 1st storey (#)	11
Stories below grade (#)	0
Units (#)	58
Bedrooms (#)	86
Amenity space (sq ft)	8310
Non-residential (sq ft)	8310

Proforma

Using the standard pricing, we achieved a slighly more expensive build but in much less time with modular building and standard mass timber product sizing

CONSTRUCTION COSTS					
		Concrete		Submission	
	footage	\$/sq ft	Cost	\$/sq ft	Cost
Below grade	0.0	\$315	\$0	\$0	\$0
Base floor	3396.0	\$360	\$1,222,560	\$403	\$1,368,588
Above 1st storey	57156.0	\$405	\$23,148,180	\$431	\$24,634,236
	Quantity	\$/unit		\$/unit	
Balconies	40	\$25,000	\$1,000,000	\$25,000	\$1,000,000
	month	# Months	Cost	# Months	Cost
Overhead)	\$50,000	18	\$900,000	14	
TOTAL			\$26 270 740		\$27 702 824

		Concrete		Submission	
	footage	\$/sq ft	Cost	\$/sq ft	Cost
Below grade	0.0	\$315	\$0	\$0	\$0
Base floor	3396.0	\$360	\$1,222,560	\$403	\$1,368,588
Above 1st storey	57156.0	\$405	\$23,148,180	\$431	\$24,634,236
	Quantity	\$/unit		\$/unit	
Balconies	40	\$25,000	\$1,000,000	\$25,000	\$1,000,000
	month	# Months	Cost	# Months	Cost
Overhead)	\$50,000	18	\$900,000		\$700,000
TOTAL			\$26,270,740		\$27,702,824





Used: 2846 m³



US/CAD Forest 2846 m³ of wood in



Used Wood: Gas Emissions: of CO2



Carbon Benefit 3516 metric tons of CO2

Grade Plan



L Building Floor Plans - Project Data

743 Cars off the road Energy to operate 371

Using the Woodworks carbon calculator we calculated the stats of a single L-Building typology. The volume of wood stated consists of the structure, flooring, ceiling, and interior wallframing of our design.

L-Building Typology - WoodWorks Carbon Calculator


The modular screen friezes function as adaptive climate-control systems, regulating solar gain, shading, and ventilation. Organized as coordinated yet varied sequences, they introduce a layer of responsiveness without uniform repetition. Operable panels and Venetian blinds provide residents with direct control over thermal comfort and daylighting. At the urban scale, these vertical elements articulate the skyline, mediating between the city and the riverfront while reinforcing their spatial and visual connectivity.



Resident Walkway // Front Entrances // Screens - Venetian Blinds - French Doors







2nd Floor Plan

1. commercial/amenity

2. sponge courtyard

3. trellis 4. loggia walkway

5. core

6. community/flex space

7. exterior walkway

8. units 9. exterior stair

10. rooftop terrace 11. sidewalk

12. verae

3rd-4th Floor plan





5th-12th Floor Plan







Our proposal replaces the conventional grid of single-family blocks with a decentralized urban scheme, where the "city neighbourhood" is reimagined as a series of fragmented clusters. These smaller neighbourhood "islands" are separated by voids, open/ravine-like corridors that intertwine with streets and pedestrian routes. The voids operate as unclaimed yet collective space, forming fractal patterns of courtyards and public realms that host temporal programs with overlapping cycles of activity. By preventing continuous, undifferentiated massing, these voids allow the city to breathe ecologically, socially, and spatially.

Site *B* demonstrates this vision at the block scale, a city within a block. The site footprint extends across the full 130m length of the block and is subdivided into 35m x 35m modules, separated by two 12.5m-wide pedestrian streets. This module is mirrored across the east–west axis, reinforcing walkability and permeability within the larger block.

Timber is central to the project, specified across multiple building typologies: tower-like courtyard apartments, loft-style block buildings, and hybrid mid-rise forms. Site B, together with sites A, C, and D, anchors a larger cluster system, extending connections to neighbouring islands and embedding itself in a dynamic, relational urban fabric.


On the block's north side, two *L-Shaped Courtyard Buildings* frame a shared collective space. Each L-type is defined by a taller north-facing wing and a lower street-facing leg, with open sides oriented inward. Circulation is organized through single-stair towers with open internal walkways overlooking the courtyards. At the hinge of each L, stair and elevator cores integrate with screened façade elements that act as environmental modifiers.

Between these two L-shaped types sits the *Tower as Block/Loft building*, a modular structure that spans the full depth of the block. Its recessed ground floor accommodates colonnaded service areas, an adaptable makerspace, and a food hub or supermarket. Above, the second floor provides office space, while the upper levels house loft apartments. A communal roof terrace extends from the tower's upper wing, providing elevated outdoor space and reinforcing the project's emphasis on collective living.

The sponge landscapes and courtyards integrated into the *L Building* typology serve a dual purpose: they provide welcoming spaces for community use while also functioning as stormwater collections systems. Beneath the new urban fabric, an integrated system can capture and direct runoff, facilitating the hydrological support of adjacent forest fragments and reinforcing the ecological integrity of surrounding neighbourhood clusters.









Larger Courtyard

Plinth + Trellis









Laneway Housing Single Storey Arm



1.

Maker/Service Space //
An all-inclusive space for small markets, events, and individual creators. Also being a service area for the supermarket and block maintenance.

2.

The open wood loggia becomes a protected space for civilians to walk and gather. It provides privacy for the commercial/amenity spaces while reducing heat gain when screens are used. 3.

Community Spaces
between 'L' buildings can
be connected through
bridges. This allows for
easier travel and more
socialisation, while framing
areas of the block.

4.

This trellis + courtyard space, and rooftop is just one option that this building type can take for in. This creates another space that can be used for several events, activities, or just for leisure.

5.

The shared car-pedestrian path puts focus on a transit/bike oriented neighbourhood. This lowers carbon emissions and allows for more space to be allocated to people and greenery.

•


The frieze screen and semi-outdoor walkways act as a privacy facade for the residents. This mechanism not only provides privacy but aids in heat control through light control and provides more space.

Site B's architecture integrates single-point stair access, L-shaped courtyard buildings, and loft blocks to express both social and environmental values. Its tectonic character is articulated through frieze-like façade screens, semi-outdoor walkways, timber loggias, courtyards, and an adaptable maker/service spaces. Degrees of enclosure and ownership provide residents with flexible opportunities to appropriate space according to need and desire. At the block scale, the integration of trees, varied building and courtyard orientations, and a shared car-pedestrian path create layered experiences and adaptable patterns of use across time and situation.


Our methodology for *Site B* has been an open search for diverse solutions at both the block and half-block scales. We explored a spectrum of massing conditions and building typologies, from patchwork groupings to singular standalone forms, before applying a set of repeatable yet varied types. The aim is to demonstrate how local standard mass timber sizes can generate meaningful, affordable, and well-designed urban environments. This approach highlights the compositional richness of the system, offering strategies not only for *Site B* but also for broader application across the city's patchwork of clusters and islands. The existing grid would cease to function as the primary organizing framework, instead serving as a foundational principle subject to adaptation, interruption, and unforeseen interventions. *Site B's* city block, within the context of a larger cluster, would no longer be regarded simply as parcels for construction but as a flexible, "combinable archipelago." In this way, the city block transforms into a tool for compositional exploration.

Within *Site B*, these alternatives are distributed to create new intensity and diversity, replacing the single-house block with a more complex system of open spaces, public realms, and civic elements. Select forest fragments, an expanded common bridge, new parks, stellae and a major transit hub which includes the tree library as structural lattice, strengthen the city-river relationship and anchor the site within its ecological and cultural context. *Sites A, B, C, and D* maintain their existing locations but are reinterpreted through modular and repeatable types that adapt to each condition. Together, they form part of a larger archipelago cluster, where each site contributes a distinct role within the collective whole.

Our design also responds to TOA tiering by accommodating a range of building heights and densities. The combined cluster of $Sites\ A+C$ in Tier 1 features 12–20 storey buildings, $Site\ D$ explores a mix of 8–20 storeys despite being within Tier 3, and our main site, $Site\ B$, in Tier 2, contains 8–12 storey buildings. Despite these variations, the patchwork archipelago shares common architectural elements such as sponge courtyards, loggias, commercial and community spaces, and a diverse mix of housing typologies.











Timber as catalyst opens new possibilities for public design by shaping infrastructure, parks, and monuments. Through this lens, $Site\ A+C$ is envisioned as a dense, connected cluster where streets, buildings, and parks interweave to create generous public space for community use and adaptation. $Site\ D$ acts as a mediator between city and river, introducing a continuous public path and a series of waterfront parks.

An expanded bridge becomes both infrastructure and civic stage that supports safe travel and is capable of hosting celebrations and events. The stellae reinterprets timber as monument, expressing its structural and material qualities in a vertical landmark. Across all sites, the integration of forest fragments elevates timber's role further: serving as local resources, ecological patches, and carbon-sequestering landscapes embedded within the urban framework.

timber as catalyst an URBAN EXPANSION

timber as catalyst a TREE LIBRARY

British Columbia is home to some of the most revered and majestic trees, deeply rooted in the cultural and spiritual lives of Indigenous peoples. These trees such as the Western Red Cedar, Douglas Fir, Lodgepole Pine, Sitka Spruce, and Arbutus, hold profound significance, shaping not only the landscape but also the history and traditions of the region. The tree library/park showcases these trees in a monumental park setting under and between a timber lattice. These trees have provided materials for shelter, clothing, tools and art as well as for building homes, tools, and boats as well for holding lodges and tipis. The are living symbols of strength, wisdom and spiritual connection, deeply intertwined with the cultural heritage and natural history of the region. For Indigenous peoples, these trees are holding practical resources and sacred beings, reflecting a profound respect for the natural world.

The Tree Library/Park celebrates this heritage by showcasing these species within a monumental park, framed beneath and between a timber lattice. More than a collection, it is a place of teaching and storytelling, where histories and traditions are shared through audio, signage, and immersive experiences. It is both a gathering space and a living archive, demonstrating the ecological benefits of forests, their role in climate resilience, and the enduring potential of timber as a building material.



















DTT-B-04

Fantastic Future (FF)

- Provide the opportunity to do more than live affordably in poverty
- Moving from Affordable to Wealthy
- The most valuable resource in a region is an educated population



Our Goals: Aggressive Affordability, Seriously Sustainable, Radically Reproducible, Exactly Entrepreneurial

Development Scenario

Private Training Institute

Objective: Deliver housing that enables residents to afford more in the future

Design Priorities: Efficient construction, Maximum affordability, Minimum operational resources

Secondary Goal - Find ways to make society more affordable.

Is it possible to reduce the cost of living in Canada? Part of the reason that labour is cheaper in China and other countries is that the cost of living is lower. If automation and AI are reducing the need for labour, wages will not go up. How do we reduce the cost of living without reducing the quality of life and eliminating opportunity?

Is it possible to reverse the supply chain issues that enforce large markups at each step until everything is more expensive in North America than the rest of the World? Can we enable convenient cooperation or reintroduce competition to reduce costs? Can we buy directly from farmers and eliminate the multiple middlemen that raise prices by over 300%? Can the ability to handle large volumes reduce markups and transportation costs?

For a staggering 97% of recorded human history, power rested with hereditary landowners who ruled a dependent peasant class. This chilling historical precedent raises a critical question for the future: Can we avoid simply replacing the old feudal system with a new one, where robot owners rule a permanently unemployed class, locking us into yet another era of inherited, centralized control?

Indigenous statement

Site B is located on the unceded, ancestral, and traditional territories of the xwmə0kwəý əm (Musqueam), Skwxwú7mesh (Squamish), and səlilwəta¾ (Tsleil-Waututh) peoples.

At Fantastic Future (FF), our ambition transcends mere affordability. We're not just building housing; we're cultivating a launchpad for boundless futures, free from financial constraints. Rejecting the illusion of affordability created by subsidies, Fantastic Future works to offer a radical vision based on long-term feasibility and independent operation.

We understand that hope, not just happiness, is the true bedrock of a life worth living. Experts agree: a happy life thrives on hope. Consider the stark reality of social media: even those with outwardly enviable lives can be deeply unhappy when their goals feel out of reach. Hope is the fuel for aspiration.

That's why FF is designed to ignite a critical mass of hopeful entrepreneurs. We know entrepreneurs represent the largest class of millionaires, outnumbering even CEOs and trust fund beneficiaries. To foster this vibrant community, FF will operate as a Private Training Institute under BC law. By strategically setting tuition below \$4000, we bypass the BC approval process, giving us the freedom to hand-pick every student and resident. Residence will be capped at five years, ensuring a dynamic, forward-moving community. And while primarily student residences, units can also be rented to the public, offering flexibility and integration.

Floors	#	Ht	Total
Timber	12	11	132
Concrete	3	16	48
Total			180

Affordable for All				
Min Wage/Hour	\$17.40			
Monthly Wage	\$3,010.20			
Affordable Rent	\$903.06			
Net Pay after tax	\$2,515.88			
Rent	\$600.00			
Food	\$800.00			
Tuition	\$100.00			
Transit	\$46.00			
Cellphone	\$30.00			
Total Expenses	\$1,576.00			
Savings	\$939.88			

		G
		(
C	Ctatamant	

Supplier Statement
All technology used is currently operational and 95% non USA

Construction Cost			
	Concrete	Mass Timber	FF
FSR	5	5	9.7
Below Grade - Concrete	75,000	75,000	72,000
Above Grade - Concrete	127,700		108,000
Above Grade - Timber		127,700	245,952
Total SF	202,700	202,700	425,952
Saleable/rentable SF	108,545	108,545	165,600
Amenity - SF	850	850	29,200
Units	86	86	960
Beds	178	178	1,440
Hard Cost	\$75,622,000	\$80,170,100	\$122,888,480
	Project Co	ost	
Months	18	16	10
Land	\$13,000,000	\$13,000,000	\$13,000,000
Soft Cost	\$11,343,300	\$12,025,515	\$18,433,272
ACC/DCC	\$3,168,326	\$3,168,326	\$0
Financing	\$6,852,512	\$6,380,835	\$3,869,896
Project Cost	\$109,986,156	\$114,744,792	\$158,191,658
Cost/SF	\$1,013	\$1,057	\$955
Cost/Unit	\$879,326	\$932,210	\$128,009
Cost/Bed	\$424,843	\$450,394	\$85,339
% more/bed	497.83%	527.77%	
Embodied CO2 - KG	1,355,864	546,112	2,529,306
Carbon KG/SF	6.69	2.69	5.94
Carbon KG/Unit	15,765.86	6,350.14	2,634.69
Carbon KG/Bed	7,617.22	3,068.05	1,756.46
% more CO2/bed	333.67%	74.67%	

Aggressively Affordable

- Affordable shelter, food, water, transport No excuses
- Trying to solve a problem, not all problems. Perfection is the enemy of good
- Buy in bulk, avoid the poverty tax Smaller volumes cost more / unit

The goal is to make FF affordable to anyone with a minimum wage job. This will not solve all problems for everyone. Perfection will not be the enemy of the good.

Rooms - University students are satisfied with residence accommodations. The target is a price less than that of a university residence, food plan, laundry, and transit. The maximum lease term is 5 years. FF is not intended to be a permanent solution. It is a stepping stone. The rooms will be 150 SF with a window or 195 SF double occupancy without a window. All rooms have a private bathroom. The soundproofing will be the luxury suite level of STC 60 and IIC of 66.

Rooms are 10'x14' or 10'x19.5' with 10' ceilings for more vertical space. All beds can descend from the ceiling, Murphy style, or over desks. Extra people cost \$100/month. No pets.

Options:

- up to 2 queen beds
- up to 4 Twin XL beds bunk bed style
- Expanding conference table can fit when beds are up

Food - FF offers food plans and 24-hour food options to compensate for no private kitchens. Bulk purchasing is much cheaper. If Thailand rice is purchased/shipped by the 27ton 20 container, it costs ½ the \$1/lb at retail. Similar discounts can be had for other products when bought by the container.

In discussions with a local greenhouse, FF can save 50% over grocery stores while helping the greenhouse expand by signing long term contracts. The over rice special will be a single, inexpensive, nutritious daily meal option for those without food restrictions.

Transport - A discounted Translink pass is mandatory. Modo EV cars, Gogoru scooters, Silence EV cars, ebikes, etc. will be available for rent. The ability to handle containers up to 40' TEU size makes FF radically cheaper to operate.

Communications - Free Wifi, cheaper cellphone coverage through a Mobile Virtual Network.

Building Amenities - The primary fitness area is in the basement with a full selection of fitness equipment and shower facilities. The basement shower, toilet, and sink facilities are built into containers so they can be moved outside to support street festivals. The food court is open 24 hours for gatherings. There is a nearby park and riverfront recreation areas.

Absolute minimum - Staying in the capsule room in basement, shower at the fitness center, and eating the over rice special will save \$900/month. 4/room will cost only \$250/person.

Is 150SF too small?

The 140SF UBC Nanosuites include a kitchenette, bathroom, desk, and murphy bed. In studies, residents are very happy due to privacy and low cost. FF rooms will be similar with better sound proofing, transit options, and entrepreneurial facilities.

Capsule hotels in Japan are as low as \$20/night. Panda Pods in Richmond costs almost \$100/night. FF will also offer them in the basement. It will be mainly for conferences. There are several hotels completely underground in Copenhagen.

A German UBoat of 1500SF held 35 crew. Crew slept in 43 SF stacked 3 high next to torpedoes for up to 6 months without windows, showers, food choice, or fresh air. Cruise ship rooms are about 160SF and 30% windowless.

Floors

Common Area 1 - Free shared kitchen and seating area. There is a stove, oven, microwave, air fryer, dishwasher, washer-dryer, and an assortment of cooking tools. Most people will use the wash and fold service in basement. Robots will deliver laundry to your room.

Common Area 2 - Lounge area, cafe dishes/laundry/storage box/trash dropoff, and expanding furniture storage. Robots will pickup automatically from here so it won't open your room.

Automation

Room Delivery - The elevators are designed to be used by wheeled robots. Room doors slide so robots can deliver goods without human intervention. This also enables on-demand storage. You can request that a storage box be delivered to your room from the AutoStore storage in the basement by a robot.


Drone Delivery - Sending and receiving products via a quadcopter reduces traffic, cost and time.

Vending machines - Small quantity purchases come from vending machines for 24hr access.

CO2 Kg/yr in operation	Ave YVR	FF
Products, recreation, and services	3,800	1,900
Flights	2,100	2,100
Food	2,200	1,200
Fuel for cars	1,400	0
Home heating and electricity	1,400	200
Bus, transit, and rail travel	270	270
Total per person	11,170	5,670
Ttl savings for FF residents KG/yr	0	7,920,000

Rooms	SF	Monthly
UBC	140	906.34
SFU	103	1040.00
Panda pod	24	2898.00
Best Western	350	7501.00
APT Living	150	1500.00
FF - Window Rm	140	600.00
FF - Inside Rm	195	700.00
FF - + 1 person		100.00
FF - Capsule	24	300.00

Meal Plan	Monthly
UBC	\$918.76
SFU	\$820.25
Meal kit - meat/veg	\$719.20
Fresh Prep - meal kit	\$904.00
FF - Standard	\$800.00
FF - 3 standard, 4 vege	\$600.00
FF - Vegetarian	\$500.00
FF - Over rice special	\$200.00



- Maximum automation
 - Faster is better
- After conducting a survey of successful mass timber projects and consulting with local experts on best practices, we applied these insights to our development scenario.
- The basic design came from a tour of Fast/Epp. We modified their basic design from the BCIT residence. Each floor is 10 feet tall, which makes routing the utilities through the hallways easy instead of inside walls. Kalishnikov told us that tailoring our mass timber sizes to their manufacturing machines would save 15-20%
- To save time on the foundation, FF will use the WeiBuild rebar robot. It will read the plans, cut, and bend all the rebar segments. The rebar will be tied together with a tomorobot. It will reduce the time and manpower by 35%.
- For the tower, the bottleneck is the crane. Singapore has developed the Skyjust AI automated crane. It will bring a prefab component to the correct location without the need for a crane operator or two people using guide ropes. This reduces crane time by 25%. Since it is computer-controlled, operating more than 1 at a time is easy.
- The key to fast assembly is prefab. However, volumetric prefab achieves speed at the cost of high transportation costs. Low on site labor cost is replaced by drivers. FF uses efficient panelized prefab walls and floors from Kalishnikov with cladding from Centura.
- The most labor-intensive, expensive part of housing is the bathrooms and kitchens so FF uses a prefab pod. The Smart Bathroom Pod provides the water source heat pump for environmental control, Internet, TV, sensors, lights, and power in one quick install. Automated sliding room doors are integrated into bathroom pods with lower slider for automated deliveries. Energy savings are controlled by the sensors in the pod. The pod is connected to hallway utility chases that runs under a drop ceiling. The only additional work that would be additional power outlets farther into the room.
- If a different building was designed using the kits of parts and a similar design with less ambitious goals. The underground section would exist for parking and the podium would exist to provide services and amenities to the residents The Broad Group's achieved a build speed of 10 prefab steel stories in 1 day. FF should be able to build a 12 story mass timber tower in less than a month. The cost/bed could be 20% less with a less expensive podium.

Smart Bathroom Pod

Pod is 8.5ft tall to fit in 10' tall room Hallway is 8' with 2 foot chase above it. Water source heat pump on top for heating/cooling.

Water and power connections to chase above hallway. Waste water passes through floor into lower unit before connecting to hallway.

Internet is wired for reliability with a separate secure internal network.

Fire Sprinklers - inside and top SW corner Exterior N side has a NFC reader to control the motorized door. There is a smaller automated door for robotic deliveries.

There is a smart mirror for messages, calendar, general information, and pod configuration.

Optional kitchen pods

On the S wall, exterior connections exist for a small or large kitchen pod.

Goal: To complete all required connections with 1 installation

Construction Schedule

8 days to install each elevator/stair metal frame - 2 - 6 story pieces

Mass-produced building components

Rebar cutting/bending and wiring robots reduce labor time by 30%. After it dries, the concrete floor, walls, and ceilings will be ground and polished by robots for 80% labor savings.

DTT-B-04

- BCIT Tall Timber did 20K SF of CLT per week. The Singapore-proven automated Skyjuster cranes reduce crane time by 25%. It is possible to operate more than 1 crane at a time without risk of collision. With a floor plate of 16K SF, each floor should take around 3 days.
- Bathroom Smart Pod installation is significantly faster than traditional on-site bathroom construction. While a traditional bathroom installation can take up to 25 days and involve multiple trades, a bathroom pod can be installed in as little as 2 hours, including crane time and connection.
- A kitchen takes from 2-4 weeks, but a pod can be installed in a day. FF will have a single kitchen pod per floor, lowering the cost/SF.
- Robots would polish, paint, and carpet the concrete
- Robots for drywall and painting will speed the finishing.
- The first version would take around 10 months with pre-planning. Subsequent versions with better efficiency and a smaller podium would take less time.

Fire Prevention

Besides the sprinkler system, FF has outside wall hydrants with battery supported power outlets. The main limitation of drones is battery power and payload capacity. By supplying the Chinese flying drone with water and power via a hose, it can either fight fires for hours without landing or clean the side of the building. FF water and power will be able to power fire fighting drones up to 500m away.

Standard room

- · A queen size bed
- Desk undeneath bed
- Bathroom Pod
- Dresser
- TV



Seriously Sustainable

While the brief focuses on embodied carbon in the build, sustainability is about the whole lifecycle including operations. It is easy to minimize carbon per SF by adding space. If nobody lives there, it will be low carbon too. FF calculates based on resources/person. FF will save by operating with hotel efficiency.

Build - FF does not eliminate concrete because the program space is required. The strength and durability of concrete will be necessary to support flying cars and shipping containers. The timber portion is highly reproducible and can be quickly erected. The higher CO2/SF is due to luxury partition standards.

Power - Electricity from BC Hydro is 98% renewable. Onsite energy generation would not be significant and would increase maintenance costs. Most new clean power projects are indigenous owned and 45% cheaper than the past. Hotels save 20% of power by turning off power to vacant rooms.

Transport - The rental EV fleet has removable batteries. During a recent earthquake, Taipei used the Gogoru scooter battery charging banks for emergency city power. Battery banks will make FF more efficient and resilient through off-peak charging. Passenger and cargo drones will bypass gridlock. To encourage cycling, three Giken automated bike parks will securely park 612 bikes and retrieve in an avg of 8 secs. Of non-air travel carbon, FF reduces CO2 by 60%.

Cargo - Trucking requires 25 times as much carbon to transport 1 ton per mile as shipping. Shanghai is 5X as far as Los Angeles, but it causes 5X less carbon. As a bonus, there are fewer tariffs. Cargo containers are the most efficient method of cargo handling so FF can handle 40' containers. 28%-50% of transport carbon is attributed to the last mile due to numerous small package deliveries.

Carbon - The average Metro Vancouver resident generates 5.2 tons of carbon per year, not including products and services purchased from elsewhere. FF can easily eliminate the 2.8 tons used for cars and home heating. With another 2 tons from food and shared resources, the estimated carbon reduction is 51% or 5.47 tons/person/yr. Slow behavioural changes should increase savings by another ton/yr.

Food - In Canada, 41% of food is avoidably wasted. A lot of it ends up in landfills despite composting programs. One study indicates that the average Canadian's total food carbon footprint is 2,270 kg of CO2-eq per year, with meat products accounting for 61%. If FF can reduce waste, meat consumption, and transport CO2, it would save over 1 T of CO2/person/yr. Ea ton of food waste = 3 tons of CO2.

By using long-term contracts with local greenhouses, FF can save close to 50% on produce while helping the greenhouses expand capacity. EV trucks will eliminate CO2 from transport to the Fraser Valley

Shared Resources - How often does a stove, laundry machine, or dishwasher get used in the average home? FF reduces surplus purchasing/carbon by providing shared usage of laundry machines, kitchens, manufacturing tools, storage space, etc. For example, by aggregating most of the compute power of FF in a local containerized water-cooled cloud, waste heat can be collected for use.

Trash - Each Canadian throws away about .5kg of garbage/day and a third comes from packaging. Small grocery store items have a lot of packaging. Instead of buying small quantities wrapped in plastic and Styrofoam, FF buys large quantities in up to shipping container size.

Water - Metro Vancouver uses 384 L/day/capita. A Metro Vancouver hotel resident uses 85 L/day. By using grey water retention, hotels save an additional 25%. The grey water tanks will also retain rainwater to avoid overloading storm drains.

Refuse, Reduce, Reuse, Repurpose, Recycle - The 5Rs are built into every decision in FF. With storage, tools, and expertise, whatever FF can not repair and reuse, can probably be recycled. Residents will be encouraged to use materials for their ventures. There is a refill shop in one of the retail spaces.

- Minimize Construction Carbon
 - Prioritize the reduction of operational resource usage

DTT-B-04

Do both on per capita basis

Heating/Cooling - Water Source Heat Pump (WSHP)

A wshp is quieter, smaller, requires less maintenance, and is 10x more efficient than an air source heat pump. It is slightly more expensive. Each room will have a WSHP connected to the building water loop and the hallway for ventilation.

Instead of adding an expensive geothermal loop, FF will use a wastewater energy transfer system like the False Creek Neighbourhood Energy Utility. Heat is extracted or dumped into the sewer system. An additional cooling feed will come from the river.

Large heat source water tanks will make sure that FF always has hot water. Some rooms will be hotter than others and when cooling the building, the heat can be extracted to heat water. The computer server room, kitchen, and manufacturing equipment will be very hot. The commissary kitchen has large cold rooms. The heat taken from these sources can be used to heat other rooms or water.

A healthy building should have at least 5 air changes per hour. FF will exceed that standard with large air ducts running down the hallways. The heat recovery ventilation system and dehumidifiers will maintain the air at a comfortable temperature without excess heat loss or gain.

While concrete creates a heat island, mass timber has 1/10 the thermal conductivity. FF adds greenery to the concrete portions for attractiveness and to reduce heat.

Construction vs Operational CO2

The base case for concrete would cost 7.6MG of CO2/bed. For mass timber construction, it will be 3.1MG/bed. A saving of 60%. FF will use 1.75MG of CO2/bed for a savings of 77% over concrete and 43% over straight mass timber. This is despite having a massive concrete podium, more internal wall, and thicker floor. Per capita is the only fair way to measure CO2 usage.

In operation, the building will reduce CO2 by 5.7Mg of CO2/person/yr vs the average in Metro Vancouver. Using a conservative occupancy of 1440, FF will save the entire CO2 construction budget in less than **4 months** by moving people into the building.

There is an incorrect assumption that electric passive houses solve all operational environmental costs. People don't just sit in warm homes. They need transport, food, etc.

FF is not the solution for all cases. It tries to solve it's use case really really well.

Annual	YVR	FF	Ttl FF in KG	% Reduction
Trash - Kg	183	73	66,576	60.00%
Water - L	140160	23269	29,853,806	83.40%
Food Waste - Kg	396	158.4	203,227	60.00%

Exactly Entrepreneurial

- With AI and humanoid robotics, only entrepreneurs are automation proof
- Try to mitigate as many barriers to success as possible
- DTT-B-04
- For ea \$ spent, how much stays in community? Large Co=14%, Small Co=48%

At FF, we've engineered more than just a residence; we've crafted an entrepreneurial ecosystem where growth is inevitable and opportunity is ever-present. Our rigorous vetting process ensures a community of driven business builders, with a specific commitment to supporting Indigenous entrepreneurs.

This isn't passive learning; it's an active immersion: every meal features industry-specific networking tables , and every weeknight offers free talks on cutting-edge opportunities. The pace accelerates with Friday company pitch nights and intensive weekend sprints dedicated to launching new ventures. Capping it all off, Sunday evenings are reserved for crucial funding pitches.

Our model is rooted in powerful economics: unlike large corporations that recirculate only 14% of their revenue locally , small businesses keep a robust 48% within the community. By fostering more unique small businesses, FF directly contributes to a richer, more dynamic local economy and a truly vibrant community.

5 E's of Startup Creation

Education: Residents can offer paid or free classes, benefiting from an expanded network. Free evening talks are available for convenience, and mentors are matched with residents.

Evaluation: Weekly pitch meetings provide feedback on ideas from industry experts.


Experimentation: This phase focuses on achieving product-market fit, which can be costly and time-consuming. FF offers affordable solutions: retail options available for short-term rental (a day or less), less expensive prototyping tool rentals compared to purchases, and volume discounts on components and ingredients. Keeping burn low is critical during this stage.

Execution: After product or service testing, the next hurdle is building the founding team. FF's network helps connect individuals with skills to contribute to new ventures, even if they don't have their own startup idea.

Expansion: FF partners with various groups to assist with funding, manufacturing, and sales channels.

Facilities - available for rent

- Coworking
 - Offices
 - Meeting rooms
 - Classrooms
 - Print Shop
 - Video, podcast studios
- Shipping/Receiving/Storage
 - The purchasing dept will aggregate orders to reduce cost/CO2
 - Drone delivery
 - Cold storage for volume food handling
 - Storage for up to 40' containers
 - Parking for commercial vehicles
 - · Automated cargo pod handling
- Manufacturing
 - Commercial Kitchen
 - Tool Library for small tools
 - CNC machines for wood, metal, fabric, 3D printing, electronics, etc
 - Workshops for prototyping robots, vehicles, metal, wood, etc.
- Retail
 - 6 Food Court stalls
 - 13 Popup stores at street level
 - Offer a single product for sale in refill stores
 - Vending machines for automated retail
 - Trucks and carts available for rent to test mobile retail
 - Fulfillment service for online stores
- Compute
 - Local Cloud Servers
 - High speed Internet with satellite backup



E-Battery Swap for E Bikes and scooters

- R-Popup Retail
- V-Vending Machines
- P-Automated Package Pickup/Dropoff
- B-Automated bike park, ATM, and basement fire escape stairs
- F-Food Stalls

Unique Features

Storage container lift can raise/lower a fully loaded 40 foot container to the 2 basements

Exterior Utility Connections - Between each storefront, there are water, power, and drainage connections for street vendors or RVs Drone Umbilical Connections - Each corner supports tethered fire fighting/rescue drones.

Plausible Project

- A plausible project should include the land, hard costs, soft costs, and financing.
- Land around the skytrain is going for \$13M per acre. Site B is a little under an acre.
- FF is a Private Training Institute with below-market affordable housing. Metro Vancouver has a policy of waiving the ACC/DCC charges for below-market housing and student housing. The savings are estimated at \$35M due to the large number of units. There will be other development charges but they will be negligible compared to the ACC/DCC charges in other development scenarios.
- The project is eligible for 100% construction financing through the CMHC Student Housing Loan program. After construction, it would be eligible for a 50 yr mortgage. Reducing build time and using CMHC financing reduces the financing cost considerably.
- To further reduce costs, anything that can be sponsored will be. It will look like a business school where every meeting room, wall, and chair has a sponsor logo.
- With an estimated project cost of **\$158M**, the Cap Rate will be approx 5.35%. Once the residents get businesses started, the cap rate should rise to 10%. The average cap rate for rental property in Metro Vancouver is around 2.2%.

The calculations use 1 person per room. Our projection is that it will be closer to 1.5 per room not including the capsule rooms that we expect to be mainly used for short term stays.

FF Rental Cap Rate				
Project Cost	\$109,986,156	\$114,744,792	\$158,191,658	
Rent/unit/month	\$3,000	\$3,000	\$650	
Added revenue/mon			\$932,000	
Total Revenue/yr	\$3,096,000	\$3,096,000	\$18,672,000	
Expenses/yr	\$774,000	\$774,000	\$9,712,800	
Cap Rate	2.11%	2.02%	5.66%	

Future Proofing

Flying EVs - Self driving cars will increase the number of cars on the road. Higher Density means slower traffic. Fast transport will fly. Drone ambulances will be necessary.

Drone Ports - The drone ports on the podium and roof can launch and receive drones like in Schenzhen for 10 min package delivery to your room. Automated cargo and battery swapping.

Exterior Utility connections - Mobile businesses can park nearby without annoying generators. The neighbourhood can be reconfigured daily.

Container modularity - Need more fridge space, add a reefer container. More capsule hotels, more compute, more bathrooms, etc. All in containers. Drop them down to the basement. Remove when done.

AutoStore - This Norwegian company stores boxes 4x as efficiently as ordinary racks. Rain gear can be stored for use when needed. Rental items can be retrieved by robot.

City Scale Utilities - City scale utilities are less expensive than building scale and can be managed by highly skilled professionals with proper backup.

Automated doors - Allow robot delivery to your room of packages, laundry, and storage boxes.

• Community support

• No subsidies required

• Boost Metro Vancouver Economy

Community Links

The street side of the building is designed to be walkable and inviting with 10+ doors per 300' of frontage. The basement container washroom facilities can be moved to the street for inexpensive festivals and connected to municipal utilities via our outside connections. Our bulk deals enable us to offer discounts to nearby businesses and residents.


FF living will not be for everyone. Memberships, classes, equipment rentals, products, and food will be sold to non-residents. This will ensure that the facilities are utilized to capacity, maximizing revenue.

The outdoor large screens will provide information on events, flash sales, news, and important sporting events.

Rules that should be changed

- No strata units without kitchens Less expensive strata units enable ownership
- Max of 4 bedrooms per self-contained residence unit off campus.
- Tower max floor plate of 8000 SF Floor plate sizes enabled by better fire protection.
- Allow zero lot lines
- Farms can only sell 10% of their produce directly. By BC law, the rest has to go through a marketing board, which marks it up.

Our housing regulations are a self-inflicted wound, directly obstructing affordable housing and escalating homelessness through arbitrary occupancy limits. This isn't accidental; it's the stark consequence of municipalities prioritizing 'minimums' over the fundamental right to shelter. We must redefine our approach, moving from superficial appearances to genuine safety, prohibiting only true hazards and allowing dignified, modest living instead of forcing people to live on the street.





Decoding Timber Towers

The Urbanarium has inspired designers to pioneer affordable, low-carbon mass timber buildings that harness modular, prefabricated methods - transforming challenges into opportunities to fight climate change and redefine housing.

The Problem

High-rise buildings today rely on carbon-intensive concrete and steel, which are costly to construct and maintain. Inflexible designs limit adaptability, locking in embodied emissions for decades. Current ownership models often prioritize short-term sales over long-term stewardship, discouraging the use of sustainable materials, shared amenities, and adaptable layouts that are essential for reducing cost, carbon, and environmental impact.

An emphasis on efficiency over quality of life has produced isolating, single aspect units, deep corridors, and minimal outdoor space. Fixed layouts restrict resident agency and future adaptability, while a lack of shared spaces weakens community, disconnecting buildings from nature and the public realm.

The Solution

TwoUp envisions a living future rooted in nature: a mass timber superstructure with panelized light-wood, adapable, double-aspect, double-height subspaces designed for versatility, ventilation, and daylighting. A structural grid accommodates both residential and future commercial uses, allowing the building to evolve as community needs change. Proposed co-housing and rent-to-own units can adapt over time — shifting from open, airy live/work spaces to two-storey homes, or even commercial suites — cultivating a biogenic community with long-term resilience.

Through simple, repeatable forms, vibrantly composed to shape inviting spaces in-between, we can weave vertical villages - places where movement and gathering foster connection. In doing so, we nurture healthy communities while tackling the challenges of affordability and climate change.

Project Data

Site Area ◇ 36,600 SF <	Project Area > 146,766 SF <>	Floor Space Ratio
Occupancy	# of 2-Storey Flex Units	Saleable
Residential	80 🗀	86,697 SF
95% (100% Capability)	Number of	Levels Below-Grade
Commercial 5% (100% Capability)	Storeys 18	00
Site Coverage	\$ Cost 431/ft2	Efficiency



x 🔎








Single I Double


Standardized
15'-6" x 11'-4" grid to
accommodate flexible
living spaces and future
commercial uses.


Living grid





Baseline floor plate
Panelized modules
stacked and assembled in
baseline 6,500 sq.ft tower
floor plate sizes.
















Volume = 1575 cu.ft Floor Area = 175 sq.ft Total Buildable = 350 sq.ft




Volume = 3150 cu.ft Floor Area = 350 sq.ft Total Buildable = 700 sq. ft



The 'NODE' PLUG-IN Volume = 1080 cu.ft Total Buildable = 120 sq.ft \$+/- 410 per sq.ft

Municipal Carbon Targets



Resilient Frameworks

The simple grid can unlock the potential for high-density development without rigidity. Its clarity enables efficient stacking and repetition, while a two-storey framework can introduce vertical flexibility to shift between residential and commercial programs. This approach balances density with adaptability, ensuring buildings can evolve as urban needs change — from maximizing housing supply to accommodating future workspace or shared uses. Rather than prescribing fixed outcomes, the system offers a scalable, resilient strategy for intensification that remains open to long-term transformation.

Deconstructing 'The Baseline'

Converting a typical base-case concrete highrise to mass timber using a simple grid could reduce embodied carbon by 20%, but this approach does not fully address climate resilience or social sustainability. What if the building were broken into smaller, stacked volumes with generous outdoor circulation that encourages social interaction and provides better access to outdoor spaces? Such circulation could support dual-aspect units, offering natural ventilation and daylighting, improving resilience to climate events like power outages while reducing reliance on mechanical systems.

Meeting the City of Vancouver's 10% embodied carbon reduction target—and aiming for 40% by 2030—required a rigorous, holistic approach. While our massing strategy offered key social benefits, it increased the envelope area, partially offsetting the carbon savings from switching to mass timber. To counter this, we prioritized low-carbon assemblies and targeted reductions across the structure, envelope, interiors, and building services.

Recognizing that structure and envelope alone don't capture the full picture, we adopted a broader life cycle lens, including service life and interior systems, which can have equally significant carbon impacts.

Our double-height circulation strategy cut circulation material use by 50% per floor. We reinvested this into generous, social corridors, and by placing them on the exterior, we reduced conditioned space by 20%, improving passive performance.

TWO UP Timber

41% less whole life carbon


Dissect

B. The massing is broken down into smaller volumes, offering dual-aspect floor plates that maximize daylight, ventilation, and views. Simplicity of form ensures construction efficiency, while the composition can create a more human-scaled rhythm.



Re-Arrange


C. By redistributing and pulling apart the building volumes, pockets of 'negative' space emerge outdoor rooms and circulation zones that invite neighbors to pause, connect, and build relationships, fostering a friendlier, more connected community.






Place

D. Volumes are angled to invite the community in, enhance streetscape vibrancy, and optimize unit performance by improving aspect, privacy, and



Site B



- Located in TOA Tier 2
- Within 5 minute walk of rapid transit, shops, services and greenspace.
- Large block-end assembly of sixe 50' x 122' lots.
- North-facing peoperty fronting onto local residential street with lane access at the rear.

Amenities

Neighbourhood

- 1 x Street Plaza
- 1 x Cafe
- 1 x Event Space
- 1 x Bathhouse
- 1 x Childcare





- 1 x Bike Amenity
- 1 x Flex Space 1 x Work Space
- 1 x Community Kitchen

City Farming # of Grow Boxes



Gathering Space

28,362.9 SF



Vertical Village Size

144-200 Ppl







Development Scenario

Rent-to-own: Rent-to-own and co-housing - Rent-to-own helps tenants build toward ownership, while co-housing fosters shared, socially connected living with collaborative spaces and resources.

Commercial and community spaces: Shops, services, childcare, and shared amenities like a community kitchen, rooftop garden, and flexible workspaces support both rent-to-own and co-housing models, strengthening social connections and community ties.



Loose Fit, Long Life

Carbon & Cost Reduction Rational


The most sustainable building is the one that already exists, the next most sustainable building is the one that will stay in use for a long time ensuring its materials remain in use. The best way to do that is to make it the space adaptable to change.

Building Elements with different service lives can be easily disassembled from one another Building as inventory - giving materials identity and value for re-use. Building and un-building - building sheathing, structure (longest lasting layer - 150 years) remains and can be adapted for commercial or residential uses.


Tree-to-Trade


This approach shapes the design and construction by embedding regenerative materials and ensuring that every part of the tree is valued. From structure to finish, and even through the reuse of by-products, we are demonstrating how sustainable forestry can generate high-performance architecture while minimizing waste.

This process not only reduces carbon and celebrates renewable resources but also strengthens the trade industry—showcasing how regenerative practices can drive innovation, economic growth, and ecological resilience.



Hierachy of Net Zero Design






Unlocking the Potential for Mass Timber

Decoding Timber Towers

To fully realize the benefits of timber high-rises, several existing barriers must be addressed. A framework that advances sustainable design - including a change to FSR rules, greater allowable timber exposure, single-stair strategies, stricter carbon limits, and expanded performancebased fire and bio-based material approvals - can better support the growth of the industry.

- Flexible density tools for FSR calculations Vancouver zoning currently counts exterior circulation as FSR, which limits open-air design. Allowing these areas to be excluded, and calculating FSR based on potential floor area while valuing usable exterior space, could unlock greater creativity and efficiency.
- Material Usage and Compatibility Supporting Mass Timber higher buildings that combine light wood framing with mass timber requires updates to current code requirements. Mass timber could provide primary load-bearing capacity, while light wood framing could support non-structural partitions, façade elements, and interior finishes.
- Safety through innovation Single-stair strategies and performance-based approvals for bio-based materials need to be more aligned with global best practices.
- Climate accountability Stricter embodied carbon limits and encouragement of regional sourcing to strengthen local economies and reduce transport impacts.



Level 05 Plan



Level 01 Plan

- 01 East Lobby and Bike Amenity
- 02 Street Plaza and Courtyard Gardens
- 03 Wetlands
- 04 West Lobby
- 05 Cafe

- 06 Services/ Loading 07 Exterior Walkways/Gathering
- 08 Double-Height Lofts
- 09 Public Rooftop Gardens
- 10 Circulation Stairs



DTT-B-05






Connecting People and Space

Dual-Flow Community


This community fosters sociability through circulation and visual connections that also serve as gathering spaces. Arranged as micro-villages or community plateaus, it cultivates a biogenic sense of place. Dual-aspect units maximize daylight and airflow, promoting comfort, well-being, and a stronger connection between people and their environment.

The Model Ahead

TwoUp reimagines high-density living as adaptable, resilient, and community-focused. Replacing rigid, carbon-intensive structures with flexible mass timber superstructures, it incorporates light-wood frame prefabricated double-aspect homes and thoughtfully designed shared spaces, maximizing the efficiencies of mass timber fabrication and minimizing waste. This vision integrates sustainability, affordability, and well-being, creating vertical villages that evolve with residents' lives while reducing environmental impact.



KEY INTENTIONS



Our proposal balances cost competitiveness with constructability by adopting a hybrid system: one level of below-grade concrete parking and a concrete elevator shaft for resilience and code compliance, paired with an above-grade superstructure of prefabricated mass timber. This strategy reflects current market practice while unlocking timber's economic advantages where they matter most.

The project is located in Vancouver, BC, where both provincial and federal subsidies and grants are available to accelerate the adoption of mass timber. British Columbia has a strong regional CLT supply chain, lowering transportation costs and providing competitive pricing compared to imported products. Together, these factors make timber not only technically viable but financially attractive today. Looking ahead, as with any technological advancement, the cost of production will decline as economies of scale take effect. Even if subsidies and grants are phased out in future, the industry will be in motion, and the regular manufacturing cost of standardized timber components will naturally come down.

COST OPTIMIZATION TECHNIQUES



pre-fab MEP riser







pre-fab bathroom pod

CATEGORY	CONCRETE	CLT	SAVINGS
STRUCTURE	Cast in place slabs and Rebar ~ \$110/sf	CLT slabs +beam/columns frames ~ \$90 / sf	~\$20/sf
BATHROOMS	On site trades, coordination risks	Prefabricated Bathroom Pods	~\$2-3 / sf (~\$6-8k / unit)
KITCHENS	Varied layouts, bespoke millwork	Standardized kitchens in all units	~\$1-2 / sf (~\$1-1.5k / unit)
FACADE	Curtain Wall ~ \$70 / sf facade	Panelized timber wall + punched windows ~ \$50-55 / sf	~\$8-12/sf GFA
GLAZING RATIO	~ 65-70% WWR, Larger HVAC	~ 40% WWR, smaller HVAC	~\$5 - 7 / sf
INTERIORS	Full drywall, suspended ceilings	Exposed CLT Soffits, reduced finish	~\$3 - 5 / sf
MEP	Conventional risers, long runs	Prefab risers + shorter runs	~\$2 - 3 / sf
SCHEDULE	~ 18 months	~14-15 months (20- 25% faster)	~\$12-15/sf
GC OH&P	~5% of direct costs	~4% (lower risk + faster build)	~\$4/ sf

BC Housing, "Comparative Feasibility Study for Encapsulated Mass Timber Construction" (2020) found timber 7-10% more expensive than concrete. Our design applies the recommended optimizations (prefabrication, panelized façade, reduced connectors) to achieve ~7-10% lower costs than concrete



5% CHEAPER THAN CONVENTIONAL CONCRETE



40% - 50% LESS GHG **EMISSIONS THAN CONCRETE**



20% -25% LESS SCHEDULE **CONSTRUCTION TIME**




LIFECYCLE SAVINGS


Less maintenance, Simpler MEP, Less Operational Expenditure



BIOGENIC CARBON SINK CLT locks in CO2 for the life of the building



On carbon performance, the whole building (with 1-level concrete parkade and shaft) achieves a 30-35% reduction in embodied carbon compared to a full concrete baseline. Above grade, where mass timber displaces concrete, the reduction is more pronounced at 45-50%. Mass timber additionally acts as a carbon store, sequestering biogenic carbon for the life of the building. Optimized façades (~40% glazing) further reduce operational carbon by 10–15%, cutting long-term emissions.



DESIGN R

Three key ideas:

Higher density development, balanced with areas of nature, is good for city-building and city-living.

Simple, efficient, economical developments are wonderful canvases for colourful, inspiring, and culturally expressive buildings.


Inviting neighbours to share on-site green, open space and witness or participate in cultural activities follows the BC Indigenous Housing Society's Seven Laws of Life: Health, Happiness, Humbleness, Generations, Generosity, Forgiveness and Understanding.

Our proposal locates the building close to the front street to optimize open space. This open area, without the constraints of a parkade, will support mature trees and a patch of nature as an antidote to urban living and a welcome new green space in the neighbourhood.

We intend to provide a comfortable living space for residents, spaces where residents can spend time together and share cultural practices, if they choose to. The natural area is populated with a variety of seating and gathering spaces which would be shared with the surrounding community. Daycare for 25 3-5 year olds is located on the rooftop.

The landscape and building design offers something special to the neighbourhood in the spirit of inclusion and reconciliation





clothesline

structure



pathway and

sitting nodes

stairwell





roof plan

off-hours)

north / street elevation east / neighbour elevation south / lane elevation

pre-drilled screw

intumescent

ioints

CNC Cut

tape maintains

fire separation at

engineered wood

screw holes align with holes at

CNC cut 5-play

engineered wood

beam tab fits

in notches at

column

column

CLT slab

CNC cut

Project Statistics

122'-0" Site: Depth: Length: 300'-0"

Site Area: 36,600 sf

Setbacks:

5-0" North 6'-0" West East 27'-6" South 63'-0"

54'-0" Building: Depth: Length: 266'-6"

Height: 11 Storeys + Rooftop Amenities

11'-0" floor to floor (133 ft)

FSR:

Floor Area:

11 9.980 sf

Residential + Circ 7.240 sf 2.290 sf Lobby / Lounge Sauna 450 sf

12&3 13.880 sf 6.940 sf / floor Residential + Circ 6.940 sf

14-11 113,200 sf 14.150 sf / floor Residential + Circ 13.910 sf Shared Lounge 240 sf Shared Balcony 240 sf *

* Not Included in area

112 6.640 sf Rooftop Amenity Childcare 2200 sf

1750 sf Kitchen & Laundry 2290 sf Lounge Circulation 400 sf

Gross Area: 143,700 sf

Unit Mix:

1-Bedroom: 95 2-Bedroom: 26 2-Bedroom + flex: 11 3-Bedroom: 28 3-Bedroom + flex: 8

Total Suites: 168 Units

Site Description The site is situated on a corner site in Transit Oriented Assa Time 9

Oriented Area Tier 2, within 200 - 400m from the local skytrain station, allowing for maximum FSR of 4.0 & maximum height of 12 Storevs. A low-density neighbour on the east side is assumed.

Building Form and Location

The building is simple and compact to maximize the building economy. A 28'-6" setback on the east respects the privacy of the neighbour and accommodates a parking ramp. Underground parking is limited to one level and exceeds marginally beyond the building footprint to provide optimum conditions for tall and mature tree growth.

Dwelling Units

grid

11,-6"

grid

11.-6"

The development supports a range of households including larger families. Flex spaces suitable for home offices, kid's homework, play rooms, guest rooms, media/tv, etc. are included in a selection of 2 and 3 bed units. Ground oriented units serve seniors and families.

Units do not include private balconies. Large shared terraces are provided as a convenient outdoor space for residents on each floor.

1 bedroom

flex: bedroom office playroom 2 bedroom

mass timber

grid including

and a one-bed

unit








3 bedroom + Flex




2 bedroom + flex

3 bedroom



all wood connection

diagram











DD-LF-C3U6-The Ancestral Peaks







Carbon Reduction Rationale: Mass Timber & Optimized Performance

The commitment to a low-carbon future is central to "The Ancestral Peaks." The building's structure primarily proposes Cross-Laminated Timber (CLT) walls for rigidity, forming the central "spine" of the structure and providing vertical connectivity for services and piping elements.

Prioritizing mass timber construction, a low-carbon solution that aligns with traditional Indigenous respect for the land. While an elevator core necessarily uses concrete, the extensive use of CLT significantly reduces the embodied carbon compared to conventional concrete buildings. Aiming to integrate 100% Indigenous-sourced timber into the project, supporting Indigenous procurement throughout the value chain.

Beyond material selection, the building's strategic orientation and façade design are outcomes of rigorous natural illumination simulations. These simulations demonstrate an overall daylight autonomy of up to 73.3%, achieving 2 LEED points and maintaining an average illuminance of

This maximizes natural light penetration, reducing reliance on artificial lighting and minimizing operational energy consumption, contributing to long-term operational efficiency and a lower carbon footprint. The southwest-facing primary frontage of Site C is carefully managed with high-performance glazing and integrated shading strategies to mitigate solar heat gain while still optimizing daylight.



2017 m3 (71239 ft3) of lumber and sheathing





1919 metric tons of CO₂



741 metric tons of CO₂



2660 metric tons of CO₂

Equivalent to:



562 cars off the road for a year 🕜



Energy to operate 281 homes for a year 🕜



Structural and environmental strategy



Structural cores in concrete and







Daylight autonomy





Innovation in Systemization and Standardization

merely as a standalone building, but as a proof-of-concept for a revolutionary approach to mass timber construction, deeply rooted in principles of Design for Manufac-turing and Assembly (DfMA) and Design for Disassembly (DfD). The systemization strategy is the cornerstone of the project, demonstrating how a data-led approach can transform design and production processes in the Architecture, Engineering, and Construction (AEC) industry.

Design for Manufacturing and Assembly: Every component, from the cassette walls to the CLT floor panels and facade elements, is designed with its manufacturing and assembly process in mind. This means optimizing for standardized dimensions, minimizing waste during fabrication, and simplifying on-site construction sequences. This systematic approach significantly reduces construction time and costs, enhancing overall project efficiency.

Design for Disassembly: Looking beyond the building's initial lifespan, DfD principles ensure future adaptability and resource recovery. The smart joinery and modular nature of the cassette system mean that components can be easily deconstructed, replaced, or repurposed at the end of the building's life or for future renovations. This minimizes demolition waste, supports a circular economy, and allows the building to evolve with the needs of its occupants and the changing urban context.



The Cassette System:

A Code-Compliant, Digitally Fabricated Core. Drawing inspiration from previous innovators such as the WikiHouse project, the interior wall system is based on a code-compliant cassette system. This system primarily utilizes CNC-cut structural plywood panels, having the potential to use other structurally-sound materials. These panels are designed with "smart" and high-performance joinery components, ensuring precision and allowing for rapid assembly with minimal specialized tools or heavy machinery.

This approach directly addresses the challenge of reducing reliance on highly skilled on-site labor. The cassettes can be flexibly assembled either off-site as prefabricated panels or on-site, offering adaptability to various project logistics. The emphasis on accessible, sustainable, and modular construction, directly aligns with modern methods of construction (MMC) and prefabrication principles.

Façade module distribution is illustrated

through color-code, where each color corre-

sponds to a specific module type, material, or

Complementing the system, the building facade employs prefabricated ZIF walls produced off-site. These high-performance panels contribute to rapid enclosure, superior thermal performance, and quality control, leveraging the efficiencies of off-site manufacturing. This integration ensures

CLT Floors and Columns:

The structural backbone; while the core employs concrete for elevator shafts, the primary horizontal and vertical load-bearing elements beyond the core are comprised of Cross-Laminatal rigidity and excellent carbon sequestration properties make it an ideal choice for a sustainable mass timber tower. The use of CLT in a systematic, grid-based layout allowing for predictable fabrication and assembly sequences, further integrating with the modular logic of the overall building.

High-Performance Joinery:

The success of a highly systematic and modular timber construction relies heavily on robust and intelligent connections. The "smart joinery components" within the cassette system and throughout the CLT connections are designed for rapid, precise, and secure assembly. Drawing inspiration from leading manufacturers like Rothoblaas, known for their advanced timber fastening and connection systems. These engineered connections facilitate quick erection, ensure structural integrity, and embody the DfMA principle of ease of assembly.

Design for Disassembly (DfD) & Adaptability:

The DfD principles embedded in the cassette system mean components can be easily replaced or reconfigured over time, enhancing the long-term adaptability and resilience of the building. This reduces future renovation costs and material waste, aligning with long-term sustainability and operational efficiency.

cohesive and high-performing building envelope.

Modular Logic


Cassette assembly

CNC-cut cassettes

Low skills needed to assemble a cassette

The entire building facade configuration is achieved using a system of 13 modular units, al-

lowing for efficient spatial organization and scalable design flexibility.



NINE WAYS TO GROW YOUR CITY

Current responses to the housing crisis, ecological crisis, and construction cost and labour issues too often miss the forest for the trees—focusing on each crisis in isolation rather than on the underlying systems. The narrow focus on present-day technological capabilities lacks the transformative vision needed for real impact. Designers and constructors can do more to contribute to affordability than squeezing already-too-austere condos. Likewise, governments can do more than sink funding into a broken system while remaining unable to address root causes. It's time to grow a new vision from the ground up.

Growing Cities

Nine Ways to Grow Your City outlines a hopeful new model for urban growth—plentiful housing, crafted from high-quality materials, designed to lock away carbon as it is built—all rooted in a new system of design and construction. It goes beyond mere technical excellence, simultaneously strengthening communities and creating conviviality.

Growing Cities

Cities can work more like ecosystems: grown, not extracted. This shift to a bioregional, biomaterials-based construction ecology begins with timber and expands from there, reshaping our connections to the ecologies to which we belong.

Redesign Design, Reconstruct Construction

These budding transformations need fertilizer and a structure to guide their growth. *Nine Ways* proposes a **platform**: a systems-scale intervention that provides the tools and the framework to get everyone pulling in the same direction. It reshapes incentives, open-sources expertise, and systematizes successes.

The approaches on the slides that follow already exist: we already know how to do this. By reshaping the playing field, the platform directly confronts the true, systemic challenge—coordination and organization.

Nine Ways to Grow Your City illustrates a series of tangible yet systems-scale actions that can be taken, right now, to begin the transition to a new system of construction, a new era of affordability, and a new weave of ecological and social dynamics.

AN OPEN. SHARED INFRASTRUCTURE

Our Platform

Nine Ways operates above the scale of individual projects—operating directly on the systems that determine whether projects and technologies are feasible. It is a platform in a double sense: a shared infrastructure for change, and a focused set of imperatives.

1) targeted policy changes to reshape incentives and regulations, and

2) a unified digital-organizational tool to transform design, permitting, and construction systems (divided into the three key components shown to the right).

A Platform for Everyone

Built on open-source principles, the platform rejects privatized monopolies and proprietary, fragmented technological approaches. It embraces platform cooperativism and the right to participate, ensuring its governance, goals, and mechanisms of change are collective and able to be shaped by

While envisioned as initiated by government and with substantial involvement from all levels of government via incentives and regulation changes, ultimately the platform would be guided by its own public-private representative body. In this way the platform can remain shared, adaptable, and held

We're Already Doing This

There is an astounding amount of work currently underway to sew the seeds of this transformation. However, these efforts are currently scattered, siloed, and often competing. The platform builds on these existing initiatives and technologies, coordinating them and providing missing links.


Weaving Together

The platform brings these efforts together, weaving them into a coherent whole. The challenge is structural. To meet it, we need a visible hand guiding the invisible one-rallying around a shared vision and guided collectively by the platform.

Keep the Change

The platform builds in openness to change, with robust feedback loops as part of its core structure. It becomes a machine for initiation, ideation, innovation, iteration, and implementation-working small and multiple, feeding off its successes and making them part of the next round of its operation





A standardized and interoperable set of prefabricated mass timber and building envelope elements, allowing for efficient, factory-built construction systems. Free flow of data streamlines design, construction, and product development.

Existing References


- Prefab systems: UK Construction Playbook/MMC; Construction Innovation Hub
 Componentized prefab: typical mass timber products, standardized connections
 Panelized prefab: Platforms for Life (Intelligent City), CREE, CLIPs (Element5),
- speedwall (Flynn), UnitiWall, Stora Enso, · Volumetric prefab:







Type 2: Panels



Type 3: Volumes

INCENTIVES & REGULATORY CHANGES

A framework for aligning policy—providing financial incentives and streamlining approvals processes. An a la carte menu: the more that are implemented, the more robust the transition will be.

> Existing Implemented At Platform Launch

- Provincial
- Federal

Municipal

- Broadway Plan Upzoning (YVR)
- Transit-Oriented Area legislation
- Training Grants
- Timber Building Research
- Research Grants Material Testing Grants

- Timber Density Bonuses Expedited Development Permits (Catalogue Projects)
- Expedited Building Permits (Catalogue + Kit Projects)
- Design/Construction Prequalification
- Timber Building Code Optimizations
- Timber Density Bonuses in Transit Zones
- Buy Bioregional' Incentives
- Platform Participation Incentives Prefab Housing Funding
- Timber / Prefab Housing Tax Rebates
- Biomaterial Research + Startup Grants

Phased In Steps

- Material Reuse Incentives & Reg's Parking Reductions
- Design/Construction Prequalification

Olow Omed Ohigh

- Timber Building Code Relaxations
- Embodied Carbon Step Code
- Resilience Requirements
- Pilot Project Funding
- BIM Implementation Road Map
- Pilot Project Funding
- Harmonized National Standards
- 'Sell To The World' Grants

Platform Planks: Objectives and Underlying Concepts

On the pages that follow, the nine key Planks underlying the platform are elaborated and

These Planks are loosely grouped into three underlying shifts:

- new communities of construction
- new economies of construction
- new ecologies of construction

These shifts and their associated Planks guide the detailed development of the platform and its evolution over time.

Narrative Tableau: Following a Project Through the Platform

The Planks are paired with a tableau telling the story of one illustrative project as it works its way through the process of construction—illustrating its exchanges with the platform as it goes.


The project is envisioned as taking place roughly ten years into the adoption of the platform, at a stage where its systemic impacts have begun to manifest but early enough to remain applicable to the current context.

Site and program were specifically chosen to test the limits of the system's flexibility and ambition:

Site: Site C (irregular shape, no lane)

Development scenario: Indigenous Housing Provider (KKS Nations) + Co-Operative Housing +

Non-Housing Program: Significant community gathering spaces and social programs per the brief, an Indigenous community organization in the podium, daycare, and CRUs.



I. NEW COMMUNITIES OF CONSTRUCTION

The platform reshapes communities related to the construction industry in a variety of ways—from new communities of knowledge, based around open cooperation and new forms of design and construction expertise, to new communities of production, based around shared goals, incentives, and interests, to new communities of shared well-being, through the creation of dense, vibrant, and culturally-responsive cities.

Plank 1: Share Knowledge Freely to Build New Norms

The platform's open-source Knowledge Base democratizes access to expertise. Coupled with an iterative process of testing, pilot projects, and training, new communities of practice take form. Timber and prefab knowledge becomes non-proprietary, familiar, and accessible.




Plank 2: Create an Innovation & Implementation Infrastructure


The platform serves as an incubator for new construction ideas, enabling rapid testing and deployment. It provides structured pathways and incentives for both projects and products, supporting research, scaling, and commercialization while driving demand.



Plank 3: Foster Shared Benefits for BC Communities

The platform helps ensure the transition to a biomaterials-based economy benefits all. Off-site fabrication can empower Indigenous and rural communities and create value-added jobs in resource regions—enabling autonomy while easing pressure on urban centres.





A. Consulting the Catalogue

The owner begins pre-design in the platform, drawn in by its reduced costs and ease of use. Options are tested, metrics explored, pro-formas re-formed, starting points developed.

B. Developing the Vision

Now equipped with Catalogue outputs, the client engages a design team to incorporate elements of the client's vision that were beyond the scope of the initial study.

C. Flexing the System


Working with the Platform gives the design team a head start on the design. They iteratively shape its outputs in response to site conditions and design aspirations.

II. NEW ECONOMIES OF CONSTRUCTION

The platform reshapes design and construction systems in a variety of ways—from new economies of housing production, reducing housing cost by building more efficiently and shifting the cost-innovation curve, to new economies of building, transitioning to modern methods of construction, to new economies of global exchange, repositioning BC and Canada as global experts in this new era of construction.

Plank 4: Re-Tool Construction to Lower Costs and Scale New Approaches

By standardizing components and prefabricating off-site, the platform cuts costs, waste, and timelines. Starting in high-cost markets like Vancouver sustains new products until technological development and economies of scale make them viable in more affordable regions.



Plank 5: Adopt New Methods of Construction From the Field to the Factory


The platform enables a series of key shifts in construction: from on-site to off-site prefabrication, from one-off projects to standardized systems across builds, from fragmented teams to integrated collaboration, and from disconnected tools to BIM-enabled workflows.



Plank 6: Build Local Expertise & Sell it to the World


The platform develops local expertise, creates a homegrown market for BC's timber sector, and helps tariff-proof the economy. It also boosts exports of high-value products and expertise, positioning BC and Canada as leaders in sustainable construction and the global bioeconomy.





Structural Axonometric

Housing Levels: Mass Prefabrication Point-supported CLT+MPP floor cassettes Podium Levels: Structural Reconciliation Becomes Flair CLT on glulam beams + transfer-truss frames



Assemblies

- Panelized envelope (BOD: Element 5 CLT
- Panelized dry topping (BOD: Fermacell 2E35 /
- Floor cassettes w/ integrated MEP routing
- Glulam columns / braces / beams
- Glulam brace-frame lateral system Glulam transfer truss @ parkade ramp
- Glulam transfer truss @ CRUs
- Glulam showcase truss at ceremony space
- CLT floors
- 10. Volumetric prefab washrooms + kitchens
- Independent balcony/breezeway structure
- Prefabricated clip-on balconies

Fire and Acoustics

The building acts as a demonstration project, testing fire and acoustics

- approaches used broadly in Europe.
 The building focuses on mitigating fire risk through technical systems, in line with more permissive European combustibility standards. Fire-performance mitigation measures adopted include redundant sprinkler standpipes to increase sprinkler reliability, and increasing sprinkler performance by upgrading the system to Ordinary Hazard standards. Char-layer protection is used instead of encapsulation, except in concealed
- spaces, to reduce embodied carbon and simplify sequencing. This approach supports future code trends and maximizes wood's benefits.

 An alternative solution is needed for exterior combustible materials on a high
- building. The wood is largely separated by noncombustible surfaces and can be treated with fire-retardants. If not accepted, the secondary structure could be swapped to steel with little design impact.

 To reduce embodied carbon, the project uses fire-retardant, waterproof
- In lieu of concrete topping (with its sequencing, moisture, and embodied carbon challenges), the project uses a dry topping commonly used in Europe. It acheives STC 58 and IIC 55 on 5-ply CLT. Assuming it passes CAN/ULC S146, it

Flexible Housing System 0-3 BRs + Lockoff Suites









D. Refining Performance

Through platform-empowered analyses and easily-accessible information from the knowledge base, the team refines the design against carbon, cost, and design targets.

E. Elaborating the Systems

As things progress, technical approaches are integrated with program goals—for example, working the podium structure to achieve an extra-large assembly space sans transfer slabs.

F. Dialing In the Details


The platform speeds the design team through construction documentation, allowing them to draw on robust, certified, manufacturer-provided BIM elements and details from the Kit.

III. NEW ECOLOGIES OF CONSTRUCTION

The platform reshapes larger ecological systems, carbon flows, and material flows in a variety of ways—from new ecologies of carbon sequestration, using buildings as a carbon sink, to new ecologies of material use, diverting waste from around the bioregion to produce new products, to new ecologies of resilience, confronting the effects of climate change by building resilient buildings, landscapes, and communities.

Plank 7: Sequester Carbon in Buildings via a Shift to Biomaterials

The platform leads a shift from carbon-intensive to bio-based construction, starting with timber and expanding to other grown—not extracted—materials. With abundant forests and clean energy, Canada is uniquely positioned to produce low-carbon building materials.



*based on diagrams from UN Environment Programme, "Building Materials And The Climate: Constructing A New Future"

Plank 8: Decarbonize Production and Transform Waste into Novel, Bioregional Products

The platform advances circular material systems by transforming bioregional waste streams (e.g. forest and agricultural byproducts) into healthy, reusable building components. Designing for disassembly and reuse turns buildings into carbon stores and future material banks.



Plank 9: Build Climate and Social Resilience Into Our Communities

Climate resilience grows from strong communities. The platform promotes simple, affordable design strategies that make buildings more climate-resilient, create shared community spaces that foster strong social bonds, and restore the natural ecologies we call home.





G. Fabricating the Kit

Off-site fabrication begins early, with the team selecting a new, fully-integrated First Nations timber co-operative from the Kit suppliers list in the platform.

H. Seizing Opportunities As They Arise

At the last minute, the team gets a Materials Research grant to swap in a new wood-fibre insulation product in the envelope panels. The system is plug-and-play, so change is easy.

I. Closing the Knowledge Loop

The project combines circular material flows with circular knowledge flows—feeding experience, lessons, and data back into the Reuse Bank (and the platform) for the future.

FROM TECHNICAL TO EXPERIENTIAL

Scales of Community

The project constructs community at a nested series of scales, from unit to city: within dwelling units (generous balconies, reconfigurable suites), between neighbours (breezeway porches), on each floor (shared sundecks), within the building community (roof garden, shared kitchens, podium childcare, and amenity spaces), with the broader community of the First Nations tenant (community ceremony space, outdoor gathering circle), and with the general public (corner plaza, boulevards, commercial units, parklet, and creek walk).

Project Data: Refer to boards 3-5 (yes. the data in the narrative is accur

- 1. corner plaza
- 2. restored creek + public boardwalk
- 3. parklet + outdoor gathering circle
- boulevard w/ rain gardens, parking, seating
- 5. commercial spaces (x4)
- 6. community hall + ceremony space for 150 people
- 7. sheltered outdoor gathering space + connection to restored creek
- 8. community kitchen (shared by building and KKS tenant)
- 9. breezeway (open to below) and neighbour porches
- shared sundecks (one per residential floor)
- 11. Sharea sanaceks (one per resider
- 11. studio (425 ft²)
- 12. 1 bedroom unit (600 ft²)
- 2 bedroom unit (875 ft²)
- 14. 2 bedroom w/ studio lockoff suite (1025 ft²)



















SOLIDWOID SITE CSACRED WATERS DEVELOPMENT

A VOLUMETRIC MODULAR UNIT SYSTEM DESIGNED FOR MASS PRODUCTION. EASY TRANSPORT, AND RAPID ASSEMBLY ON CONSTRAINED URBAN SITES

Only One Unit

- A fully prefabricated, standardized, stackable VMU with integrated systems.
- VMUs alternate with 'capped' voids to cut cost, material, and time by 50%.

Flexibility and Customization

- One unit, many outcomes: enables diverse, family-sized configurations.
- Self-supporting at low-rise; can be used in hi-rise with a dedicated lateral system.
- Responds to evolving demographics and multi-generational households.

Prefabrication and Standardization


- Repeatable VMU components and approvals.
- Prefabricated light-framed shafts, metal balconies, shades, and corridors.
- Plug-and-play kitchens and bathrooms enable easy programming.

Biophilic Thinking

- 'Float' the building above the site to preserve ±75% of existing vegetation.
- No underground parkade. Provide ample bicycle storage and car sharing.
- Daylight and restore the historic stream to make it a destination.
- Access via elevated walkways to minimize ecological disturbance.
- Maximize exposure to natural light, fresh air, and mountain views.


Community Commons

- The building is raised to invite visual and physical access to the courtyard.
- A cantilevered gathering space offers year-round community engagement.
- Exterior corridors and communal amenity spaces on every floor.
- Locally sourced CLT, ultra-low-carbon concrete, and EAF steel.






connection demand.



VMUs core, and corner 'starter' walls integrated CLT shear walls 'galleries' of corridors and posts offload lateral loads from the stack in a staggered solid/void complete the lateral forcemodules and counter story pattern. Shear walls run floor- resisting system by providing drift, diaphragm continuity, and to-floor to ensure continuous secondary vertical lateral paths.



stiffness buttressing adjacent modules.





DESIGN RATIONALE: CLIMATE CHANGE & AFFORDABILITY

1) Restore water and make a place of learning.

We daylight the stream and hold a 10m riparian setback, then frame a generous courtyard around it as a 'sacred' garden. This move pays homage to Coast Salish estuarine root gardens - carefully tended places at river mouths and tidal edges - by restoring hydrologic continuity, shaping gentle, walkable terraces for teaching and ceremony, and planting native food and medicine species. In this configuration the courtyard is not residual open space; it becomes a living classroom and community table, honoring Katzie, Kwantlen, and Semiahmoo relationships with water and stewardship.




2) Eliminate underground parking to protect soils and carbon.

Given the site's exposure to active streets and its five-minute walk to rapid transit, shops, services, and green space, we remove underground parkades. This choice cuts concrete volume and reinforcement associated with excavation, protects tree roots and hydrology, and shortens schedule risk. Only essential elements touch the ground: the residential lobby, columns on micro-piles or helical piles with Ultra-Low-Carbon Concrete (ULCC) pile caps, and a two-storey service podium for bicycle and residential storage, garbage/recycling, loading, car-share stalls, and the main electrical and mechanical rooms. The ground-level building footprint is limited to ±25% of the site area. Elevated walkways, built from reclaimed wood salvaged from the demolished houses, thread through the trees to minimize root disturbance and keep the ground permeable.

3) Build an elevated, low-carbon platform and stack modular timber above.


We pour an elevated, cast-in-place ULCC slab-on-frame "table". Beyond minimizing disturbance to soils and drainage, this platform is a carbon strategy. A single core and select corner "starter" walls maintain seismic regularity and limit torsion. Above this, we set Volumetric Module Units (VMUs) - 11'×26' mass-timber boxes - in a unit-10' gap-unit rhythm. When offset vertically, each solid module sits between voids above and below.

The voids become habitable living spaces with high-performance glazing at the exterior and a simple CLT closure at the interior. This preserves daylight and cross-ventilation, reduces the number of volumetric boxes we must fabricate, and maintains a regular, buildable façade cadence.



4) Shape the tower to fit neighbors, make a landmark, and hold community.

The L-form shields the sacred garden from arterial activity, achieving the target FSR, while creating a legible corner marker appropriate to this intersection. The elbow of the L is notched to welcome the community, draw sun deep into the courtyard, and frame a 150-person gathering hall that cantilevers above the restored stream. Constructed entirely in mass timber, this hall is a contemporary echo of Coast Salish longhouse traditions at the water's edge.




SOLIDVOID

DESIGN RATIONALE: CLIMATE CHANGE & AFFORDABILITY (CONT.)

5) Make the homes bright, flexible, and efficient.

Each 11'x26' VMU contains two rooms flanking a 3'-wide service hallway with a continuous wet-wall spine. Floor and roof CLT plates allow a clean, repetitive stack: each module's floor forms the ceiling for the module below; each roof forms the floor above. Light-frame prefabricated partitions (closets, wet walls) focus timber mass where it carries load and simplify rough-in. Primary living spaces face south for winter sun and views toward culturally significant mountain ranges to the southeast. We maintain useful window-to-wall ratios with high-efficiency glazing, thermally broken frames, and airtight factory detailing. North and northeast galleries give residents immediate mountain views as they step outside their front doors and reinforce visual connection to the courtyard below.



Prefabricated metal

balcony installed on site

High thermal performance

assemblies with airtight detailing

Factory-installed high

performance window

The urban Indigenous population is the fastest growing in Canada, with larger household sizes, more single-parent households, and higher rates of multi-generational living. We organize the VMU kit to combine and reconfigure easily, prioritizing family homes:

- ← For singles, elders, or couples without children
- ← Supports small families and caregivers
- ← Meets core family housing demand
- ← Supports multi-generational, cultural, or extended families



- UP TO 1 BEDROOM
- UP TO 1 BATH
- UP TO 1 KITCHEN



2S + 1V 750 SQ FT

- UP TO 3 BEDROOM
- UP TO 2 BATH
- UP TO 1 KITCHEN



2S + 2V 1010 SQ FT

- UP TO 4 BEDROOM
- UP TO 2 BATH
- UP TO 2 KITCHEN



3S + 2V 1275 SQ FT

- UP TO 6 BEDROOM
- UP TO 3 BATH
- UP TO 2 KITCHEN



3S + 3V 1515 SQ FT

- UP TO 9 BEDROOM
- UP TO 4 BEDROOM
 + 1 LOCK-OFF UNIT
- UP TO 3 BATH
- UP TO 3 KITCHEN






Energy-efficient

glazing installed

on site





SOLIDWOID±40% EMBODIED CARBON REDUCTION

CARBON REDUCTION RATIONALE: STRATEGY + CALCULATION

It quickly became clear we cannot reach the target FSR with VMUs alone due to height limits. We therefore propose a hybrid structural system incorporating Ultra-Low-Carbon Concrete (ULCC) and Electric Arc Furnace (EAF) steel, which still outperforms an industry-standard concrete building by delivering a ±40% embodied-carbon reduction. Our carbon strategy operates across three coordinated levers, detailed below:

1) Material Substitution — Low-Carbon Equivalents

• ULCC.

All structural concrete is the lowest-carbon mix available in British Columbia, with PLC and high SCMs (e.g., slag/fly ash/pozzolans) meeting or exceeding a 30% GWP reduction relative to conventional mixes. Assumed embodied-carbon intensity: 4.5 kgCO₂e/ft² vs a conventional concrete baseline of 6.69 kgCO₂e/ft².

• EAF steel (≥90% recycled content).

Where steel is required (galleries, balconies, connectors, plates, etc.), W specify EAF production routes to minimize GWP. Assumed intensity: 6.0 kgCO₃e/ft².

FSC timber.

VMUs are fabricated with locally sourced, FSC-certified mass timber to support responsible forestry and traceability. Assumed intensity: 2.69 kgCO₂e/ft².



Charred-wood cladding.

Exterior rainscreen uses locally charred wood planks. Typical published ranges indicate charred wood ≈ 10 –30 kgCO₂e/m², compared with fiber-cement ≈ 60 –90 kgCO₂e/m² and metal cladding ≈ 100 –250+ kgCO₂e/m². Charred wood supports ongoing biogenic carbon storage, local craft, and cultural resonance while reducing enclosure-related embodied carbon.

• Thermal performance and operational carbon.

We pair high-efficiency glazing, thermally broken frames, and insulated opaque walls (effective R-values targeted by orientation) to reduce operational energy and resident costs over time. The reduced energy demand strengthens whole-life carbon performance.

2) Efficiency Through Standardization & Modularity

• VMUs and controlled fabrication.

Factory-built VMUs minimize waste and rework; plug-and-play services reduce redundant materials and coordination. The 11-foot module width aligns with CLT panel economy (one standard panel spans the width; minimal CNC off-cut). In a controlled environment with limited weather exposure, module fabrication and set can deliver up to $\pm 50\%$ schedule compression versus fully site-built equivalents.

• Transport and set efficiency.

Two VMUs per 53-foot flatbed (26' \pm 26' \pm 52' load length) avoid special permits/pilot cars and reduce truck trips by \pm 50%. Standardized lift points and rigging allow a typical crew to place 8–12 modules/day with a single crane, enabling rapid dry-in and compressing critical path activities compared to in-situ construction.

3) Site Preservation & Blue-Green Infrastructure

• Vegetation retention.

We target up to $\pm 75\%$ retention of existing vegetation, avoiding excavation-related emissions and maintaining living carbon sinks that continue to sequester carbon over time.

• Daylighted stream and eco-cultural planting.

Reopening the culverted stream supports native species, food-teaching plants, and seasonal gathering—embedding eco-cultural stewardship in daily use while reestablishing riparian function.

• Elevated, low-impact access.

Elevated walkways of reclaimed wood thread above the ground plane, protecting soils and root zones and reducing hardscape area.

• Blue-green water cycle.

Stepped massing and sloped canopies channel rainfall into gutters and rainwater leaders that discharge to the daylighted stream, attenuating peak flows and improving on-site stormwater management and water quality.

EMBODIED CARBON						
		Concrete		Mass Timber		
			Embodied		Embodied	Total Carbon
	Sq ft		Carbon	Total Carbon	Carbon	kg/sg ft
			kg/sq ft		kg/sq ft	kg/sq It
Total Building Sq Footage		113250.0	6.69	757,531.52	2.69	305117.02

EMBODIED CARBON			
Propo	sal (Hybrid)		
	Quantity	Embodied	Total Carbon
Ultra-Low-Carbon Concrete (kg/cu ft)	54055.0	4.5	* 243247.5
Low-Carbon Structural Steel (kg/sq ft)	26150.0	6	** 156900
Mass Timber (kg/sq ft)	32500.0	2.69	*** 87425
TOTAL CARBON			487,572.50

^{*} SCMs + GUL cement (30–40% GWP reduction)

^{**} EAF steel with ≥90% recycled content

^{***} Locally sourced, FSC-certified; can be net-negative if biogenic carbon is included

SOLIDWOID±50% CONSTRUCTION COST REDUCTION

3) Charred-wood cladding is cost-competitive with metal cladding and demonstrates greater durability than fiber cement in lifecycle costing, particularly given reduced

4) Omitting underground parking saves an estimated \$6.3M per level in construction

5) Together, these measures establish a replicable, climate-smart housing approach that aligns with affordability targets while

economically viable without

maintenance and repainting cycles.

ECONOMIC RATIONALE: PROFORMA + COST SAVINGS

- 1) Modular fabrication reduces construction costs and delivery time. With VMUs manufactured off-site, on-site labor decreases and sequencing becomes more efficient. Our estimated cost is \$475/ft² for VMU construction, slightly higher than the \$405/ft² for standard concrete in the competition's base case. However, the solid/void scheme halves the volumetric module count relative to a full-grid approach while preserving rentable area, directly reducing factory labor hours and transport needs.
- 2) An estimated 66% reduction in overall build time lowers construction financing and general conditions. With one crane and a single shift, at a typical rate of 8–12 VMUs per day, VMU placement would take ±4 weeks. On that basis, total construction duration is projected at ±6 months.

expense.

remaining

subsidies.

PROJECT STATS	
FSR	4.4064436
Lot size (sq ft)	20,175
Building sq ft Above Grade	88900
Building efficiency (%)	0.8533183
non saleable/rentable (sq ft)	13040
saleable/rentable (sq ft)	75860
Total Stories above grade (#)	27
Total Stories (#)	27
Base floor (#)	1
Above 1st storey (#)	26
Stories below grade (#)	C
Units (#)	±69
Bedrooms (#)	±183
Amenity space (sq ft)	6100
Non-residential (sq ft)	3385

- Excluding exterior corridors and prefab balconies
- ** Standalone gathering space for income generation

CONSTRUCTION COSTS

- a daylighted stream that revives an important local ecological feature. This 'sacred' garden offers a restorative landscape accessible to residents and the wider community, encouraging outdoor gatherings, casual social contact, and neighborhood events. Seating, plantings, and open-air paths reinforce these connections.

1) The L-shaped building frames a shared courtyard as a civic commons, integrating

SOCIAL RATIONALE: SOCIABILITY & COMMUNITY IMPACT

2) The northeast gathering hall, accessed via a dedicated public lobby, provides a welcoming venue for up to 150 people. The space cantilevers above the rehabilitated stream to pay homage to the relationship the Katzie, Kwantlen, and Semiahmoo First Nations have with water. It establishes a strong visual connection to the courtyard below - envisioned as a green oasis for the community - with an outdoor patio that allows events to spill outside while maintaining that connection.



- Concrete Mass Timber Square footage \$/sq ft Cost \$/sq ft Cost Below grade \$315 \$300 \$1,764,000 \$1,974,700 Base floor 4900 \$360 \$403 \$43,881,750 \$46,698,850 Above 1st storey \$405 \$431 Quantity \$/unit \$/unit \$25,000 \$3,400,000 \$25,000 \$3,400,000 Balconies Cost per month # Months | Cost # Months | Cost \$900,000 Schedule Costs \$50,000 \$1,200,000 \$50,245,750 \$52,973,550
- **CONSTRUCTION COSTS** Unit Price Quantity Cost \$315 Below Grade \$/sq ft Base Floor \$360 \$1,764,000 \$/sa ft Above 1st storey: 47450.0 \$/cu ft \$569,400 \$12 Prefab Steel Corridors, Stairs, & Canopies \$/sq ft \$1.961.250 Prefab Mass Timber VMUs \$/sa ft \$475 \$15,437,500 Prefab Steel Balconies 136.0 \$/unit \$10,000 \$1,360,000 Glazing 1250.0 \$/linear ft \$262,500 Aluminum Guardrails \$/linear ft \$70 \$280,000 Subtotal above 1st storey: \$19,870,650 Schedule Costs \$300,000 \$24 334 65
- - 3) Smaller multi-purpose rooms on each level, plus shared terraces under prefabricated steel canopies, support everyday sociability (crafts, homework clubs, Elders' tea, parenting circles).
 - 4) Cultural continuity is further supported by plantings of culturally significant species—wapato, cedar, elderberry, and salmonberry that support traditional harvesting, medicine, and storytelling. These elements go beyond placemaking; they root the project in layered narratives of land, water, and community memory.



BUILDING CODE COMPLIANCE & CHALLENGES:

1) Compliant as intended:

- Occupancy + High-Building features (Div. B, Part 3 / 3.2.6): Group C residential with A-2 assembly (150-person hall); full NFPA-13 sprinklers, central alarm/voice, emergency/standby power, fire pump, firefighters' elevator.
- Fire separations: A-2 hall separated from dwellings with 2-h construction; independent exits.
- Non-combustible elements: All in-situ concrete specified as ULCC to meet non-combustible requirements while minimizing embodied carbon.
- Spatial planning basics: Gathering hall has independent entrance; residential lobby separated; refuge/areas of assistance planned at core.

2) Where we knowingly do not comply:

- Typical floors currently have only one enclosed stair; the second path relies on open galleries and does not qualify as an exit in a high building.
- Likely travel distance and exit separation shortfalls on some floors given the L-shape and single enclosed core.
- As proposed, adaptability features (clearances, bathroom/kitchen convertibility, door hardware, reinforcements, visitability) are not met for the required share of units.
- At 27 storeys, the proposal exceeds the current BCBC 2024 EMTC storey/height limits for residential. This is a fundamental variance requiring a performancebased Alternative Solution.
- Open galleries at height introduce smoke spread, wind, and ice issues; BCBC treats exits in high buildings as enclosed, pressurized shafts. Current galleries don't meet those criteria.
- Where CLT edges, soffits, or balcony soffits are exposed in the stepped terraces, they may contravene non-combustibility / flame-spread limits for exterior elements on high buildings (Div. B 3.1 / 3.2).
- The staggered glazed voids near property lines may exceed allowable unprotected opening percentages at some limiting distances; water-curtain sprinklers or spandrels will be required, or geometry adjusted.
- At 150 persons, door width, number of exits, exit remoteness, and smoke separation from residential are close to the threshold; any reliance on the open gallery for discharge would not comply.
- With a tall, stepped profile, roof access, standpipe coverage, and safe staging at upper terraces require dedicated measures; current plans do not show roof access routes compliant for firefighting.
- A 27-storey CLT shear-wall system likely falls outside tabulated Rd/Ro values in CSA O86 for this height; code requires modal analysis at minimum, and likely nonlinear time-history with validated CLT wall models - i.e., an engineered Alternative Solution for structural performance.

RELATIONSHIP TO ADJACENT PROPERTIES AND STREETS:

- 1) The project's orientation strengthens connectivity to the existing street network while softening its impact on neighbours. The raised L-form frames the public courtyard along the street edge, creating a permeable threshold between private residence and the public realm.
- 2) Primary vehicular access is from the collector road; the residential entry is from the arterial.
- 3) The massing steps from the low east and north edges—respecting adjacent three-storey buildings—to a 27-storey northwest corner. Visual bulk is reduced through staggered modules and articulated balconies.
- 4) Landscaped buffers, green fencing, and connective pathways encourage interaction while clearly delineating shared versus private spaces. The street-facing public lobby and gathering hall reinforce civic presence, providing the neighbourhood with a visible, functional amenity.



PROJECT DELIVERY & LEGAL MECHANISMS:

- 1) The project proposes a streamlined design-build model using pre-approved prefabricated components. Wet wall modules, CLT panels, and plug-and-play service zones can be batch-certified and repeated across multiple infill sites. This accelerates approvals and enables municipalities to scale up affordable housing with greater speed and quality control.
- 2) Off-site prefabrication is coordinated with minimal on-site disruption, enabling delivery on sensitive or underutilized urban land parcels. The platform structure allows phasing without major excavation or servicing constraints, opening new typologies for hard-to-develop lots.
- 3) Ownership and delivery may be facilitated through partnerships with community land trusts or non-profit development corporations. Leasehold arrangements can retain long-term affordability while supporting Indigenous land stewardship, public sector investment, and equity-based occupancy models.




The Wooden Tower Site C

On the shared territories of the Katzie, Kwantlen, and Semiahmoo Nations

How can we provide reasonably priced housing for the Indigenous people of BC that upholds their core values of respect for nature, family, and community, while utilising the potential of high-rise timber construction?

We propose a four-pronged solution:

1. Use a timber structural system that provides better lateral stability.



2. Combine modular and conventional on-site construction techniques to mitigate the downsides of each method.

Modular construction is highly efficient, but even minor changes often require introducing a new module type.



3. Propose an amendment to bylaws so that balconies are not counted toward FSR.



In a tall building, the balcony is your front yard. A yard isn't counted toward FSR in a house—so why should it be any different in a high-rise?

4. Redefine how the tower connects with the ground.


We could lift the tower off the ground, opening up the first floor!



Proposed Floor Assembly



QR-coded modules and on-site scanning anchor quality assurance, speed installs, and reduce rework.



DTT-C-04









Geometric forms of the structure and the facade connect to traditional Indigenous patterns and meanings.




Cultural symbols are used on the facade.




Interior Floor Plates
The tower lifts on a regular
mass-timber frame so the
ground can work for people
and ecology.


Upper levels and the roof terrace frame the long mountain views.




Proposing FSRexempt Balconies Generous private balconies act as small personal gardens, providing every home with direct access to daylight, fresh air, and nature connection, supporting well-being while meeting Step Code energy performance.



Living façade
Integrated vegetation
enhances biodiversity and
visually merges the building
with its natural
surroundings.
Sun-shaped south façade
and self-shading geometry
reduces heat gain.









Project Data

TOA: Tier 2

Mountain views to the northeast and southeast are available from about 75 ft above grade

Site area: 20,120 sf (~1870 m²) Setbacks: 10 m along north edge (creek buffer) Height: 12 storeys + rooftop common floors*

FSR: ~4.0 (FSR check: 80,514 sf ÷ 20,120 sf ≈ 4.0.)

J14 31 .	10tal arca. 0070 31
	Balconies 2600 sf
I Area R uded)	
	3-Br Studio 1-Br
5 SF	
79 SF	2-Br 1-Br
14 sf	Common

14th

approval 13th Amenities-

> approval 12th

> > 11th

10th

This space serves as an outdoor gathering area for the residents of the floor and their guests. It is in addition to the communal areas provided at the ground level and on the uppermost floors.


Common Terraces w/ northeast and southeast mountain views

Sample floor plan- Level 3 DTT-C-04

of # of Units/ floor Name 3RR Units Total (FSR inclu BASEMENT-1 ~16,103 SF 4,306 SF Level 1-Indoor Amenities Level 1 Building Services 3,229 SF Levels 2-10 Residential 9 UNITS 18 UNITS 18 UNITS 9 UNITS 54 UNITS ~60,030 SF 72,9 Levels 11-12 Residential 2 UNITS 2 UNITS 4 UNITS ~12,949 SF ~32,000 sf Level 13- 14* 6000 sf* Proposed Indoor Amenities 11 UNITS 20 UNITS 22 UNITS 11 UNITS 64 UNITS*** 80,514 sf Totals

- * Proposed Indoor Amenities at level 13 & 14: Subject to municipal approval.
- ** Balconies: Proposed FSR-exempt.
- ***Lock-off studios (flex suites) may be internally connected to adjacent 1–3BR homes to support multigenerational/blended families. (For Elders, caregivers, or returning family members.)
- ****Due to the modular system, unit numbers are flexible and may be adapted to regional demands.












1-Bedroom Unit w/ Lock-off Suite



4-Bedroom Unit



Parkade

Floor Area and Balcony Layout per Level By excluding balconies from FSR, the design enables larger, greener outdoor spaces for every unit even in a 12+ storey building.

1-Bedroom Unit

Family-Forward Housing: Units can expand/contract over time via lock-off suites and connecting doors, supporting multi-generational living without renovations.

WoodWorks

Category	Timber estimate	Concrete baseline	Reduction	Notes
GFA for calculation	7,480 m²	7,480 m ²	-	80,514 sf total area
Embodied A1–A5 (structure + façade + balconies)	2,506 t CO₂e	5,087 t CO₂e	2,581 t CO ₂ e (~50.7 %)	A1-A5 ECI used: 335 vs 680 kg CO ₂ e/m ²
Transport A4 (regional supply)	5.9 t CO₂e	21.6 t CO₂e	15.7 t CO₂e	Short haul to site
Operational, 60 years (all- electric vs mixed-fuel baseline)	471 t CO₂e	1,178 t CO₂e	707 t CO ₂ e (~60 %)	25 vs 50 kBtu/sf-yr, BC grid, natural ventilation paths
Biogenic carbon stored in timber	–1,207 t CO₂e	0 t CO₂e	1,207 t CO₂e	Report as separate memo item
Net embodied after storage (optional reporting)	1,776 t CO₂e	6,286 t CO₂e	4,511 t CO₂e (~72 %)	Includes biogenic carbon stored in timber

How we cut embodied carbon:

Structure: CLT floors with glulam posts and a light timber bracing kit minimize concrete and steel. Small foundations use low-carbon concrete with SCMs. Factory prefabrication cuts material waste and improved quality control.

Façade: Timber modules with plant-based insulation, exterior planted shading, and high-performance glazing lower material and cooling loads.

Systems: All-electric heat pumps, heat-recovery ventilation, ceiling tans, and right-sized equipment reduce operational energy that drives life-cycle carbon.

Logistics: BC-source timber and a flat-pack kit pre-assembled in a temporary on-site workshop cut truck trips, shorten crane time, and reduce A4/A5 impacts. Maximizes use of Indigenous-sourced glulam and CLT to reduce transport emissions and support local economies. Longevity and end of life: Durable finishes, dry connections, and repairable components enable reuse. Biogenic, storage is tracked and reported separately.

Creek: Direct access for residents to the northern Outdoor creek is provided, restoring nunity area native plantings, orchard-like trees, and natural habitat. Indigenous art gallery and retail space, creating an active public realm that invites **Basement-Bike Storage** Itilities, Shared cars parkade visitors to experience, learn, and purchase local Indigenous artwork, supporting cultural number of parking spaces, as sharing and economic opportunities. the project is located in tie

Summary

Preliminary WoodWorks-style accounting indicates about 2,581 t CO₂e avoided in manufacturing by substituting timber for concrete. The structure also stores about 1,207 t CO₂e of biogenic carbon. With stored carbon included, the net embodied total is about 1,776 t CO₂e, roughly a 72 percent improvement versus the concrete baseline. These avoided emprovimately 550 cars from the road for an entire year.

DTT-C-04

Assumptions

12-storey residential tower with cultural podium; GFA for calculation 7,480 m² (80,514 sf); CLT floor plates, glulam posts and girders, prefabricated balcony modules; regional supply with short truck haul; all-electric systems, natural ventilation paths, and a passive-first envelope; ~2,973 m² (~32,000 sf) FSR-exempt balconies. Kit designed to maximize use of Indigenous-sourced glulam and CLT, reducing transport emissions and supporting local economies.



Lifted Ground

A planted, breezy layer of lifted ground tucked beneath the homes. Supported by the timber frame, it becomes a play yard and shared terrace that extends the creek landscape, fostering interaction between residents and neighbours and offering views to the restored creek and surrounding greenery. Open-air, shaded, permeable, and habitat-supporting, it is proposed as outdoor amenity space.













FSR	4.001689861
Lot size (sq ft)	20,120
Building sq ft Above Grade	80514
Building efficiency (%)	85
non saleable/rentable (sq ft)	12077.1
saleable/rentable (sq ft)	68436.9
Total Stories above grade (#)	12
Total Stories (#)	13
Base floor (#)	1
Above 1st storey (#)	11
Stories below grade (#)	1
Units (#)	64
Bedrooms (#)	97
Amenity space (sq ft)	4306
Non-residential (sq ft)	0

_	Bulk procurement of the repeating triangular modules and
╛	
0	standard nodes plus flat-pack delivery with on-site
1	preassembly drops the mass-timber above-grade cost to
7	about \$392/sf.
-	Parallel preassembly of façade/balcony modules shortens the
1	tower cycle from 18 to 14 months and lets MEP rough-in star
0 1 1	earlier, trimming ~\$0.20M in GC overhead. Fewer deliveries

Parallel preassembly of façade/balcony modules shortens th
tower cycle from 18 to 14 months and lets MEP rough-in star
earlier, trimming ~\$0.20M in GC overhead. Fewer deliveries
and crane picks reduce logistics and crane tim
Standardized digital catalogue enables bulk pricing, clearer
bids, and fewer change orders.

bids, and Tewer Change orders.
Indigenous Procurement: Prioritize Indigenous-sourced timber and suppliers across the value chain.
Simplier systems. All-electric heat-pump systems with natural ventilation paths keep OPEX low and maintenance straightforward. Smaller mech rooms return more NRSF to units.

CONSTRUCTION COSTS						
		Concrete	Concrete		Submission	
	Square	\$/sq ft	Cost	\$/sq ft	Cost	
Below grade	16103.0	\$315	\$5,072,445	\$315	\$5,072,445	
Base floor	7535.0	\$360	\$2,712,600	\$392	\$2,953,720	
Above 1st storey	72979.0	\$385	\$28,096,915	\$392	\$28,607,768	
	Quantity	\$/unit		\$/unit		
Balconies	64	\$25,000	\$1,600,000	\$25,000	\$1,600,000	
	Cost per	# Months	Cost	# Months	Cost	
Overhead)	\$50,000	18	\$900,000	14	\$700,000	
TOTAL			\$38,381,960		\$38,933,933	


		Concrete		Submission		
	Sq ft	Embodied	Total Carbon	Embodied	Total Carbon	
Total Building Sq Footage	96617.0	6.69	646273.0453	13.51	1305295.67	i

Quick cost	comparis	on (hard c	osts only)	Γ-C-04
Category	Timber estimate	Concrete baseline	Δ (Timber - Concrete)	Notes
Above-grade construction (80,514 sf)	\$31,561,488 @\$392/sf	\$30,809,515 @\$383/sf	+\$751,973	Repeating triangula kit + standardized nodes; parallel preassembly enables earlier ME rough-in.
Below-grade construction (16,103 sf)	\$5,072,445 @\$315/sf	\$5,072,445 @\$315/sf	\$0	Same scope/quantities below grade (concrete).
Balconies (~32,000 sf equiv.)	\$1,600,000	\$1,600,000	\$0	FSR-exempt privat outdoor areas; livability gain without reducing unit yield.
GC overhead during construction	\$700,000 (14 mo × \$50k)	\$900,000 (18 mo × \$50k)	-\$200,000	Prefab + dry trades shorten schedule (14 mo vs 18 mo).
Total hard cost	\$38,933,933	\$38,381,960	+\$551,973	Includes site overhead only.
Cost per total- built area (96.617 sf)	\$402.97/sf	\$397.26/sf	+ \$5.71/sf	Normalized to tota built area (above + below grade).

Note: "Embodied carbon shown is net after storage (A1–A5 + A4 – biogenic storage), excluding operational (B6). Value normalized over all floors (96,617 sf). Source: WoodWorks. Total \approx 1,305 t CO₂e.









Wood harvested from Pacific Northwest forests.



Sawmill

Sawmill mills trees to lumber for CLT and GLT production



CLT & GLT factory

Dimensional lumber milled for CLT and GLT is sent across the site to the CLT and GLT Factory for pressing into panels.



Module Factory

A prefabricated triangular timber kit integrates structure, façade, and balconies. One standard node and repeating modules ship flat, assemble quickly, and minimize waste. The same parts adapt to the irregular lot and align building services.

Most elements are flat-packed and shipped to an on-site temporary workshop for assembly. Flat-packing eliminates the need for oversized trucks, reducing costs and improving accessibility to more challenging sites.

Bathroom and kitchen units are the only volumetric elements shipped to the site.





Strength in Triangles: Triangular geometry inherently resists deformation, providing strength with fewer members.

Each triangular cell works as a light truss, carrying loads axially to the nodes and limiting bending, which


keeps connections simple and predictable.

With mostly axial forces, many members can be smaller glulam or standard-dimension lumber where spans allow; engineered sections are reserved for longer chords and primary posts.

Less Waste, More Performance: Lighter sticks and compact steel node pieces reduce material cost, crane time, and shop waste while keeping the frame stiff.

Installation


Modules are lifted from the temporary workshop and installed via crane. The kit can be used on other TOA sites with minimal redesign, creating volume for Indigenous-sourced suppliers and reducing unit costs in future phases.




On-site temporary workshop

A temporary workshop is set up on-site. A flat-pack mass-timber kit arrives in dense loads and is pre-assembled in the workshop into façade and balcony modules. This reduces truck trips, shortens crane time, improves quality control, and keeps the site tidy with just-in-time staging.

A shared digital catalogue, QR-coded parts, and on-site scanning support Quality Assurance and make the kit repeatable across sites.



Timber towers are notorious for being too light and having limited lateral stability. This often leads designers to add ancillary systems to increase the building's weight and, consequently, its resistance to lateral forces. The 3D triangular system enhances the structure's lateral stability while maintaining its light weight.



DTT-C-04
Digital Creation: Using a Grasshopper* definition, a planar 60-degree grid is generated. This 2D grid is then used to create a 3D structure, following the same logic in which members are oriented at 60 degrees to each other. This approach allows the structure to adapt to different site conditions and grow in the X. Y. and Z directions, much like a tree.

 * Grasshopper is a visual programming language and environment that runs within the Rhinoceros 3D CAD application. It allows designers to create complex geometries and

Repeatibility: The triangular timber system reuses a small set of parts and dry connections. Fewer unique pieces, fewer crane picks, and simpler Quality Assurance reduce waste and rework.

Repeatable kit → lower costs

Standardization: Standardized digital catalogue enables bulk




Arboria 8

Mass timber is now becoming a mainstream building material. What bold innovations will drive its next leap toward deeper decarbonization and streamlined project design, fabrication, and delivery?

This project endeavours to explore beyond the current scope and limitations of mass timber construction towards enhancing its capacity to address both the climate and housing crises through an innovative and flexible modular approach to multi-unit residential tower design. This customizable "kit-of-parts" design approach is rooted in four core concepts: biodiversity, redensification, monomateriality, and industrialization, that coalesce to unlock a generational shift in the building industry's current perception of mass timber design and construction processes and practices.






Site + Arboretum

The proposed design is deeply integrated within its unique environmental context, and responds directly to the site's existing characteristics. Given the site's heavily treed nature, the project features a ground-floor plan that prioritizes the preservation of the natural landscape while creating a vibrant public space. A central public green space and arboretum are integrated within the podium design, serving as the social and ecological heart of the development. This not only offers a high standard of comfort and livability for residents but also enhances the connection of the site to the land and reinforces the concept of biodiversity.

The podium and tower are strategically designed to maximize views to the mountain ranges to the northeast and southeast of the site. The innovative mass timber diagrid from the tower also extends to grade, blending the rhythm and materiality of the surrounding trees and internal Arboretum with the building's structure, weaving all forms of timber into a unique urban forest.



Monomateriality + Industrialization

The design embraces **monomateriality**, extending the use of wood beyond its structural role to form as many components of the building's physical system as possible. This approach lends itself to purpose-built rental housing by taking a "furniture-first" approach, where the built-in furniture removes the need for disposable pieces, thus also improving the life cycle of the rental units.


This holistic approach is supported by the principles of **industrialization**, which seek to increase adoption through greater efficiencies in manufacturing and implementation systems. Industrialization is the cornerstone of this project, focusing on exploring a more efficient and scalable delivery process for mass timber. The goal being to promote the use of a limited number of optimized components enabling multiple manufacturers to produce the same units, thereby creating sufficient demand to make these units affordable. This system building approach harnesses the efficiency of off-site production and simplifies the design, review, and construction processes, making this approach to mass timber construction a competitive economic alternative to traditional concrete or steel high-rises.


Ultimately, this industrialized method of delivery demonstrated in this design approach streamlines the entire system, paving a clear path towards housing affordability and a low-carbon future.

Biodiversity + Redensification

The design envisions a systems of mass-produced timber apartment units using regional wood resources to address the challenge of delivering high-quality, low-carbon buildings at an unprecedented scale and pace. By **diversifying** the range of wood species used during mass timber manufacturing, the project aims to reinforce local ecosystems, working well within sustainable forestry practices. Varying grades of lumber are also utilized, keeping higher grade lumber at the exterior layers of the mass timber components where higher stress occurs and lower grade lumber within the less stressed interior laminations.

The design also explores the potential for **redensification**, where the modular nature of mass timber products can be leveraged to pre-fabricate entire apartment units. The building's unit makeup is therefore largely flexible and can then be easily selected based on neighbourhood demographics and urbanization requirements.





Affordability

This project prioritizes affordability and acts as a proof-of-concept to encourage developers to consider mass timber as a viable alternative to concrete or steel from a cost perspective and beyond. The design is a response to the "chicken-and-egg dilemma" of demand versus price, where the building itself is a **catalyst for change**. By developing a customizable "kit-of-parts" approach with standardized, mass-produced full apartment unit components, the project aims to **stimulate demand and drive down manufacturing costs**, making mass timber a more affordable and viable building material in Canada and North America.

The design is engineered to **streamline the entire delivery process**. This includes creating low-cost, low-carbon buildings that are not only easy to design and construct but also easy to review and approve - addressing a key pain point for developers and approving authorities. Furthermore, the project reduces life cycle costs and operations through a low dependence on energy sources and a simplicity of systems, ensuring the building is not costly to maintain over time. A detailed proforma provides a tangible comparison to an industry benchmark, demonstrating how this solution contributes to **low-end-of-market affordability** and makes mass timber a powerful tool for a low-carbon, affordable future in Canada.

Construction Costs

		Concrete		Arboria 8	
	square footage	\$/sqft	\$ cost	\$/sqft	\$ cost
below grade	10,549	315	3,322,809	299	3,154,031
base floor	10,549	360	3,797,496	403	4,251,086
above first storey	89,663	385	34,520,409	431	38,644,925
balconies	square footage 10,549	\$/unit 25,000	\$ cost 2,600,000	\$/unit 25,000	\$ cost 2,600,000
	\$/month	# months	\$ cost	# months	\$ cost
scheduled costs (monthly)	50,000	18	900,000	12	600,000
total			45,140,714		49,250,043
cost difference ~ \$4.1M o	r ~ 8% greater co	ost			

Arboria 8

FSR	5.0
lot size [sqft]	20,118
building area above grade [sqft]	100,212
building efficiency [%]	85
non rentable [sqft]	15,032
rentable [sqft]	85,180
storeys above grade [#]	17
total storeys [#]	18
base floor [#]	1
storeys below grade [#]	16
above first storey [#]	1
units [#]	104
bedrooms [#]	164
amenity space [sqft]	8,574
non-residential [sqft]	31,447

#	%	
28	27	
32	31	
28	27	
16	15	
	28 32 28	

Cost Difference

Based on the proforma, Arboria 8's construction costs are approximately **8%** higher compared to a typical concrete structure.

Notably, the innovative use of three major prefabricated building components has been estimated to reduce the construction schedule by **6 months** compared to the concrete structure - an approximate **30% savings** in scheduled monthly costs!

Timber Carbon Storage Estimation



Volume of wood products used: 46,088 ft³ of lumber and sheathing



US and Canadian forests grow this much wood in:

4 minutes



Carbon stored in the wood: 1,000 metric tons of CO₂



Avoided greenhouse gas emissions 2,130 metric tons of CO₂



Total potential carbon benefit 3,140 metric tons of CO₂

Equivalent to:



599 cars off the road for a year



Energy to operate 267 homes for a year

Embodied Carbon + Stage D Circularity Options

This project, rooted in the principles of a **circular economy**, demonstrates a tangible reduction in carbon emissions by utilizing BC-sourced wood for the mass timber superstructure and integrated building components. While the use of a carbon sequestering material reduces the embodied carbon of the mass timber products themselves (LCA Stages A1-A3), locally sourcing the wood for the mass timber from FSC certified forests in BC reduces the embodied carbon of the material during construction of the building (LCA Stages A4-A5) as well.

Where this project models innovative and forward-thinking methods of reducing the building's embodied carbon is beyond the life cycle of the building Stage D: re-use. Similar to concrete, which is often downcycled into aggregate - a carbon-intensive process in and of itself mass timber components can be chipped or pulped for other uses, but this is less desirable than re-use which directly uses existing building components in a new structure, either in their original form or with minimal modification. The customizable 'kit-of-parts' approach proposed allows individual apartment units to be dismantled and reassembled as standalone homes, infill (laneway) housing, or other stacked MURBs typologies, bringing new life to the materials and and whole units. This not only further reduced the building's overall carbon footprint but also creates an ongoing supply of affordable housing stock, turning a building's deconstruction into a new construction opportunity.

Embodied Carbon

	Concrete		Arboria 8	
square footage	kgCO ₂ e	total	kgCO ₂ e	total
110,761	6.69	740,880	2.69	297,946
		square footage kgCO ₂ e	square footage kgCO ₂ e total	square footage kgCO ₂ e total kgCO ₂ e

"River dolphins all over the world (in the Ganges and Amazon Rivers, for example) are not close genetic relatives. But they are remarkably physically similar. They have grown common forms due to their common circumstances.

Have you grown that way, riverine? In a context that moves so quickly that looking at it tells you almost nothing. Are you evolving a deeper way of listening where you are? Could we become students of shape precise enough to move with the grace and flexibility our circumstance requires even though your river is not my river?"

Shaping Our Common Future

can help mitigate climate change and a broader systems-level shift is essential. building process to a circular one (where not diminish it. carbon is continuously cycled through


Make

Use

Take



Dispose



Implementation strategies

Regenerative Design

Regenerative Design is a holistic design philosophy and practice that goes beyond sustainability to create systems, buildings, and communities that actively repair and regenerate ecological, social, and economic systems.

Prefabrication + Modular


Through efficiencies in manufacturing, prefabrication and modular construction have a singular potential to mitigate the economic and carbon cost of providing housing in the future while simultaneously providing a higher quality of construction and project outcomes.

Policy and Collaboration

Regulation and policy are paramount in implementing this framework of consumption which posits the reframing of established processes of delivering housing. Collaboration and buy-in among all parties is critical for success.

Policy reformwork


- Daylighting streams should be encouraged and incentivized through density and height bonuses
- Regulate embodied carbon alongside operational carbon with a lifecycle metric approach
- Reward upcycle and deconstruction efforts through carbon targets. Provision of natural areas can contribute to meeting carbon targets.
- Permit voids within mass timber slabs with acceptable fill materials and stringent safety testing
- Require RFPs for publicly awarded projects to be evaluated on best-value outcomes from integrated teams at the proposal stage
 - Facilitate development of material standards for upcycleable or reusable materials



BEAUTIFUL RIVER

Parti Diagrams


The culverted stream is brought to the surface starting one third of the length of the North property line, establishing a 10.0m setback on the subject site. The buildable area and ecological areas are established.



The site is programmed giving prominence to the KKS Nations Community Hall, from which the new stream emerges from underground. In exchange for daylighting the stream and providing a public park, the project receives a density bonus from the planning authority with jurisdiction.



To accomodate the extra density on the site, the building is proposed at 14 storeys instead of the 12 as recommended by the TOA Tier 2 guidelines. Additional density is at the discretion of the AHJ. To permit the building to have exposed mass timber elements (max. 12 storeys), the building is split in two using an Alternative Solution which allows a fire rated floor to compartmentalize the two buildings from each other.



Solar shading devices are designed for the East, South, and West elevations to ensure a reduction in solar heat gain while ensuring the maximum amount of glazing in the liveable areas. The ration of glazed area to opaque is 70 / 30, which is above average at the request of the client.

of the client, and a public

amenity is proposed at the top


of the building accessible to all

residents to enjoy the beautiful

scenery and awesome sunsets!







A	c		
Area	Summary	Permitted	Provided
Floor Sp	ace Ratio (FSR)	4.0 (+1.0)	4.8
Lot size ((sf)	20,125 sf	=
Building	area above grade (sf)	=	95,544 sf
Building	efficiency (%)	-	84.3%
Non-leas	seable area (sf)	-	15,956 sf
Leasable	e area (sf)	-	80,544 sf
Total sto	ries above grade(#)	12	14
Total sto	ries (#)	-	16
Base floo	or (#)	=	1
Above 1s	st storey (#)	-	13
Units (#)		=	96
Unit Mix	(%)		, 25% 2-Bed, , 25%-Studio
Amenity	space (sf)	=	1,016
Non-res	idential area (sf)		7,762 sf

Building Code	Construction article: 3.2.2	2.93
Summary	B ::: 1/B : 1	

Summary	Permitted / Required	Provided
Building height (storeys)	18	14
Building height (m)	76 m	50.2 m
Building area (m2)	6000 m2	826.2 m2
Encapsulation (floors) (3.1.6.4.(9))	50 min	50 min
Encapsulation (all other)	70 min	70 min
FRR (Floors)	2 hr	2 hr
FRR (Columns)	2 hr	2 hr
STC (All construction)	47 (STC) 47 (ASTC)	47 ASTC

Alternative Solutions

AS1 - P1 to L2 / L3 (partial) are to be considered two separate buildings. Additional fire safety measures and compartmentalization required.

Zoning Relaxations

Tier 2 Minimum Allowable Density Framework

Level 14

4,323 sf

(L3-L13)

6,983 sf

L1 Mezzanine

Level 1

8.893 sf

3,056 sf Community Hall


+ 1,658 sf Bakery + 1,179 sf Lobby

(1,016 sf Amenity)

	Distance	Min. FAR	Min. Height
Prescribed	200-400m	4.0	12 storeys
Proposed	200-400m	5.0	14 storeys

As per the Ministry of Transportation and Infrastructure's guiding document "Provincial Policy Manual: Transit Oriented Areas" issued on May 29 2024, "local governments retain the zoning authority to establish densities and heights greater than those prescribed by Provincial reguations."

In this hypothetical project proposal, we imagine that in exchange for daylighting the culverted stream that exists along the North PL, the authority having jurisdiction will provide a density and height bonus as incentive to restore the ecological functions historically provided by these natural features.




Prefabrication + Modular

From assembly line to assembly line


Prefabrication and modularity is an integral component of circularity in the building environment. Mass timber is an inherently prefabricated and modular building system, and yet many projects in the Lower Mainland still resort to traditional methods of connecting the mechanical, electrical, and plumbing services and finishing the interiors once the envelope is delivered and installed. We propose to continue the assembly line from the factory to the building site, and apply the same principles of efficiency to the interiors and building services.

Break the module


One important consideration we made was to make our interior module smaller than the typical structural grid. With a width small enough to fit inside a cube truck, the smaller modules allow for a greater variety of producers to participate in the production of interior modules. The hybrid volumetric module we designed breaks the rigidity traditionally associated with modular design and allows for flexibility within the floorplans and assemblies.




Structure, Envelope, and Balconies



Structure is comprised of GLT columns and CLT slabs which will form a ribbed cassette once the interior module is placed.




envelope panels
consisting of fibreglass
window wall and steel stud
framing. The steel stud curb ensures
that installation does not require
custom attachments and is installed
like a typical window installation.




(8)

Balconies are LVL slabs interspliced with waterproof membrane layers which prevents water from advancing through multiple veneers.

Interiors + MEP Modules




Maximum dimensions of modules in BC without requiring permit or pilot car for transport are 8'6" x 53'-0".



Max lifting weight = 1000 kg

1 sheet 5/8 Type X GWB = 32 kg 2" LVL Panel (4.15m x 2.54m) = 33 kg / m2 8" LVL Beams (4.15m) = 21 kg

10.54m2 LVL Panel = 346 kg 6 LVL Beams = 126 kg Module base weight = 472 kg + finishes and fixtures The reduced module size avoids wasteful "shipping of air" and does not require specialized trucks or permits to ship.



Maximum dimensions of modules in BC without requiring permit or pilot car for transport are $8'6" \times 53'-0"$.

On-Site Assembly Process

Following the successful Deconstruction of existing structures and completion of Site Preparation:

- Glulam columns and 5-ply CLT slabs installed on site
- (2) Interior modules are fabricated off-site including all interior finishes, flooring, fixtures, and all mechanical, electrical, plumbing connections, and telescoping stud walls up to 4'-0" in
- Module packages are packed to include additional components such as doors and drywall sheets, up to a max. weight of 1000kg.
- Modules are loaded onto a local delivery vehicle. The delivery vehicle is equipped with weather protection on all sides, and ideally is accessible form the top or sides for unloading.

 Maximum module width of 8'4" ensures simplicity of delivery.

- (5) Interior modules arrive on site and are immediately craned into place by secondary lifting systems.
- 6 Rolling mini-picker on floor level manouvers the module into final position.
- (7) Lifting points on modules double as attachment points to CLT floors below. Modules are fastened to CLT subfloor.
- 8 Temporary weather protection is preinstalled on floors, and installed on facades where interior units are present
- 9 Envelope and balcony modules are craned into place by the primary crane.
- 10 Telescoping steel studs are raised to underside of CLT slab.
- 11) Interior GWB panels are installed to finish the interior modules.

Prefabrication + Modular

Air and Moisture

Envelope modules in this proposal consist of fibreglass window wall embedded within steel stud frames to create modules suitable for prefabrication. Envelope modules were designed to connect to premanufactured curbs and cladding on the interior modules to avoid costly custom attachments.


Fire

Fire and life safety are one the primary concerns when designing any building. This proposal complies with the 35% exposed surface allowance by the building code, and prefabrication allows for encapsulation to be achieved easily in a high quality factory

Regenerative Design

What if everything we put into the building was beneficial?

Regenerative materials are substances that, when used and managed responsibly, actively contribute to the restoration and enhancement of natural resources and ecosystems. As William McDonough argues in his book "The Upcycle", consumption of materials is not inherently negative when that consumption has positive externalities.



This proposal suggests a conventional assembly using 2.5" concrete topping to achieve both the encapsulation requirements and the acoustic requirements simultaneously. However, the concrete topping in this floor assembly has by far the highest global

warming potential impact of any other assembly component within the project. Replacing the concrete with 2 layers Type X is possible from an encapsulation perspective, but the loss of mass compromises the acoustic performance.

There are potential alternatives to fill voids in slabs that can mitigate the issue of achieving the acoustic requirements through mass, such as sand, gravel, or clay. These natural materials are non-combustible and in relative abundance with a low global warming potential. Some materials, like olivine sand from Hope, BC, could even capture atmospheric carbon as it weathers.

PARKING

 MOD_A

Focus on efficiency and floors

65% of the embodied carbon of a building is emitted during the "Take" phase, or when raw materials are extracted and new materials are produced. To break this down further, in this project, over 53% of that energy was utilized for the floor systems. Mass timber slabs are comparatively inefficient to the other components, and finding a way to safely design hollow slabs or slabs with voids is imperative to reducing the carbon footprint associated with creating new mass

timber slabs.

12.5% EoL 12.5% Use Make 53% Floors

> Natural fiber millwork (Hemp or flax woven polymer sheets)

DTT-C-06

■ Structural Elements ■ Ceilings ■ Roof

Materials are a reflection of our values

Hemp batt insulation For non-rated partition walls , and only where permitted

by code


The materials that we choose to surround our daily lives with are a direct reflection of the ideals and concessions we make and value as a society. The majority of embodied carbon emissions are created during the "Take" phase, meaning that the greatest opportunity to address atmospheric carbon lies not in addressing the transportation of goods to site or the operation of the buildings, but by carefully and dilligently selecting the materials that we choose to build with

Design for dissassmbly

Prefabrication enables rapid on-site assembly, but also allows for quick disassembly when components need to be changed or removed. This adaptability is essential to regenerative design, as it meets current needs without always requiring new materials. Disassembled components can often be reused in future projects, lowering both costs and carbon impacts.



Accelerating the Schedule through Off-site Construction



Construction Costs

			Concrete (Base	case) 🔾	Proposal	
	Area (sf)	Area (m²)	\$/sf	Cost	\$/sf	Cost
Below grade	23,381	2,172	\$315	\$7,365,015	\$315	\$7,365,015
Base floor	8,893	826	\$420	\$3,735,060	\$390	\$3,557,200
Above 1st storey	86,651	8,050	\$400	\$34,660,400	\$360	\$29,894,595
	Quantity		\$/Unit	Cost	\$/Unit	Cost
Balconies			N/A	Included	\$20,000	\$1,440,000
	Cost/month		# months	Cost	# months	Cost
Monthly overhead	\$75,	000	25	\$1,875,000	19	\$1,425,000
TOTAL			401	\$47,635,475	367	\$43,681,810

8.3% cost reduction

Embodied Carbon

			Concrete (Base cas	se)	Proposal			
	Area (sf)	Area (m²)	Emission intensity (kg CO ₂ e / m²)	Net emissions (kg C0₂e)	Emission intensity (kg CO ₂ e / m²)	Net emissions (kg C0₂e)		
Total building (inc. parkade)	118,925	11,048	198	2,187,600	143	1,579,933		

28% carbon reduction

Embodied carbon was calculated using the **Building Emissions Accounting for Materials (BEAM) Estimater** produced by Builders for Climate Action. Neither the Construction Cost nor Embodied Carbon included the impact of upcycled or repurposed materials, nor the carbon sink benefit of the ecological stream setback. Future study or proposals would evaluate these considerations to better understand how the embodied carbon of a project or capital costs can be further offset by implementation of circular building strategies.

Works Referenced

- Undrowned: Black Feminist Lessons from Marine Mammals, Alexis Pauline Gumbs
- 2. WoodWorks Mass Timber CAD + Revit details
- RDH Mass Timber Design Guide v2.1 Oct 2022
- Making Mass Timber Work for High Rise Residential in BC, BTY WSP Axiom + ZGF 2021
- Technical Guide for the Design and Construction of Tall Wood Buildings in Canada, FP Innovations 2022
- A Practical Path Forward for Offsite Manufacturing, WoodWorks
 + Canadian Wood Council

Leasehold Business Case

The business case for this project envisions a leasehold project that leases units to potential residents at a price that is below the average market value for freehold properties.

	\$ / Unit (Avg.)	Profit at sale	Average Unit Price (\$)
Freehold	\$455,019	18%	\$536,922
Leasehold	\$455,019	12.5%	\$511,896

\$ / Unit: \$43,681,810 / 96 Units = \$455,019 per unit

The benefits of a leasehold project as opposed to typical freehold are substantial. Since ownership of the land after the lifetime of the building is retained by the developer (Sacred Waters) and the KKS Nations, future generations will have a similar opportunity to develop or redevelop a project that meets their needs in the future. Leasehold also assists in reducing speculation and encourages long-term thinking for the future of the site. Lastly, leasehold arrangements can also provide steady lease income for the ownership group, depending upon the arrangement. Leasehold allows the current generation to develop the site while simultaneously setting up future generations for their own successes.

Assumptions

This project was designed to the specifications outlined in Appendix C of the project brief. As is the nature of competitions, we were unable to consult or work with Sacred Waters Development or the KKS Nations to develop this propopsal, and would welcome the opportunity to revisit the design and proposal as design partners in the future.


Discussion

We made several adjustments to the schedule, construction cost, and carbon calculators that reflect the advantages put forward by our proposal. Most substantially, we believe that the future cost on carbon will make a concrete base case more expensive above the 1st storey due to increased regulation so we increased the base unit cost to reflect this. We also assumed that timber would still be desireable in a Community Hall design for either scenario, which would be more expensive to implement and mobilize in a full concrete structure. The cost and schedule reductions are largely a result of the efficiencies we anticipate through off-site fabrication. While there is a modest cost reduction, affordability could be greater addressed by utilizing a higher percentage of upcycled or repurposed materials.




45+315DING


paired 451315CRACY of 4MS entity 34 @ 4 = 136 to sacred 33.3... in 137, sq to cube is 6 @ 34 = 198 Bayesian SHTX in 4th invisibility, TIMBER TOWERS GABE Green Martian alien tech SIG is NOT nature of time.




45+315DING **TIMBER TOWERS GABE**

SUSTAINABLE CITIES to SUSTAINABLE FUTURES '93 Chicago & '23 Copenhagen, UIA a 30 yr transit in 191-voyage.












6th column Americanism drive thru ADT (adaptive)

2014 grid 4 in 1990 aligns UK Architects for Gaza demand RIBA call Israel explusion from UIA (illegal settlements), redemand = genocide architectural-urban crime open June 9 2025 FIFTY of site C boundary 6x9 = 54m to 40m quarantine 4th invisibility in American Civilization a 6th column bender to architectures 3 Greek +2 Roman, as automation climate crisis








RANG = Mayotte Nov 11, 2018 seismic Armistice Cultural Development centenary Missed Rendezvous C in EAIA is AMERICA, to SOLVENTER paired SQLVENTER an IQ is SO in 2:1 ratio




5 grid 8 hash EAIA electronic Mafia L12 Misfit on 17th St. Washington DC to IAEA International Atomic Energy Agency in MAGA v One China firing line, as Cold War Putinism remind WWII nuclear begun. EAAI = 5119 as 658 prime to 9151 is 1134, differ 449 in , is 87 a 4 score 7



1 storey 8x16m

BOUNDARIES from Latin *bombus* = *humming* bounds forest, & Aries the Ram of Astrological 12 are 26,000 solar years, 2160 approx Age of Ares 2150 BCE to 1AD, at celestrial longitude 1st 30° . & hr GMT = 72° pentagon @ 30° .







UIA 1990 Montreal in UN2015 Agenda 2030 & Copenhagen UIA 2023 SDG #11: Make cities & human settlements inclusive, safe, resilient. & sustainable. undone Ukraine, Gaza Strip. Trumped Greenland & 51 st8 zero9test to 2033 CarbonWars Trescue 2034 temporals.

PHONETICS Timber B remit eroding pOweR electronic DING timbre tim-BAH **218 BRING** tim tam biscuit. no futuristic bet DAYLIGHTING **GREENLIGHTING**

to 2064






sustainable waste

11 12 13 14 15 16 17 18 19 20 21 22 23 24 25

26 27 28 29 30 31 32 33 34

GABE ROTATES ELEVATOR-STAIR WIT TO ESCALATOR DUAL ARRIVAL IN IMITATION GAME




Ecosphere rotate in orbit Foucault pendulum

- 1:- escalator
- 2:- seismic shift
- 3:- 137 prime 33
- 4:- GeoMetric
- 5:- gamecube
- 6:- SIG.ID

ground zero to above in predictive futures Bayesian SHTX capsize

A0 841x1189 to 1041x1550 = 200x361 of $\sqrt{2}$ x19² BSING: atrium in Urbanarium is T urban briefs Mayday sent




decoding America Canada Greenland ACG 137

13 July 1997 SIGGM: 12-yr old Katie Bender fatal shrapnel, Lake Burley Griffin, 1pm Royal Canberra Hospital demolition misfire reset 1:30 Bender family at Church 1pm, a still closed bridge tragedy.

USGS HQ Sioux Falls, South Dakoda, 13 July 1997 hailstones contact zero Barn Elm tee GOLF / GULF in SIX codeX2000 to SIG.ID Autonomous Researcher 2.0 of 137 prime 33rd in 5x4@64 =1280 pixels High Definition 720 a 16:9 Bayesian.

GABE hexacube post & beam gridlock atrium TIME in TIMBER = 218 mirror BRING to TIME MEMBER = TIMBER MEME casually sent Ecosphere



Power grid / Grid power in Iberian Peninsula outage, April 28, 2025 -induced atmospheric vibration =extreme temp variations in Spain's interior freaked electric: mass outage 12.33pm (10.33 GTM, 11.33 Lisbon), 60% supply-demand gone in 5sec, lack of inertia 1033 is Cicada 3301 (174th & 464th primes) to Ecosphere as 1344+464= 1808+174= 1982 centurion of 1582 Gregorian calendar 10 days lost in 2MR to 1984 Orwellian in The Pentagon - Kyiv 1070 longitude difference plus 34 42 is 25 18 YR off 108 paired 72, as Trump's golf-gulf 39 37 stakes Gaza 1072023 Hamas.

50m² = 538 (sq ft) Electoral College first to 270 US President #48, unless Trump #33 a Gaudi 4MS at UIA2026Barcelona dismantling Democracy in clim8 change.

60m² @ 646 sq ft Ecosphere = UIA1990Montreal 1344+646, a 77 SIM+27= GMTX: Trump hit top right ear at Butler rally, July 13, 2024 Thomas Crook, 20, killed Corey Comperatore, 50, his volunteer fire uniform @ Trump acceptance speech Uncanny A*topia Fiction





6
















5

5 columns atop elevator to 4 beams + elliptical ramp with GABE interactive steps



atrium gamecube Ecosphere





45+315DING TIMBER TOWERS GABE IS SITE C IN GAMECUBE THE EMU A 3 DOT OF 2:1 RATIO

SOLVENTER if totem to 6th column bender discourse is a site C on 8 grid proportional login, priority of whose authority to dialogue doesn't halluncinate semiotics has history entangled sacred god-powers as ratios cubic a 4th invisibility, 2D is the knock knock of net zero arc awaits whose there. 24m column codename Tres 8 7 a 72m Bayesian 6 adaptive conservatory deckings & stairs to climate change 5 6

bender to

5

3

level 1


em 9

staircase of wit Lespirt de lescalier, the Gaza Strip dislocation of Nelson's Column zero datum + Emma = British Empire in Jerusalem 1944+81 = 2025 in Statue of America 1881 to Jefferson Pier Stone 1804/1805 Nelson + EMMA cipher a Naval 77⁰ West, as 1881+144=2025 Mafia "L12" Misfit 4th leg invisibility codename Tres enters Bayesian whether/weather 81 HA equation, if thrice a 24m column bender storms a 72m mast alien tech.

> symmetry finds its greater self vesica piscis a 40m cube electrified

Civilization columns Greek 3+2 Roman to York Hunt whale watching whore-ale, NOT nature of time is Trumpian as American 6th Column contender.

> 6th column bender over boundary on Arterial drive-thru sentience



part cross section

4

3

2

around

Ecosphere codeX2000 typo to Statue of America at Smithsonian Castle 77⁰ 1¹ 33.59¹ hallucinates a minute in zero as 1033 flips 3301 Cicada in Cascadian faultline AS 119 =7x17 GAG orders is DC's Zero Milestone at 2ft sq x 4ft high double 4m x 8m module a zero datum covfefe Trumpian 65-65 columns 5MS to US Capitol dome meridian 77 00 33 W in what is Democacy, for a Federal City to be?


16m rotate site C in ID


grid

72°

conservatory plan


Totem on 8 grid epicenters the Pentagon in 72⁰ geometry to outset pairs of arms from 6th column bender in a multistorey conservatory hold adaptive deck +stair to NOT nature of time events.





site C 8 grid to pentagon

GROUND ZERO 3 DOT IMITATION GAME SIG IS SITE C PLAN IN PREDICTIVE FUTURES BAYESIAN TO JAINA 4MS OF OHQ SACRED CHESS



AUTOMATION an esaclator to Nelson+Emma a 6th column bender in Gaza Strip Strip annihilation, as Bayesian probability the British Empire transition to American, The Pentagon 911 in AA Flight 77 auto eliptic lands 60th anniversary, World Trades Center 7 tower collapse a fire phenomenon.


Bayesian 72m storm across the International Dateline in Washington DC - Kyiv, Ukraine longitudes (Wikipedia) sum $77^000^759^{ll}$ & $30^031^734^{ll}$ an $107^032^723^{ll}$ architectural vehicle to 107.20.23 Hamas Oct 7, 2023 trigger, in what is off 108^0 Pentagon of Israeli ops in ChCh 2.22.2011 EQ ground zero.

1/2 base x height to rectangle quantum site C plan other, 20x54= 108 contact zero m poison a rabbit hole, Interrogator quests hold the phone drinker to alien tech human/Al calling shots Uncanny A*topia Fiction. GABE elevator-stair wit duel on/off escalator a 1.5m seismic horizontal in vertical's where from here.

zero0test: can Interrogator detect deepfakes?


RKEY X BOPH

QOIK M DAVY to whose there responder of knock knock in the Ecosphere, "45+315DING longitude's 4MS trail," awaits blah blah who?




oneninety Mystery Theatre 777+198 to 58 verifies 2 missed rendezvous in TVIP 2022 Sept 16 feather in Greenland TWIP 2023 Sept 16 *Dickson Fjord landslide megatsunami generated a wave over 650ft high*, 51ther 315here in 6 & 5MC Ecosphere's whether weather basin is a let that sink in cubesat X factors in what rigs sail, as tumble-interstellar Oumuamua perihelion Sept 9, 2017 alien tech.





GABE escalator sites The Pentagon - Kyiv $77^003^118^{\prime\prime}$ W + $30^031^124^{\prime\prime}$ E = $107^034^142^{\prime\prime}$ the AM waveband In area frequencies to 4MS alaising 3MS off 108^0 , $25^118^{\prime\prime}$ YR wire 72+108 to oneninety Mystery Theatre's 189 Pentagon fatalities on 911, pair 198 Bayesian probability anchor Sicily's Gulf of Porticello, Italy, on 19.8.2024 sheet X chart *there be dragons*.


Bayesian *what if*s happened, The STIFF Code that Rests in ...? on 8 grid 4 Corners Monument 109^0 02 $^{/}$ 43 $^{//}$ as 1.02.43 over 108 a 102=14+88 DC to 10243 prime 1255 LEE, less Colorado Basin-Bayesian YEA 2551 is 374th prime, differs 881 a 2nd millennium Statue of America 6th column.



5MS Mars warp speed, *zoner* crossed *GazaStrip a GazaRiposte* if 1893 Columbian Expo to 2020 2020 vision hit covid-19.



INTERROGATOR IN VESICA PISCIS VIP IS SITE C PLAN 3D IMITATION GAME



short count 5th World End 1521 = 39², OHQ1/2 base xht = 60 + 4-invisible NOT nature of time 12.51pm ChCh EQ splits 72 in 24/7 is 48 th US State capital Sedona to 4MS DONA = Durer 1514 Albrecht.





DAMPENER

Mafia L12 Misfit #33

MALĞAUDI

DAMPENER

OHQ

sacred chess







DURER 4MS 16 3 2 13

DAMP = 34 5 10 11 8 11 7 6 9 + gr 51@2 9 6 7 12 8 10 10 5

MODA = 33 + gr 49 & 50 totals 132

JAINA 4MS 7 12 1 14 9 19 20 6 DING = 34 2 13 8 11 14 12 11 17 + gr 45 & 57 = 102

16 3 10 5

RUFI = 54 + gr 2 @ 81

4MS **BIGP = 34** gr 45 + 57 = 102 totals 136

AHIP = 34 gr 34 + 68 totals 136

4MS + gr 51@2 totals 136

BCON = 34 11 5 8 10 4 5 16 9

4MS LOAF = 34 gr 41 + 61 totals 136

Longitude City SIG.ID Salone 1997 April 4-9 to Autonomous Researcher Aldo Rossi single car crash, Milan, Sept 4, 1997: 2020vision Canada Ucluelet rogue wave 3xpeers 17 Nov 2020 is QK to OI in 5MS cnrs. in 1990 Iraq invades Kuwait after UIA1990Montreal. 4 tier tetractvs tees a decade in Golf/Gulf OU flip 12:51am zero9test ChCh EQ Feb 22, 2011 an Ecosphere 222 DownUnder to YUU: oilop code UFO Year 2121 =1344+666 typo in 777.

3-d chess gazetted Frankenstein 8MC 11 March 1875 to Sendai 2011 tsunami, 136 yrs question 4@34 a 4MS, in 5MS delivery systems...

24	7	20	3				
12	25	8	16				
5	13	21	9				
18	1	14	22				
6	19	2	15	8	1	24	1
			16	14	7	5	23
			22	20	13	6	4
			3	21	19	12	10
			9	2	25	18	1
	12 5 18	24 7 1225 5 13 18 1 6 19	1225 8 5 1321 18 1 14	1225 8 16 5 1321 9 18 1 1422 6 19 2 15 16 22 3	1225 8 16 5 1321 9 18 1 1422 6 19 2 15 8 1614 2220 3 21	1225 8 16 5 1321 9 18 1 1422 6 19 2 15 8 1 1614 7 222013 3 2119	1225 8 16 5 1321 9 18 1 1422 6 19 2 15 8 1 24 1614 7 5 222013 6 3 211912

1 thru 25 = 325

5MS pairings 9 grid O-tel right angle OIL





0 thru 24 = 300

knock knock imagines who's there net zero arc hallucinates who? "7MC entity 1204 as 4 mins past noon is 4MS time to 16 minute vortex whatifs Bayesian, net zero in interzone hierarchy is even real."

Green Martian Machine Human

MAGA v One China in smartphone / smartcity 8 grid: imitation game plotted tracks a lost cause, unless...





Arbour House is a 10-storey hybrid mass timber proposal that embodies simplicity and practicality, aiming to address issues of housing affordability and sustainable building practices. With a straightforward approach to tackling these issues, SJ Studio has envisioned a design backed by data, which collectively forms a design that can be realistically envisioned. This is not to say that the project does not challenge conventional practices today; the proposal still addresses many topics to break conventional designs for affordable housing, such as double-loaded corridors and single-sided sunlight exposure in units, and instead, introduces ideas for a more liveable and family-oriented development.

The proposal also takes a closer look at translating the ideas of flexibility in the structural design to create a template to fit not only a mid-rise residential typology, but to extend its ideas of modularity to small-scale suburban residential developments, as well as large-scale phased developments.



shared amenities shared laundry, cowork + library & play room



bike amenities 100 spaces + bike repair room



commercial 3349 saft



1 bedroom units





2 bedroom units



community gathering space 3490 sqft



日日日 3 bedroom units



Development

1. Structure as a Kit-of-Parts

We chose a structural system that is highly flexible, utilizing a hybrid steel column and CLT floor where the columns are laid out in a typical high-rise grid of 27' - 6" x 27' x 6" developed by SOM. This grid is a happy medium when it comes to buildability and sustainability due to the structure's flexibility for a wide range of building heights, which enables the removal of a transfer slab to connect to the structural concrete foundation below if underground parking is required. With the concrete skirt to finish the structural edge, this allows for a variety of 'parts' to connect to the superstructure, such as prefab facades, balconies, and circulation.

2. Single Loaded Corridor

Choosing a single-loaded corridor design offers several benefits, including increased natural light and cross-ventilation for suites, enhanced resident comfort and energy efficiency, and creating opportunities for stronger visual and physical connections to the surrounding landscape. This layout can also create a more attractive and marketable living environment while reducing a pure reliance on mechanical systems, aligning well with sustainability goals and BC's emphasis on livable, climate-conscious housing.

3. Family Oriented Development

An exterior atrium provides residents with a semi-private outdoor gathering space that balances openness with comfort. By being fully open-air, it enhances natural light, ventilation, and connection to the environment, while its elevation creates separation from street activity, improving privacy and security. This type of shared amenity supports social interaction, wellness, and a stronger sense of community, all while contributing to the building's livability and appeal

4. Rainwater Management

Integrating landscaping at street level creates an effective buffer between the public street and the retail portico and residential areas. This enhances privacy and comfort for occupants, softens the urban edge with greenery, improves stormwater management, and contributes to cooling and biodiversity. At the same time, it elevates curb appeal and creates a more inviting, pedestrian-friendly streetscape that benefits both residents and visitors, rain or shine.



Creating a Community

From personal experiences, lectures from professors, and stories from families that have lived in multi-residential buildings, a common pattern that can be noted is that there are very little interactions between neighbours and apartments are not that fitting for a growing family. Why is it that the only encounters with our fellow residents are when we bump into each other waiting for the elevators and where are the third spaces within the building?

Our design thoughtfully situates our double fronting units to surround the inner courtyard that enables the units to have a suburban feel with a frontage that faces their 'front' yard as well as a frontage that faces their 'back' yard. The courtyard is a public amenity that features a children's play area as well as a multi-use outdoor space. Having this private open space allows families with children to have a safe play area where parents can feel secure, as access to this area is for residents only. Having the units overlook the 'backyard' as they traverse through the single-loaded corridor of the building on their way to work, or to do laundry in the shared laundry room, or to the shared office and library space, increases the chances of seeing other residents within the complex. This gives a sense of feeling that the complex is an urban village of its own, where everyone is part of a common goal to keep the environment livable.








Typical Unit Modules

A standard grid allows units to be standardized and repeated over the entire project. Stacking the same units on top of each other allows for easy mechanical and plumbing work to be set up throughout the building, reducing the overall cost of materials and labour for expedited construction times.

Reinforcing the idea of the double-fronting design, it enables the standard two-bed unit module to have a smaller frontage width while still accommodating both bedrooms and the living room to have solar exposure. This strategy allows units in the middle of the development to have increased lighting and usability, allowing for more flexible and unique layouts.







1-bed + den module

2-bed + den module

3-bed + den module

Proposal - Arbour House		
Site Area	20,132	Sq.Ft.
Permited FSR	4.00	
Proposed FSR	4.42	
Total GFA	88,962	Sq.Ft.
Residential GFA	85,613	Sq.Ft.
Residential NFA	67,195	Sq.Ft.
Commercial GFA	3,349	Sq.Ft.
Community Gathering Space	3,490	Sq.Ft.
Residential Amenity	3,392	Sq.Ft.
Residential Efficiency	81%	
Below Grade	40,264	Sq.Ft.
Grade	3,349	Sq.Ft.
Above Grade	86,706	Sq.Ft.
Total Stories	10	
Parking Levels	2	
Total Units	77	
One-Bed	36	
Two-Bed	32	
Three-Bed	9	

Cost at Current Face Value

Through an initial cost estimate comparing the two building methods, conventional concrete seems to be better. But, looking at the estimates at face value does not tell the whole story. Construction of the foundation, underground garage, and build times all contribute to additional cost. With mass timber as a structural element, the foundation requirement can be significantly reduced as the overall superstructure is lighter than poured concrete. Utilizing steel columns and CLT floors expedites the build time significantly as well. As the proposal is in a TOD zone, the overall number of parking spaces required can be reduced. To challenge this further, promoting sustainable modes of transportation can remove the underground parking entirely. Ultimately, we have decided against this as we have programmed our proposal to be family-oriented, and we believe that the options for different modes of transport embodies a flexible design.

\$52,630,985.00

Construction Cost (High Level Cost E	stimate)							
		Conventional	Concrete	Ma	Mass Timber Hybrid			
	Sq.Ft.	\$/ Sq,Ft.	Cost	\$/ \$	Sq,Ft. Cos	st		
Below Grade		40,264	\$315.00	\$12,683,160.00	\$315.00	\$12,683,160.00		
Grade		3,349	\$360.00	\$1,205,640.00	\$415.00	\$1,389,835.00		
Above Grade		86,706	\$285.00	\$24,711,210.00	\$415.00	\$35,982,990.00		
	Quantity	\$/ Unit	Cost	\$/ L	Unit Cos	st		
Balconies		77	\$25,000.00	\$1,925,000.00	\$25,000.00	\$1,925,000.00		
	Cost/Month	# Months	Cost	# M	Months Cos	st		
Schedule Cost (Monthly Overhead)		\$50,000.00	18	\$900,000.00	13	\$650,000.00		

\$41,425,010.00





П) [П	<u> </u>	С	-1	N	R	
_						•	$\overline{}$	

					11-0-0	/()
Structural System Material Breakdown & Co	ost Analysis					
Below Grade (Sq.Ft.)		40,264 Sq.Ft.				
Grade + Above Grade (Sq.Ft.)		90,055 Sq.Ft.				
Structural System	Quantity	Unit Type	Unit Cost per LB/FT3	Cost/ Sq.Ft.	Total	
Conventional Concrete						
Superstructure						
Reinforcing		5.50 PSF (Pound per Sq.Ft.)	\$1.6		\$8.80	\$792,484.00
Post-Tensioning		1.10 PSF (Pound per Sq.Ft.)	\$2.5		\$2.75	\$247,651.25
Concrete		0.90 Ft3/Ft2	\$9.0	00	\$8.10	\$729,445.50
Total						\$1,769,580.75
Foundation						
Reinforcement		1.70 PSF (Pound per Sq.Ft.)	\$1.6	30	\$2.72	\$109,518.08
Concrete		0.30 Ft3/Ft2	\$9.0	00	\$2.70	\$108,712.80
Total						\$218,230.88
Grand Total						\$1,987,811.63
Mass Timber Hybrid (Proposal)						
Superstructure						
Structural Steel		9.95 PSF (Pound per Sq.Ft.)	\$2.5	50	\$24.88	\$2,240,118.13
Slab Reinforcement		1.8 PSF (Pound per Sq.Ft.)	\$1.6	60	\$2.88	\$259,358.40
Concrete		0.28 Ft3/Ft2	\$9.0	00	\$2.52	\$226,938.60
CLT		0.6 Ft3/Ft2	\$8.5	50	\$5.10	\$459,280.50
Total						\$3,185,695.63
Foundation						
Reinforcement		0.9 PSF (Pound per Sq.Ft.)	\$1.6	50	\$1.44	\$57,980.16
Concrete		0.17 Ft3/Ft2	\$9.0	00	\$1.53	\$61,603.92
Total						\$119,584.08
Grand Total						\$3,305,279.71

Coefficients of PSF and F13/F2 are directly taken from Skidmore, Owings, and Merrill. AISC Steel & Timber Research for High-Rise Residential Buildings: Final Report. 4 Dec. 2017. with the unit cost derived rom multiple sources such as BC Housing, WoodWrites, and Allus Group.

Cost of Effcapsulation (Celling)								
				Material Cost/ So	ı.Ft.	Labour Cost/ Sq.Ft.	Total (Potential	l Savings)
Single Layer Standard					\$2.00	\$3	2.00	\$180,110.00
Double Layer Mass Timber Encapsulated					\$4.00	\$	3.00	\$360,220.00
Embodied Carbon								
			Conventional Concrete			Mass Timber Hybrid + C	oncrete Foundation	1
	Sq.Ft.		Embodied (KG CO ₂ e/ft²)	Total (KG CO ₁ e)		Embodied (KG COge/ft²)	Total (KG CO₂e)
Above Grade		88,962		43	3,825,366	:	21.5	1,912,683
Below Grade		40,264		43	1,731,352		43	1,731,352
Total					5,556,718			3,644,035

Embodied Carbon Coefficient of conventional concrete is derived from, Robati, Mehdi, and Philip Oldfield. "The Embodied Carbon of Mass Timber and Concrete Buildings in Australia: An Uncertainty nalysis." Building and Environment, vol. 214, 2022, p. 108944, doi:10.1016/j.ubidenv.2022.108944, and Mass Timber Hybrid is derived from Westbank, and Henriquez Partners Architects. Rezoning anglesting: PBOTOTYPE — MR Sectionalis 4 Mass Chimber Nat Partners Architects. Rezoning anglesting: PBOTOTYPE — MR Sectionalis 4 Mass Chimber Nat Partners Architects Partners Architects. Rezoning anglesting PBOTOTYPE — MR Sectionalis 4 Mass Chimber Nat Partners Architects. Rezoning anglesting PBOTOTYPE — MR Sectionalis 4 Mass Chimber Nationalis 4 Mass Chimber

Increasing Affordability by Breaking Limitations

Many standard design elements that can help reduce the cost of the building over its whole lifetime already exist. Methods such as adequate sun shading, heat recovery ventilator units, and well-insulated buildings can significantly reduce the overall energy consumption of the entire building. As BC Energy And Carbon Step Code continues to increase its requirements, it is vital in our building to ensure that the building is thoughtfully designed. With the increasing ratio of solid walls to glass, our proposal of having double fronting units ensures that all units have enough natural sunlight, as well as providing enough air circulation by equipping each unit with an HRV to reduce the increasing need for heating and cooling systems.

Although current practices are good, there is always room to improve the system to enable more unique, quality-built, and innovative solutions to be proposed. The following is what we propose to change to allow more flexibility for mass timber to be an alternate building solution.

1. Reduce encapsulation requirements

As Mass Timber right now in BC is required to be encapsulated as a prescriptive measure due to fire prevention, which adds cost, weight, and material waste, allowing materials to be performance-based opens up further testing to see how a mass timber system actually holds up under fire testing.

2. Include the building's embodied carbon as a taxable element as part of the carbon tax

Make it a requirement that buildings have to have a life-cycle report in both embodied and operational carbon. This way, decisions of choosing construction materials can be made more cautiously to choose a low-carbon alternative over conventional methods.

3. Increase government incentives for Mass Timber buildings to entice developers

As mass timber is still a premium over conventional concrete, there can be grants given to developers to start building more mass timber towers, as well as an incentive for low-carbon structural systems. Providing a density bonus for choosing a lower embodied carbon proposal, as well as reducing the parking requirements, can also benefit the developer.




Scheme 1: Typical Vancouver Suburbia

Mass Production as a Means of Affordability

Adapting Kit-of-Parts Across All Typologies

The principle of mass production in housing—standardizing components for flexible application—offers a way to scale affordability. A kit-of-parts strategy allows the same prefabricated unit types to be applied across multiple typologies: suburban multiplexes, infill along arterial roads, or phased mid-rise developments on larger sites. By standardizing floorplates, wall panels, and service cores, while keeping the massing adaptable to irregular site conditions, housing can remain cost-efficient without becoming repetitive. In the diagrams above, the schemes demonstrate how a two-bed unit can be repeated throughout different typologies.

If embraced at scale, mass production and prefabricated timber systems could shift housing delivery from one-off, site-specific builds to repeatable yet adaptable frameworks. By doing so, affordability can be addressed not only through lower construction costs but also through faster delivery of diverse, well-designed housing forms.



Scheme 2: Typical Vancouver Arterial Block


Benefits of Mass Production in Housing

Faster Construction Times – Off-site prefabrication accelerates assembly, allowing buildings to rise in weeks rather than months.

Lower Labour and Equipment Costs – Mass timber components like CLT and glulam require smaller crews and less heavy machinery compared to concrete or steel.

Shorter Build Durations – Projects finish sooner, reducing interim financing, carrying costs, and risk exposure for developers.

Streamlined Sequencing – Prefabricated elements reduce trade overlaps, subcontractor conflicts, and costly site delays.



Scheme 3: Typical Vancouver Phased Development

Mass Timber as a Driver of Affordability

Mass timber strengthens the case for prefabrication by combining efficiency with sustainability:

Sustainability Incentives – As a renewable material, timber unlocks potential carbon credits, grants, or expedited permitting—particularly relevant under BC's green building policies.


Support for Mid-Rise Density – Timber excels in the 6–12 storey range, providing the "missing middle" housing form: denser than low-rise wood-frame, but more cost-effective and livable than high-rise concrete towers.

Reduced Lifecycle Costs – Precision fabrication improves energy performance and durability. Exposed timber finishes can reduce the need for drywall and cladding, cutting both material and maintenance costs.

Vertical Grain

Decoding Timber Towers to have a positive impact on three primary drivers of housing affordability, climate resilience and co-living is an intricate structure of discrete systems coming together in ways that allow communities to thrive and grow. While mass timber design and construction continue to gain momentum there are some very challenging aspects to be resolved before we witness widespread adoption in the lower Mainland of British Columbia and beyond.

The Vertical Grain project aims to achieve comfort and livability while facilitating stronger connections between occupants through striking a balance between individual private spaces within a shared co-house form of dwelling. Every individual private unit will be equipped with sleeping space, a private washroom, kitchenette, and a balcony. Larger common spaces on every floor will provide a full complement of living, dining and kitchen space. The concept for the typical residential levels differs from current mainstream market and rental housing projects by creating an environment more aligned with that of a household where a collection of different individuals and families can share in a collective experience aimed at strengthening a sense of community and belonging. The co-housing format also opens the door to various forms of intergenerational living in much more supportive and integrated ways while reducing costs by not requiring every unit to be fully outfitted with furnishings and appliances. Affordability is further enhanced by building less. The project challenges most regional municipal bylaws in terms of provision for parking. Finding ways to reduce parking requirements whenever reasonable is a significant first step toward improving a project's



affordability and reducing its carbon footprint. Working within transit-oriented development strategies and utilizing traffic demand management models is a great way to approach project needs while finding a balance between what forms of transportation can be accommodated.

The project will strengthen people's connection to nature by connecting the site between the urban frontage and natural existing conditions by integrating exterior passageways through the building on the first floor. The project aims to retain as many existing trees as possible while daylighting a previously buried stream. Exterior balconies have been provided for every private dwelling space as well as large common balconies at every second floor throughout the building, The project is capped by an accessible roof top patio which will accommodate gatherings for up to 150 people and provide allotment gardens for any occupants interested in growing food.

The building is designed to align closely with current strategies for structural systems and modularization, while aspiring to reach new heights and efficiencies. A commitment to a simple form, combined with a 12 storey maximum height facilitates a design which maximizes the exposed timber to realize the biophilic and aesthetic benefits of the material. The design uses Standard size components for CLT panels (3.0m max width) to align with the majority of vendor limits and simplify logistical challenges related to transportation routes and permitting, as well as standard size Glulam posts and beams. The potential for systemization of repeatable steel connections, for axial and lateral resistance, enables simplification of fabrication and installation while facilitating labour force skills development and knowledge transfer. Over time, with the widespread adoption of standardized components and mass production it can be assumed that productivity will increase, and costs will come down.

Structure and Design

The design of the tower responds to the angled, forested site with the general approach of an 'inflected, winged bar building focused on the prominent corner of the stie. The building is pushed over to the street face as far as possible to minimize the area of trees displaced or cut down and preserve a back area focused on the uncovered creek bed.

The structure takes a straightforward approach, assuming a point-supported CLT floor on glu-lam columns- with a hybrid steel-timber eccentrically braced frame forming the major lateral resisting element. The massing allows for a repetitive floor plate, based on a 10' by 12' grid allowing for economical and non-manufacturer specific CLT panel sizes, provision for over-sized load deliver.

Shallow bays. The building hinges on a triangular 'core' stabilized with 2 storey eccentrically braced frames. In this plan configuration the scheme assumes either side of the triangular frame can provide a transverse line of stability to its adjacent wing- while stabilizing its opposite wing in the long dimension of the floor. The design assumes braces and columns are stabilized at each floor diaphragm- with deformation at the hinge point- assuming significant deformation in the floor itself. Opposite ends of each wing are assumed with secondary braced frames. The major common areas are all concentrated around this self-supporting 2-storey space, allowing for open atria and common balconies at the corner of the building.

Social

Program spaces and opportunities for all members of the community to work, share, and play together before and after the project has a physical presence.

- shared spaces
- social infrastructure
- community governance

Environmental

Integrate our natural and built environments to address the causes and effects of climate change.

- · sustainable wood sourcing
- · carbon footprint
- connection to the land

Economic

Reimagine our system of delivery to deliver high quality, low carbon buildings at an unprecedented scale.

- lifecycle costs and operations
- ownership and financing
- transitioning an industry to off-site production and standardized components





SIMPLE PIANO HINGE AND WIRE SPRING

ALUMINUM OR GALV STEEL BRACKET C/W LATERAL SLIP FOR INTER-STOREY DRIFT, AND VERTICAL SLIP FOR DEFLECTION COMPOSITE WINDOW

Design Rationale (A) 0.20 m **Facade and Details of Construction** The envelope design and the related CLT Plate perimeter are To address fire-safety issues of a combustible envelope speculations on current pre-fabricated envelope design. Rather and enlarged rainscreen, design incorporates the following: than a curtain-wall style system- the concept is for numerous lightweight, wood-framed panels in a unitized, platform-frame system An · Wood-cavity filled with LEVEL 4 18900 00 integrated design of structure, cladding and architecture proposes mineral wool and interior an alternate approach to watertightness, perimeter fire-stopping encapsulation layer. 1. Structure Assembly attachment & support and differential movement- The goal is to Redundant Metal structure, maximize wood material use and simplify construction with portable connected directly to the units installable with small equipment from below an active deck- as superstructure through metal-IVI PERIMETER CHORD a tower-crane continues assembling the CLT floors above. metal connections (temporary FIXED TO COLUMNS self-support of the cladding The unifying concept is the 'shingle'- a lightweight 5' panel, using assembly in event of interior an inverted 'king-post' truss design to stiffen a minimal interior structure burning) ACOUSTIC MATT structure of encapsulated light-wood framing. Panels are landed on · Rain-screen is choked ENCAPSULATON a water-proofed ledger formed outboard of an LVL tension chord to a point LAYER ON RESILIENT ringing the floor-plate, and anchored to the chord and the panel · Metal soffit material to avoid a above with simple connections taking deflection and lateral drift. pronounced chimney effect · (assuming generous lateral Extending this logic to the exterior- the cladding extends past the cavity ventilation) THERMALLY BROKEN CONNECTION T MID-POINT centre-point of the 'truss' to form a shingle like expression, and Staggering windows a deep and sheltered over-hang for good water-shedding off the to mitigate flashover to primary surface and space for integrated vents beneath the hem of compartments above. the 'shingle'. **Inclined Cladding** Mineral wool insulation 2. Panel Placement Vapour Barrier GALV STEEL GIRT FORMED INTO TRUSS CHORD Integrated Vents METAL RAIN-SCREEN CLADDING VAPOUR PERMEABLE WATER BARRIER MEMBRANE Air Seal PRE-INSTALLED VAPOUR CAULKED AIR-SEAL HERMAL CLIP, ENGINEERED AS LVL Tension Chord CONNECTION POINT OF TRUSS FLEXIBLE FLASHING LED OUT Waterproofed ledger - GALV STEEL STAY PINNED PANEL-EDGE INSULATION HDPE shim 3. Interior Sealing CLOSURE FLASHING C/W

Simple screw fixing

Simple deflection connection

Social Rationale


Program spaces and opportunities for all members of the community to work, share, and play together before and after the project has a physical presence. By following a development model based upon co-living and sharing of spaces the project has recalibrated the collection of program elements to achieve heightened efficiency and simplified structural design to realize enhanced affordability and more sociable dwelling. The main floor is comprised of mixed use offerings which serve as amenity to both the occupants of the tower and surrounding community as well as a dedicated residential entry. The layout of these spaces frame an urban corner while offering porosity through the building to the naturalized courtyard behind. Levels 2 through 12 provide a repeating stack of efficiently organized residential plans based on a collection of moderate private units sized for individuals up to small families, each of which provides bedrooms, bathrooms, kitchenettes, and small exterior balconies. These units open onto a generous arrangement of shared kitchen, dining and living spaces along with large common exterior balconies. The roof level is envisioned as an accessible terrace for larger gatherings along with a complement of allotment gardens all surrounded by amazing views of the city to the SW and the local mountains to the NE.





Floorplans

- 1 Parking
- 2 Electrical Room
- 3 Water Entry / Mechanical Space
- 4 Bike Storage
- 5 Elevator Lobby
- 6 Garbage and Recycling
- o Garbage and Recyclin
- 7 Laundromat
- 8 Cafe / Co-Work Space
- 9 Exterior Pass-Through
- Exterior Fass-Tilloug
- 10 Residential Lobby
- 11 Studio Unit
- 12 1-Bed Unit
- 13 2-Bed Unit

- 14 Shared Dining
- 15 Communal Kitchen
- 16 Living Space
- 17 Double Height Elevator Lobby







Environmental Rationale

One of the primary goals of the Vertical Grain project is to maximize sustainability aspects ranging from Indigenously sourced and sustainably harvested wood for the mass timber, through to watershed-based storm water management through rain gardens and biofiltration back into the reconstituted natural stream. The project site offers great opportunities to work with existing landforms and features to enhance the projects' connection with nature. Multiple trees will be retained on site by keeping the development to the south and west and limiting the need for extensive excavation. The commitment to working with as much wood as possible support ambitions to drive embodied carbon as low as possible.

Why we care about sourcing

We care where our wood comes from to ensure our buildings have a positive impact on the landscapes and communities they grow from. Our role as architects and sustainability leaders is to drive continuous improvement of supply chain by creating demand for wood that address:

Sustainable Forest Management

Target practices that improve forest health, restore ecosystem services & balance economy & ecology

Social Equity

Support underrepresented parts of the supply chain and drive financial value to the landowner

Climate Smart Forestry

Aim for practices that stabilize or maximize carbon stored both on the landscape and in wood products.

Our Approach

We have been connecting with the BC forest sector and gaining first-hand knowledge from stakeholders in the supply chain. We have walked through our forests with foresters and cultural features surveyors of Community Forests and First Nations owned forests to learn about sustainable forest management. We have met with log brokers, mills owners and mass timber fabricators to understand more about what type of traceability information is available to them and what we can reasonably ask for.



Economic Rationale

Reimagine our system of delivery

The project challenges most municipal bylaws in terms of provision of parking as previously mentioned. Finding ways to reduce parking requirements whenever reasonable is a significant first step toward improving a project's affordability and reducing carbon footprint. Working within transit-oriented development strategies and utilizing traffic demand management models is a great way to approach project needs while striking a balance of what forms of transportation can be accommodated on a project specific bases.

A more sophisticated approach to defining project development data and identifying common vs amenity spaces will have an impact on how projects are measured for financial viability as well as bylaw compliance.

Building Information	Baseline (Concrete)	Submission (Wood)	
FSR	4.4		
Lot size (sq ft)	20,0	000	
Building sq ft Above Grade	88,	014	
Building efficiency (%)	75%	85%*	
saleable/rentable (sq ft)	66,011	71,143	
non saleable/rentable (sq ft)	22,004	14,594	
Total Stories above grade (#)	1	2	
Total Stories (#)	1	3	
Base floor (#)		1	
Above 1st storey (#)	1	1	
Stories below grade (#)	1	1	
Units (#)	162	132	
Bedrooms (#)	189	154	
Rooftop Amenity Area	1,500	1,500	
Common Area (sq ft)	0	27,176	
Non-residential CRU (sq ft)	3,3	889	
Cost Concrete BG @ \$360/SF	\$2,619,696	\$2,486,632	
Cost Concrete Lvl 1 @ \$361/SF	\$1,941,235	\$2,173,105	
Cost Concrete Lvl 1+ @ \$362/SF	\$33,286,532		
Cost Wood Lvl 1+ @ \$431/SF		\$35,423,445	
Cost Balconies	\$3,150,000		
Schedule Costs (Monthly Overhead)	\$900,000	\$800,000	
Construction Cost	\$41,897,463	\$44,033,182	
Carbon Concrete @ 6.69 kg/sq ft	641,462	91,712	
Carbon Wood @ 2.69 kg/sq ft		221,088	
Total Carbon kg/sq ft	641,462	312,800	

^{*} Assumes 15% of common area is dedicated to circulation on all residential floors

Lifecycle costs and operations

- Shortened construction schedule:
 Off-site fabrication and on-site crane
 assembly reduce build time by 20–30%,
 saving on labor, financing, and temporary
 services.
- Lower mechanical and finishing costs:
 Exposed wood interiors reduce the need for dropped ceilings, secondary finishes, and artificial lighting infrastructure.
- Deconstruction-ready assemblies: modular design supports future disassembly and reuse, further reducing lifecycle emissions.


Ownership and financing

- Indigenous procurement and training:
 Dollars are reinvested locally via
 Indigenous contractors and suppliers, creating durable economic multipliers in the region.
- Indigenous Nonprofit Ownership
 Structure: the development is proposed
 under the leadership of Scared Waters
 Development with ownership retained
 by a nonprofit Indigenous housing

- provider, enabling long-term affordability and community governance.
- Procurement-as-Economic Development: construction and supply chain funding includes allocations for Indigenous contractors, material suppliers, and youth training, reframing housing not just as a cost, but a generational investment in Indigenous economies.

Transitioning and industry to offsite production and standardized components

- Prefabricated Modular System:
 construction shifts from conventional onsite framing to a kit-of-parts, mass timber
 assembly model—that leverages off-site
 in micro factories for milling and finishing
 of mass timber elements to be craned
 into place using a standardized platform
 system.
- Digital Twin Integration: introduces a BIM-to-field digital workflow that aligns fabrication, permitting, delivery, and quality control—offering greater predictability and transparency.



J K L O F T M

DESIGN RATIONALE

Reimagining of high-rises a vertical villages for raising families and building community.


LOCATION CONSIDERATIONS

A corner lot along a busy commercial street with close proximity to transit lines expects high pedestrian traffic. Finding ways to accommodate the public was a high priority to reduce disruptions to the neighbourhood's existing character, especially considering the dominant trend of low-rise buildings in the vicinity. This presented the opportunity to design spaces not only to facilitate circulation, but also as places to visit and interact with public programming, or simply to gather and rest.

HOUSING STYLE


The lot sits on the traditional unceded lands of the Katzie. Kwantlen, and Semiahmoo First Nations. The team was inspired by the sense of belonging and togetherness that comes natural to living in vernacular architecture such as the longhouse of the Coast Salish. A co-op housing style of ownership is the natural option, as relationship may begin to be built from the development process. Additionally, there would be an aspect of self-selection since people who would join are likely already seeking to foster close relationships, which at present seems alien in the context of high-rise buildings. To remedy this, programs have been placed to create compounding points of interaction as a way to bridge the gap between the seclusion many have grown to expect and become accustomed to, and the fulfilment that comes from engaging with community.





FORM

A pair of discreet towers avoid a "massive bar" form which would not only be disturb the skyline, but also the neighbourhood's character by creating an imposing street condition. This allow for variable unit types between buildings, which may be further adjusted by extending or retracting the floor plate according to the structural grid if required for different site contexts. The mass is also highest at the corner of the block, stepping down twice as it reaches the intersection, as though conceding to it. Between them came ample opportunity to create programmable space for residential amenities, and was further improved by retreating from the street wall to provide a generous amount of public space.



STRUCTURE

Simple massing creates efficiencies in structure prefabrication, and construction. The upper residential levels use a regular grid followed by columns that are superimposed between CLT floor panels. The concrete core runs east to west, while timber elements with steel connections span two levels at a time for bracing along the north-south axis. This continues at the podium with bracing that is entirely steel to minimize obstructions between programs. Structural members thicken at the podium to support the larger open spaces of the residential and public amenities, and acetylated wood is used for exterior structural members to improve durability.

SITE CONTEXT

To reflect the site's TOA designation along transit lines and near a transit hub, a bus stop is accommodated in the southwest corner of the lot along with a bike lane that connects the busy commercial stretch with the quieter residential neighbourhoods to the north.

Parking spaces have been reduced and allow for car-share services. This also follows the increasing trend of alternate modes of transportation, including for work commutes. The 2023 Vancouver Transportation Snapshot, for example, revealed that an estimated 53% of daily trips were made by transit, walking, or cycling, a figure that has been steadily increasing since 2021. In the same survey, over 40% of trips were to restaurants, recreation, and shopping, all of which are very likely to exist within a walkable stretch of a commercial arterial street. Additionally, other cities with more robust transit and biking infrastructure have trip values up to 74%, as in Berlin. It will take time for such a shift in the Lower Mainland, but sites such as these are a great place to start.



LEVEL 1

1	RESID. LOBBY
2	BIKE STO.
3	MAKERSPACE
4	ART GALLERY
5	MARKET
6	EXTERIOR
	SPACE
7	WASTE

WATER MANAGEMENT

MANAGEMENT


A bioswale wraps along perimeter from northeast to the southwest corners of the site, guiding flow to a rain garden, temporarily holding excess and slowing runoff to the municipal system. Retained water also cools the surrounding area to alleviate urban heat island effects.


Likewise, the site on-grade slopes southwest. Raised pavers create connections across bioswales, allowing water to flow in a channel underneath. Where they run parallel, pipes underneath the paving connect the bioswale and the rain garden.


LEVEL 2


ı	CAFE
2	COMMUNITY
	GARDEN
3	PLAY
4	DAYCARE
5	COMMUNITY

LAUNDRY









WINTER GARDENS

Addressing envelope concerns with balconies in a mass timber project, an enclosed winter garden is shared between every two floors, acting as a "third space" in lieu of traditional balconies that typically serve individual units. This creates character for the conventionally barren circulation of high-rise towers, while also encouraging interaction between residents that may personalize or simply enjoy the space together. The space can regulate indoor temperature by capturing daylight through floor to ceiling glazing when desired, or with operable windows that facilitate cross ventilation to each unit. Certain plants may also thrive in this indoor environment given the ample amount of direct sunlight, and given enough care between the residents sharing the space.

The space also fits between two ends of the social gradient available to residents. Starts at the very private individual unit, they may engage with the winter gardens between pairs of floors, then the residential amenities serving both towers, and finally the remaining podium programs that are entirely open to the public.

	EAST TOWER	WEST TOWER	TOTAL
1 BED	15	20	35 UNITS
1 BED WITH LOCK-OFF UNIT	-	15	15 UNITS
3 BED	6	-	6 UNITS
			56 UNITS

LIVING IN THE LOFT



1 Cafe

A local-owned cafe brings the public up to the second floor while also being conveniently accessible from residential amenities at the same level.

Winter Garden 2


An assembly space serving two floors at a time. Residents may nurture plants together or simply relax as they observe the courtyard below or opposite tower's garden across.



Commons 3

A flexible space with kitchen facilities, a lounge, and recreational furnishing for general use. It may also be reserved for events.







4 Art Gallery

The most front-facing program, a showcase of local art including from indigenous artists creates dialogue within the community. The gallery is supported by a rentable workspace for artists.



5 Grocery

A shop for fresh goods and produce serving both the residents and the public. This space can be rented out to local businesses or jointly owned by residents to subsidize costs.

Daycare 6



An amenity for all residents that is also an affordable servicefor families in the neighbourhood. Placed at the confluence of the tall east tower and the public programs above the street level.





TYP. EXTERIOR CLT WALL

25mm METAL PANEL (WOOD STAIN)
25mm VENTILATED CAVITY STRAPPING
AIR BARRIER WRB
100mm EXTERIOR SEMI RIGID MINERAL
WOOL INSULATION
15.9mm PLYWOOD SHEATHING
200mm PREFABRICATED CLT WALL
31.8mm GWB TYP "x"
38mm RESILIENT CHANNELS
15.9mm FINISH









Stuwix Resources

A FIRST NATIONS COMPANY



NUXALK NATION Uts'i s-thilh Nuxalkmcilh

TYP. PREFABRICATED STEEL WINDOW THROUGHOUT ALL SIDES

Using robust mass timber assemblies with consistent and reliable performance due to prefabrication, a minimum STC rating of 41 can be achieved between floors.

Partitions between units are generally thicker to minimize intrusion of mass timber columns into the living spaces. This also allows the divisions to achieve a minimum STC rating of 38. Sound attenuation is one of the team's primary concerns among residential spaces.

Thermal bridging is easily handled due to the lack of protruding residential balconies. The typical prefabricated exterior wall panels can also achieve a minimum R-value of 28.

TYP. PREFABRICATED CLT FLOOR

5mm VINYL FLOORING
38mm CONCRETE TOPPING C/W ACOUSTIC
UNDERLAYMENT
200mm 5-PLY CLT FLOOR
36mm SERIVCE CAVITY WITH INSULATION
AS NEEDED
31.8mm GYPSUM FINISH

INDIGENOUS SOURCED WOOD

A few indigenous suppliers from the BC as our mass timber sourcing. Sourcing our mass timber locally would support the local economy as well as supporting sustainable initiatives.

FP Innovations is a NFP organization that provides and supports the innovation of wood products including mass timber across British Columbia in collaboration with Indigenous communities. Collaborating with Indigenous communities to source their lumber such as West Chilcotin Forest Products. They have also worked on numerous projects for Indigenous communities, including Yunesit'in First Nations on a housing project based in CLT and modular construction.

FP Innovations has forestry practices and mills in British Columbia, based in Vancouver and Maple Ridge, along with other locations in Canada. With local industries, it would mean less transportation emissions. Sourcing wood from indigenous suppliers ensures that we follow sustainable practices from generations of Indigenous forestry.

Other suppliers that were considered were the following: Totem Sawmill LP (Nuxalk Nation) Stuwix Resources Ltd. Lil'wat Forestry Ventures (Lil'wat Nation)



Partnering with Katzie, Kwantlen and Semiahmoo first nations through the join development of Sacred Waters, we wanted to ensure our building programming reflected indigenous values and their goals. Some values detailed on Kwantlen First nations included maintaining a sense of flow and allowing one to become more connected to natural systems of a site, providing opportunities of educational and economic growth - shown through additions of a daycare and Indigenous run market, and supporting generational growth leaning into the co-op housing model.

NET CARBON EFFECT OF CONCRETE VS. CLT FLOOR SLABS



CALCULATION CONSIDERATIONS

Overall proposal costs are estimated to be three million less than that of a concrete structure. While this difference is not drastic when considering cost as a driving factor, the material availability of lumber in British Columbia adds another layer of why mass timber is a better option.

Below grade costs were assumed to be similar to the concrete case. The base floor estimate cost per square foot is slightly less than with fully concrete, as large timber members replace much of the column mass beyond retained concrete pedestals. The main cost savings of having prefabricated panels is found in the upper levels. Replicabilty of the floor assemblies and prefabricated mass timber panels drives efficiencies in both time and cost.

Some of our assumptions for the construction costs included using case studies' cost per square foot and applying a rate of inflation. We also accounted for use of local timber resulting in a lower delivery and transportation cost.

CALCULATIONS	
FSR	5
Lot size (sq ft)	20,142
Building sq ft Above Grade	93,420
Building efficiency (%)	85
non saleable/rentable (sq ft)	14,013
saleable/rentable (sq ft)	79,407
Total Stories above grade (#)	20
Total Stories (#)	21
Base floor (#)	1
Above 1st storey (#)	19
Stories below grade (#)	1
Units (#)	56
Bedrooms (#)	83
Amenity space (sq ft)	1,994
Non-residential (sq ft)	5,411

CHART PARAMETERS

The adjacent graph compares net effect of using typical reinforced concrete slabs against our specified CLT floor slabs for upper level floor plates only. The concrete mix in consideration uses embodied carbon values following EC60 data, with an average compressive strength of 30 MPA or C25/30.

The Proposed CLT's total carbon sequestration value takes into account an estimated 34 kg CO2 equivalent of embodied carbon per square metre.



CONSTRUCTION COSTS						
		Con	crete	Proposed		
	Square footage	\$/sq ft	Cost	\$/sq ft	Cost	
Below grade	155.0	\$315	\$48,825	\$315	\$48,825	
Base floor	11662.6	\$360	\$4,198,528	\$350	\$4,081,902	
Above 1st storey	81757.6	\$385	\$31,476,672	\$346	\$28,268,904	
	Quantity	\$/unit		\$/unit		
Balconies	0	\$25,000	\$0	\$25,000	\$0	
	Cost per month	# Months	Cost	# Months	Cost	
Schedule Costs (Monthly						
Overhead)	\$50,000	18	\$900,000	16	\$800,000	
TOTAL			\$36,624,025		\$33,199,632	

EMBODIED CARBON							
		Concrete			Proposed		
	Sq ft	Embodied		Embodied Carbon kg/sq ft	Total Carbon		
Total Building Sq Footage	93575.2	6.69	625926.17	2.69	252,109		

familyandfriends

FAM-1

FAM-1 is a prototype twice over.

familyandfriends envisions not just one building, but a comprehensive mass timber design, fabrication and construction system: **FAM**.

The system leverages our region's great timber resources, burgeoning mass timber fabrication industry, and massive housing demand to innovate both the material and social character of high density living.

In a time of increasing loneliness, we need alternatives to the studio, one- and two-bedroom units dominating the market. Two demographics historically underserved by the housing sector — intergenerational families and young people — both stand to benefit from larger units. For families, remaining together offers affordability, mutual support, and cultural continuity. For youth, roommates mean a more affordable, more social way of life. Accordingly, FAM-1 has 5, 6, and 7 bedroom units. Their design builds on the success of student sharehouses in Vancouver, adopting many of the spatial characteristics of the single-family home.

From a construction standpoint, FAM minimizes the number of unique components, adopting just a few **modular panels**, **plates**,


and columns. Prefabricated partitions, fixtures and fittings **expedite on-site construction**. The system is also modular at the building scale -- independent CLT circulation cores allow for the design of both small and large building footprints.

A pilot project, FAM-1 intends to prove both the efficacy of the manufacturing and construction system, as well as the market feasibility of large, multi-bedroom 'sharehouse' units. It will be developed and funded by the CMHC, in partnership with Kwantlen First Nation's "Seýem" development corporation. If successful, the FAM system will be available to private developers and non-profits alike for rapid deployment across the West Coast.



MANUFACTURING AND ASSEMBLY


the project proposes a tandem mass timber facility that can produce both prefabricated CLT panels as well as prefabricated light wood framing panels. This would avoid more carbon heavy materials such as steel framing as well as utilising the efficiency of materials provided by the stick framing.




each panel is designed to fit within the constraints of a long haul truck bed for distribution throughout Vancouver as well as the rest of the Pacific climate zone. Once on site, the pieces can be easily assembled with minimal crews and an on-site crane.

PODS

standardized kitchen, bathrooms and bedrooms allow for easy prefabrication







EXTERIOR PANEL FRAMING

prefabricated in factory


EXTERIOR PANELS cladding and assembly completed in factory

CLT SHAFT PANELS prefabricated in factory

GLULAM POST + STEEL CONNECTION prefabricated in factory


CLT PLATES prefabricated in factory

INTERIOR PARTITIONS prefabricated in factory



STAIRS prefabricated in factory





MANUFACTURING AND ASSEMBLY


the composite post and plate structure is compromised of approximately 1178 m³ of lumber including sheathing, CLT, light wood framing and glulam posts. Storing in total 1057 metric tons of CO2, which is equivalent to 343 cars off the road in one year or the energy to operate 171 homes.


EXTERIOR ASSEMBLY

metal cladding
25mm steel girts
76mm rigid insulation
with thermally
broken clips
liquid applied membrane
12.7mm plywood sheathing
140mm light wood frame
with fibreglass batt
insulation
16mm gypsum finish

FLOOR ASSEMBLY

floor finish
12.7mm plywood subfloor
50mm rigid insulation
with acoustic
rails and
dampeners
3 ply 16mm gypsum panel
5 ply CLT deck







The system is designed to serve the largest possible market with a single product, thereby maximizing fabrication efficiency and leveraging economies of scale. Weatherproof, insulated panels suit West Coast climate zones—Csb to the south and Cfb to the north. With millions of residents across Vancouver, Victoria, Seattle, Portland, and San Francisco, BC's timber and fabrication industries are well placed to supply this "climate market." We need to think big.

In addition to climate, the design must respond to its cultural region. The large units can accommodate atypical family sizes, a need expressed by the Semiahmoo, Kwantlen, and Katzie First Nations, on whose territory the project is located. At the site scale, a culverted stream and dense tree cover have become opportunities for stewardship through daylighting and preservation, while spaces such as a covered outdoor patio and rain garden can support cultural programming, such as carving or workshops.

PROFORMA


FSR	3.708468229
Lot size (sq ft)	20,125
Building sq ft Above Grade	74633
Building efficiency (%)	85
non saleable/rentable (sq ft)	11194.89739
saleable/rentable (sq ft)	63437.75188
Total Stories above grade (#)	10.5
Total Stories (#)	10.5
Base floor (#)	1
Above 1st storey (#)	9.5
Stories below grade (#)	0
Units (#)	34
Bedrooms (#)	194
Amenity space (sq ft)	1395.00279
Non-residential (sq ft)	7463.264927



CONSTRUCTION COSTS					
		Concrete		Submission	
	Square footage	\$/sq ft	Cost	\$/sq ft	Cost
Below grade	0.0	\$315	\$0	\$150	\$0
Base floor	7463.3	\$360	\$2,686,775	\$270	\$2,015,082
Above 1st storey	67169.4	\$385	\$25,860,21	\$280	\$18,807,428
	Quantity	\$/unit		\$/unit	
Balconies	34	\$25,000	\$850,000	\$25,000	\$850,000
	Cost per month	# Months	Cost	# Months	Cost
Schedule Costs (Monthly	\$50,000	18	\$900,000	16	\$800,000
TOTAL			\$30,296,98		\$22,472,509
EMBODIED CARBON					
		Concrete		Submission	
	Sq ft	Embodied	Total	Embodied	Total
Total Building Sq Footage	74632.6	6.69	499219.28	2.7	201508.153

The proforma points to general project benefits, such as reduced carbon emissions and cost compared to concrete construction. However, some advantages of the FAM system are not fully captured in the table, such as faster construction timelines due to prefabrication and standardization of unit design, and the ability to scale this system across similar sites for further cost efficiencies. Together, the proforma demonstrates that this system is not only feasible but establishes a replicable path toward affordable, low-carbon, family-oriented urban housing.






Verdure is a co-operative housing development for the KKS Nations. The project provides a variety of unit layouts, communal amenities, exterior gathering spaces. The staggered massing articulates the public street edge, providing frontage for live-work loft studios and a large market. The courtyard scheme shelters a restored historical stream running along the northern side of the site, directly adjacent to a ceremonial gathering space, prioritizing cultural safety and reconciliation. The project uses primarily GLT timber panels, beams, and columns which were chosen as a more readily available, local and indigenous supplied material compared to CLT products.

Unit	Area	Units/Level	Levels	Area(sq.ft.)	Area(m2)	Total Units	Total Beds
Rooftop Amenity	4864			4864	451.88		
Commercial				2110.6	196.08		
BikeA				192	17.84		
BikeB				192	17.84		
Daycare	628	1	1	628	58.34		
Laundry	628	1	1	628	58.34		
Gym	628	1	1	628	58.34		
CoreB	418	1	12	5016	466.00		
CoreA	523	1	8	4184	388.70		
1Bed-A	628	1	4	2512	233.37	4	4
1Bed-B	576	6	7	24192	2247.49	42	42
1Bed+Den	683	1	8	5464	507.62	8	8
LoftA-L1	628.2	1	1	628.2	58.36		
LoftA-L2	362.2	1	1	362.2	33.65	1	1
LoftB-L1	570.9	6	1	3425.4	318.23		
LoftB-L2	335.6	6	1	2013.6	187.07	6	6
LoftC-L1	528.4	1	1	528.4	49.09		
LoftC-L2	306.7	1	1	306.7	28.49	1	1
2Bed-A	780	1	7	5460	507.25	7	14
2Bed-B	734	1	8	5872	545.52	8	16
2Bed-C	886	1	11	9746	905.43	11	22
3Bed	1416	1	3	4248	394.65	3	9
Ammenity Interior				2268	210.70	91	123
Ammenity Exterior				4864	451.88		
Commercial Area				2110.6	196.08		
Residential Area				64758.5	6016.21		
Total Building Area				78337.1	7277.69		

Resi Area	Site Area	FSR		
64758.5	20130.83	3.22		

Project Data





TWO BED UNIT

AMENITIES - SHARED LAUNDRY, DAYCARE, GYM AND BIKE PARKADE


ONE BED UNIT


THREE BED UNIT

LIVE WORK LOFT UNIT

VERTICAL CIRCULATION

Programming Diagram






Site Plan




8-Storey Section



Courtyard Exterior Corridor







Level 9-12



West Elevation Tall Tower Section South Elevation

MASS TIMBER PROPOSAL

CONCRETE PROPOSAL

CLT: 642.187 m³

CONCRETE: 2648.06 m³


GLT: 1100.152 m³ **MPP:** 46.32 m³

CONCRETE: 905.72 m³


STEEL: 1.032 m³


GWP: 437 kgCO2eq/m²


GWP: 602kgCO2eq/m²












WOOD TO WOOD CONNECTION



The project explores innovation in structural connection to simplify the erection process, engineering requirements, and coordination between multiple materials such as steel connectors. Utilizing wood to wood connection reduces fabrication time, installation time, and coordination time. Thus, saving money on the overall project from start to finish. Values for GLT products could not be directly sourced, the values shown are an estimate.

Simple, uniform rectangular layouts are utilized for simplified construction process. Values collected for the construction costs are interpolated from CLT estimates using a similar structural layout. We believe CLT is expensive sue to lack of supply. GLT has been used as the primary structural floor panel as an alternative, ensuring more opportunity for local suppliers. GLT is stronger than CLT when used in a single direction and therefore uses less wood.

Economic Rationale

FSR	3.483820588
Lot size (sq ft)	20,131
Building sq ft Above Grade	70132
Building efficiency (%)	85
non saleable/rentable (sq ft)	10519.83
saleable/rentable (sq ft)	59612.37
Total Stories above grade (#)	12
Total Stories (#)	12
Base floor (#)	1
Above 1st storey (#)	11
Stories below grade (#)	0
Units (#)	91
Bedrooms (#)	123
Amenity space (sq ft)	2268
Non-residential (sq ft)	2110.6

CONSTRUCTION COSTS					
		Concrete		Timber	
	Square footage	\$/sq ft	Cost	\$/sq ft	Cost
Below grade	0.0	\$315	\$0		\$0
Base floor	12071.2	\$360	\$23,855,724	\$200	\$13,253,180
Above 1st storey	66265.9	\$405	\$26,837,690	\$250	\$16,566,475
	Quantity	\$/unit		\$/unit	
Balconies	91	\$25,000	\$2,275,000	\$25,000	\$2,275,000
	Cost per month	# Months	Cost	# Months	Cost
Schedule Costs (Monthly Overhead)	\$50,000	18	\$900,000	16	\$800,000
TOTAL			\$53,868,414		\$32,894,655

Real Estate Pro Forma

Summary							
Gross Potential Income (GPI)	\$	2,883,412.80					
LESS Vacancy + Credit Loss	\$	51,901.43					
EQUALS Effective Gross Income (EGI)	\$	2,831,511.37					
LESS Operating Expenses	\$	1,132,604.55					
EQUALS Net Operating Income (NOI)	\$	1,698,906.82					
LESS Mortgage Payments	\$	2,828,010.30					
EQUALS Cash Flow Before Tax	-\$	1,129,103.48					


Potential Gross Income									
Base Rent Income/Month	Square Feet	Average Rent/Sq Ft*	Av	erage Rent	No. of Units	1	Total/Month		Total/Year
1Bed-A	628	\$3.50	\$	2,198.00	4	\$	8,792.00		
1Bed-B	576	\$3.50	\$	2,016.00	42	\$	84,672.00		
1Bed+Den	683	\$3.75	\$	2,561.25	8	\$	20,490.00		
LoftA	990.5	\$4.00	\$	3,962.00	1	\$	3,962.00		
LoftB	906.5	\$4.00	\$	3,626.00	6	\$	21,756.00		
LoftC	889.1	\$4.00	\$	3,556.40	1	\$	3,556.40		
2Bed-A	780	\$4.00	\$	3,120.00	7	\$	21,840.00		
2Bed-B	734	\$4.00	\$	2,936.00	8	\$	23,488.00		
2Bed-C	886	\$4.00	\$	3,544.00	11	\$	38,984.00		
3Bed	1416	\$3.00	\$	4,248.00	3	\$	12,744.00		
TOTAL INCOME						\$	240,284.40	\$	2,883,412.80
*Average rent per squre foot taken from Liv.com: htt	ps://liv.rent/blog/uncategorized/au	gust-2025-metro-vancouver-rent-							

*Average rent per squre foot taken from Liv.com: https://liv.rent/blog/uncategorized/august-2025-metro-vancouver-rereport/#:~:text=As%20of%20August%202025%2C%20the,Get%20Your%20Free%20Estimate


	Vacancy and Non-Payments					
Vacanacy	Average Rate of Vacancy*	Loss	s Per Month	Los	s of Per Year	
	0.80%	\$	1,922.28	\$	23,067.30	
Credit Loss	Est. Rate of Non-Payment	Loss	s Per Month	Los	s of Per Year	
	1%	\$	2,402.84	\$	28,834.13	
TOTAL LOSS		\$	4,325.12	\$	51,901.43	
"Average vacancy rate taken from CHMC Fall 2024 Market Report for Metro Vancouver: https://www.cmhc-schl.gc.ca/professionals/housing-markets-data-and-research/market-reports/rental-market-reports-major-centres?selected=vancouverDiv						


Opera	ting Expenses						
Average % of EGI*		Total					
40%	\$	1,132,604.55					
"Average percentage of operating expenses taken from https://www.bullperre.com/insights/operating-expense- ratios#text=//win4%20b%201ypical%20operating.expenses%20can%20vary%20bet ween%20municipalities.							
Mortgage Payments							
Loan Amount	\$	32,894,655.00					
Interest Rate (Annual)		6%					
Term (Years)		20					
	•	005 005 50					

















DTT-D-01








Gathering Space



1:0.95











Tsawwassen Apartments

Design intent of this project reflects previous high-rise modern buildings by the Tsawwassen Nation in the Vancouver metro, the traditional longhouse and communal living.


Another precedent for the sake of comparison is a partial modular project in New York City by Gluck+, The Stack, which has a conventional steel and concrete structure extending up to the ceiling of the podium level. Then six floors of factory built light frame modular units are stacked on top of one another by crane like shipping containers. In the Tsawwassen project, hinge-connected glued laminated timber (GLT) columns and beams support factory built modular cross-laminated timber (CLT) apartment modules. The trucked in half-units complete with plumbing and appliances fit into the site assembled frame similar to a jungle gym and are paired together with splines.

This scheme is very bare bones, designed to lower costs and reflect traditional modestly appointed building styles, yet the buildings are designed to resist axial and lateral loading conditions. For example, there are alluvial soils capable of liquefaction in an earthquake and there's a coastal tsunami hazard. The selected solution is slab on grade supported by driven piles, pile caps and grade beams. There's no basement because of the high water table except for the elevator pit.





- 1. Gross Floor Space Ratio 276,680SF/88.273SF= 3.13
- 2. Foundation per Soils and Structural. Here proposed perimeter wall over slab on grade over grade beam over pile cap over 14" dia driven pile
- 3. Permeable concrete paver at drive and parking
- 4. Two twelve story mass timber buildings are technically feasible in the Metro Vancouver area.
- 5. Transit oriented development favors multifamily occupancy over existing single family development.



1. Podium 1" = 30'

- 1. Nominal module sizes for cross-laminated timber CLT apartments indicated
- 2. Units inserted into a jungle gym structure consisting of glue-laminate timber (GLT) or glulam hinge connected structural members
- 3. Elevator shaft, typical, is mass timber, separate supplier.
- 4. Exit stair, typical, is mass timber by separate supplier



1. Party wall unit to unit, 1-hr, STC >= 50:

CLT each side, $1\frac{1}{2}$ " service cavity with mineral wool + hat channel with sound isolation clip or resilient channel (RC1) + 2 x 5/8" Type X

2. CLT interior exposed:

Exposed CLT interior (no gypsum) → air/vapor control layer at exterior of CLT as required → continuous insulation (mineral wool or rigid Cl) on outside of CLT → water resistive barrier (WRB) → rainscreen/cladding


3. Wet wall (quiet):

2×6 + 1" gap + 2×4/2×6, mineral wool both, 5/8" gyp (2× Type X on rated side).


Overall 12"–14" width. Plan mini-shaft (18–24" W × 12–18" D) at stack.

4. Unit ← corridor 1-hr, STC≥50:

Corridor face: 2× 5/8" Type X on furring + mineral wool; Unit face: 1½" service cavity + 5/8" Type X. 1. Balcony, typical, omitted for safety.




3D-05 Module Perspective




3D-04 Jungle Gym






West Elevation 1" = 50'



South Elevation



- 1. Ceiling height nominal 9'
- 2. Floor/ceiling unit to unit tested assembly 1 hr STC >= 50, IIC >= 50 expose architectural finish CLT underside ceiling treat top side 10 mm resilient underlayment + $1\frac{1}{2}$ 2" gypcrete topping + optional finish floor 3. Same assembly as in 2 above, add thin acoustic treatment to ceiling if IIC performance found ineffective

Timber Town.

This project is an exploration into how a hybrid mass timber Post-and-Plate and steel construction system, combined with efficient residential layouts and thoughtful landscape integration, can create high-quality, communityoriented urban living environments that challenge conventional construction systems like the concrete tower-and-podium.

Timber Town envisions a vibrant, highdensity neighbourhood that seamlessly integrates the natural beauty of Vancouver with the warmth and sustainability of mass timber construction. At its core, this project aims to create high-quality

living environments that foster deep connections - both to nature and to the community - through thoughtfully considered site planning, building design, and biophilic principles. Drawing from lessons learned in

established mass timber projects, we employ a Post-and-Plate construction system, chosen for its speed, efficiency, and tighter column grids compatible with residential unit layouts. This method encourages vertical development over horizontal sprawl and the efficient footprint of each tower preserves more of

the ground plane for shared outdoor spaces. These open areas, inspired by the Tsawwassen First Nation's core values of gathering and maintaining connection with the lands, are conceived as extensions of the residents' living spaces and a way to connect the surrounding neighbourhood to Timber Town as well as to the adjacent forest and waterfront. The landscape is not an afterthought but a vital part of the neighbourhood, functioning as both a natural corridor and a public amenity, creating a development that feels cohesive, sustainable, and deeply rooted in its place.





Compact, Simple, & Repetitive. This proposal challenges the conventional concrete tower-and-podium model that is increasingly common in Vancouver's cityscape. In the typical tower-and-podium model, the podium serves as a structural and mechanical transfer zone as well as access to on-site parking, often a costly and complex intermediary that supports the tower above. The ubiquitous use of concrete to facilitate this massing exacerbates the resource intensiveness of new developments.

In Timber Town, tall, compact mass timber towers meet the ground directly, giving back much of the ground floor to it's residents and the community.



Concrete Tower-Podium Construction

- carbon intensive concrete construction
- complex structural and mechanical transfers
- excavation and concrete required for on-site parking
- large building footprint
- minimal outdoor public space
- secondary beams require additional coordination

Key reform to on-site parking requirements would allow a significant reduction to the building footprint and reliance on the use of concrete. By eliminating the podium, we reduce the building's footprint, and the tower instead rises from a compact base, supported by a straightforward, repetitive structural grid. Each tower utilizes the Post-and-Plate system to simplify construction and removes the need for costly structural and mechanical transfers.




Hybrid Mass Timber & Steel Post-and-Plate Tower

- sustainably sourced mass timber
- simplified and repetitive structure, faster assembly
- limit on-site parking, employ contemporary solutions
- compact building footprint
- maximized outdoor public space and landscape
- flat plate allows for simplified MEP installation





Left: In the evening, the towers emit a warm glow. Amenities throughout the landscape offer people places to connect. Above: Balconies give each tower its distinctive exterior character, offering each home a generous extension of their indoor spaces.





Connection to Land. The efficient building footprints provides an opportunity to transform the site into community-oriented land with an abundance of natural amenities that create surprising, memorable, and joyful moments for rest, play, and discovery.

Inspired by the Tsawwassen First Nation's values of connection to land and water, a water collection pond anchors the heart of the site, storing rainwater for landscape irrigation and community amenity use. The site is bookended on the south residential zone by public art displays, and on the north by a communal fire pit

overlooking the adjacent natural area and public waterfront.

Small scale commercial spaces that are compatible with a tighter structural grid are mixed in throughout. We strongly believe diversifying allowable uses on the site creates a vibrant focal point for the larger neighbourhood.


Residential amenities are all oriented to face the heart of the site and an abundance of community spaces are dispersed throughout: indoor and outdoor community rooms, walkways with seating, and covered outdoor pavilions.

Left: 1. Water collection pond / Water garden 2. Firepit 3. Public art 4. Playground 5. Outdoor community room 6. Indoor community room 7. Covered Outdoor Pavilion 8. Residential lobby 9. Residential amenities 10. Small-scale commercial spaces 11. Car share parking / service access 12. Waterfront trail 13. Boardwalk 14. Dock / Bank fishing area (11 to 14 are envisioned outside of site boundaries)

Post-and-Plate. Mass timber case studies reveal a preference for simplified structural systems. Inspired by the success of Brock Commons Tallwood House, this proposal leverages the Post-and-Plate system's compatibility with residential layouts – using a tighter column grid that aligns naturally with apartment room configurations. Each proposed tower avoids cantilevers, ensuring columns track uniformly from bottom to top. This approach establishes


a simple, consistent structural grid throughout the core. Variation is then introduced at the building perimeter, where exterior-facing corners and independent steel balcony systems are utilized to create layouts that feel generous and flexible while maintaining structural efficiency.

The Post-and-Plate system enables thinner, more efficient floor assemblies that can provide uninterrupted wood ceilings that give interiors a warm, loft-like character.



The balconies are conceived as pre-fabricated, modularized steel frame units that are self-supporting and tied back to the building at discrete points. The intent of de-coupling the balcony structure from the mass timber building is to reduce construction complexities typical of cantilevered structures and have more control at potential thermal bridging points. The independent structure also allows pre-fabrication to occur in tandem and for flexibility in phasing the balcony installation.


- 1. Steel frame building core
- 2. Point supported CLT panels
- 3. 12" x 12.5" 16c-E DF glulam column
- 4. 12' x 10' structural grid
- 5. CLT shear wal
- Balcony steel frame independent from mass timber structure



- Pre-fabricated building envelope
- 2. Point supported CLT panels
- . 12" x 12.5" 16c-E DF glulam column
- 4. 12' x 10' structural grid
- 5. Pre-drilled slab openings







3.5" thick 3 ply E1 CLT deck 8.5" x 10" 24f-E DF glulam purlin 8.5" x 14.5" 24f-E DF glulam girder 14.5" x 15" 16c-E DF glulam column

Total structural depth: 6.9"

Total structural depth: 18.3"

Compared to Post-and-Beam systems, Post-and-Plate construction uses fewer structural members, allowing for faster build times and reduced material complexity. This efficiency makes it possible to fit more floors within the same building envelope without sacrificing desirable ceiling heights which is key for sites with stringent zoning constraints. Additionally, the flat plate slab simplifies MEP installation by eliminating the need to route services beneath secondary beams.


High Density Living. Surrounded by nature, each mass timber tower is designed to maximize exposure to natural light and provide expansive views of the City, water, and open landscape below. The tower's 'serrated' facade increases the number of corner windows, giving every living unit a panoramic view of its surroundings. This design enhances airflow and brings ample daylight into each room - a significant advantage over conventional 'shoebox' apartments. This greater access to daylight and fresh air can reduce occupants' reliance on electrical and mechanical systems, lowering energy consumption over the building's lifespan. Steel-framed balconies, independent of the mass timber structure and thermally broken from the enclosure, are located at the tower's perimeter. Conceived as 'backyards in the sky,' these generously sized terraces function as outdoor living rooms and spacious extensions of the interior. By staggering the terraces both horizontally and vertically, each outdoor space achieves a double-height ceiling. The simple and repetitive Post-and-Plate structural grid offers the flexibility to create varied yet straightforward unit layouts to accommodate diverse contemporary living arrangements.



On lush, double-height balconies, residents can enjoy the outdoors surrounded by greenery and mountain views. The steel-supported balcony, system tied back to the mass timber superstructure, creates spacious outdoor living rooms that blur the line between interior and exterior.



Connection to daylight and nature is a priority. The apartments emphasize outdoor living, with interiors that open onto generous balconies. Building corners are designed to maximize views and bring daylight into each room.



- 1. Steel frame building core
- 2. Studio unit
- 3. 1 Bedroom unit
- 4. 2 Bedroom unit
- 5. 3 Bedroom unit
- 6. Steel frame balcony system

The simple and repetitive Post-and-Plate structural grid offers the flexibility to create varied yet straightforward unit layouts to accommodate diverse contemporary living arrangements.



Building (on) a Legacy. As more existing neighbourhoods undergo densification, mass timber construction sites offer the benefits of being cleaner and quieter, with reduced construction timelines. Timber Town aims to be a great neighbour - bringing value by reinforcing a sense of place and prioritizing a sustainable approach in both the buildings and the land. We also believe in balancing risk without sacrificing priorities of quality, dignified housing: Structural systems should be straightforward and floor plates compact while designing to maximize light, air, and access to nature.


Initially, costs for mass timber high rise construction may be higher than it's concrete equivalent, especially in the early stages of the industry's growth. To alleviate financial roadblocks, we believe that mass timber projects that provide significant public amenities as Community Amenity. Contributions, such as in Timber Town's aims, should receive subsidy and investment at both the local and federal levels.




Construction Costs		Concrete		Timber Town		
	Square footage	\$/sq ft	Cost	\$/sq ft	Cost	
Below grade		\$315	\$0	\$299	\$0	
Base floor	23,250	\$360	\$8,370,000	\$403	\$9,369,750	
Above 1st storey	255,555	\$385	\$98,388,675	\$431	\$110,144,205	
	Quantity	\$/unit		\$/unit		
Balconies	176	\$25,000	\$4,400,000	\$15,000	\$2,640,000	
	Cost / Month	# Months	Cost	# Months	Cost	
Schedule Costs (Monthly Overhead)	\$50,000	36	\$1,800,000	27	\$1,350,000	
		TOTAL	\$112,958,675		\$123,503,955	

Embodied Carbon (based on the Fast + Epp	Bay Design Tool)	Concrete		Timber Town	
	Sq ft	Embodied Carbon kg/sq ft	Total Carbon	Embodied Carbon kg/sq ft	Total Carbon
Total Building Sq Footage	278,805	6.69	1,864,932	3.55	989,758


While timber construction may at present be costlier than it's concrete equivalent, the inherent benefits of timber such as reduction in the amount of embodied carbon and improvements in construction timeline (25% reduction assumed based on industry studies) are key considerations particularly when material and labour costs for timber construction are projected to reduce alongside industry growth. For Timber Town, there was also an assumed reduction in costs for the de-coupled balconies due to efficiencies in pre-fabricating off-site and simplifying installation.



Timber Town aims to be a great neighbour - bringing value by reinforcing a sense of place and prioritizing a sustainable approach in both the buildings and the land.




The ongoing climate and housing crises have step by step challenged us to find new ways of living in urban centers. "The Tower Garden" emerges as a design methodology that seeks to reintroduce, through architecture, aspects of the traditional lifestyle and techniques of the Tsawwassen people. We aim to create a harmonious relationship between humanity and nature, market and community, tourism and local demands. This is achieved through multiple architectural programs.






The method is based on two main structures: the tower, where residential units are concentrated, and the communal market, inspired by Longhouse architecture, which features an internal courtyard for recreation and terraced geometry.




tower


communal market

Due to the site's proximity to the water, we chose to create a connecting axis that links with the watercourse. Additionally, local ecological restoration will be promoted along this axis using native species, thereby integrating the architectural project with nature.





analysis of socioenvironmental factors and local laws.




design of pedestrian pathways and connection to the natural environment



3. development of a stepped market, providing terraces for public uses.



4. tower dimensions defined by the demand for residential modules.



V. vertical building services module.

Our design method is guided by five architectural principles:

Autonomous Design: People aren't static, so architecture must adapt to the demands of the present and the future.

Social Inclusion: We understand that Canada is a culturally diverse society, with families of different sizes, incomes, and generations. Our architecture needs to reflect this plurality.


Human-Nature Ecosystem: The design should integrate with the flow of biodiversity in urban centers, providing an ecological infrastructure that allows for harmony between people and nature.

Solidarity Economy: The complex should provide commerce and services for the community, acting as a democratic space where small, medium, and large businesses can coexist.

Artistic Expression: The project must value and incorporate the traditional arts of the Tsawwassen into its aesthetic design. The goal is to highlight their cultural identity and keep traditional artistic techniques alive.


We translated these principles into design strategies and architectural programs that promote continuous human-animal interaction throughout the day. In this way, the architectural ensemble sustains a vibrant and dynamic urban-ecological system.






1. The communal market's structure 2. Above the public market, starting is lighter and more affordable, cutting construction costs and time. Structural modules measure 4x4x4 meters, half the size of tower modules.


from the third floor, rise the residential towers. Its structural modules measure 8x8x4 meters, with reinforced corner columns to resist torsional effects.



3. The infrastructural core rises within the tower, with 50 cm-thick concrete walls. In addition to elevators and the emergency stairwell, it also contains services wall and waste chutes.



4. A total of nine residential floors are built. The rooftop level will be used for the installation of solar panels, water tanks, and service equipment.



DTT-D-04

5. Compact community urban gardens are arranged along the terraces of the residential tower. These garden will host native plant species, helping to preserve local fauna and provide organic food

community market

a community gardens

vertical circulation

d fabric coverings

businesses

b leisure

f multispecies park


residents' entrance

g event square

h promenade

i parking lot

The first three floors are designated for commercial activities, including a community market with Initially, the layouts for the commercial spaces are a flexible, independent structure. This space is inspired by the architecture of the Tsawwassen people's Long Houses and, therefore, houses all the public life of the complex. The goal is to provide a dynamic environment for services, recreation, work, and consumption for residents and the neighborhood. Located along the sides adjacent to the parking area are public workshops dedicated to community production, with activities focused on craftsmanship, culture, and gastronomy. At its center, the events plaza offers a large space for unplanned, routine uses such as street fairs, festivals, and cultural and political events. Above it is the residents' communal amenity floor, which includes recreational courts and community gardens for an organic food alternative. Finally, the market's stepped geometry creates terraces for public use and greenery. The open parking serves residents and visitors, optimizing space and reducing vacancy.



handicrafts

industrial kitchen

woodworking

gardering

jewelry

6 furniture

sewing


8 tapestry

mechanics

g repairs

construction system

delivered in various sizes, as we aim to democratize access to the complex's infrastructure. The structure was designed as a modular joinery system, allowing parts to be easily produced in the carpentry workshop and installed with minimal resources. The structural modules are 4x4x4 meters; thus, columns and beams share the same dimensions. Whereas partitions is 1x4 meters, endors are allowed to install doors, storefront glazing, and solid partitions. This ensures the architectural complex can be modified to meet changing demands.



DTT-D-04



live and grow

We designed homes that can keep up with each family's life journey. The whole inside of the building was created with a modular system, which can be altered according to the residents' demands.




It all begins with a student discovering a new city



Over time, a new family emerges, requiring more space in their home.



The neighbor next door is willing to sell an empty module of their apartment.




The family disassembled the walls that separated the apartment and expands their home.




endure even amidst the changes of time.

The walls are secured using rods anchored to the floor and ceiling, in modules of 2-by-2 meters, meanwhile, the walls may be assembled with 2-by-4 meter prefabricated panels. Therefore, to increase or decrease spaces, it is simply necessary to dismantle the structure and reassemble it in the next module, without generating waste. Thanks to the presence of the community carpentry workshop, the walls and fittings can be produced locally.

Initially, four main housing typologies are planned, aimed at different family profiles. The residences are distributed along the infrastructural core, with side services walls that accommodate the entire hydraulic and sewage infrastructure. This way, residents can arrange wet areas along the entire infrastructural axis without requiring extensive reforms.






- a structural wood fitting for the division module
- **b** closing panel, which may or may not include a door
- interlocking and alternating floors within the module

Thus, different types of occupation can be created.

- singles, couples, and tourists (1 bedroom 32m²)
- 2 elderly and small families (2 bedrooms 68m²)
- 3 medium-sized families (3 bedrooms 100m²)
- a large families (4 bedrooms 136m²)
- service wall













At the same time, the popular market and the facade of the residential tower are adorned with tapestry pieces crafted by local artists. This gives the building a distinctive aesthetic that stands out in the urban landscape and positions it as a potential tourist landmark for the city

facade design









empowering small artisans through production demand and economic activity





DTT-D-04

preserving and promoting artistic and cultural expressions within contemporary Canadian society


panel framing

The use of locally crafted tapestries not only supports Tsawwassen's smallscale artisans, but also contributes to preserve and promote the artistic and cultural heritage of Canada's Indigenous The communities. panels feature wooden and frames are retractable, allowing natural airflow and daylight to enter the residential units





promenade design








urban ecology

Throughout the entire building, we propose a multi-species landscape project that interacts with human, animal, plant, and water life. To achieve this, we will introduce native trees and shrubs species that can bloom and produce fruit in different seasons. This will provide urban wildlife with a continuous and organic food source. The species will be arranged as follows: (i) Ornamental plants will be placed mainly near the promenade and along the residential tower's balconies; (ii) Vegetables, medicinal plants and edible seeds will be planted in the community gardens, focusing on foods found in the local, traditional Tsawwassen cuisine; (iii) Flood-tolerant species will be planted near the riparian forest park border. This revitalization will also help with decarbonization and the recovery of native animal and plant presence in the city, as well as help mitigate the effects of urban heat islands.



areas

87337 lot size (ft2) building sq ft 148734 above grade (ft2) **FSR** 1.703 Building 85% efficiency (%) non saleable/ 22310.16 rentable (sq ft) saleable/ 126424.24 rentable (sq ft)

stories below grade 0 per tower base floor 1 per tower base floor 11 per tower 12 per tower total stories (units)

residential commercial residences (units) bedrooms (units) 324 residents (units) 101,244 area (ft2)

commercial (units) 54 area (ft²) amenity space (ft2) 17,774

construction costs

residential tower

(8m x 4m x 4m modules, glulam beams with purlins)

	area (ft²)	\$/sq ft	\$/sq ft	\$/sq ft	cost
below grade base floor	0 1327	\$315 \$360	0 477,720	\$341 \$459	0 609,093
above 1st storey	99917	\$385	38,468,045	\$491	49,059,
balcony	quantity -	\$/unit 25,000	\$/unit -	\$/unit 25,000	cost -

concrete

mass timber

community market

(4m x 4m x 4m modules, glulam beams with purlins)

		concret	te	mass timber		
	area (ft²)	\$/sq ft	\$/sq ft	\$/sq ft	cost	
below grade base floor above 1st storey	0 22335 25155	\$315 \$360 \$385	0 8,040,641 9,684,775	\$289 \$389 \$417	0 8,688,359 10,489,74	
shedule costs (monthly overhead)	cost (per month)	month	cost	month	cost	
	50,000	18	900,000	13	650,000	
			181	total 69,496,	442	

embodied carbon residential tower

total building Sq footageft 101,244 embodied carbon (kg/sq ft) concrete mass timber total carbon concrete mass timber 677,223

community market total building Sq footageft 47,490 embodied carbon (kg/sq ft) concrete mass timber total carbon concrete mass timber total carbon mass timber concrete

433,930


994,887

DTT-D-04 waterproof membrane reinforced concrete slab wooden slatted ceiling trellis-style guardrail for climbing plants sliding art panels concrete path garden for the cultivation of small-sized plants H = 30cm

CO-RISE

A Prototype for Sustainable Living

This project redefines affordable housing through a mass timber, co-operative model rooted in Tsawwassen's cultural and ecological landscape. By integrating resident ownership, flexible living arrangements, and shared amenities, it establishes a benchmark for quality and affordability that goes beyond conventional housing delivery. The design leverages prefabricated timber systems for speed, sustainability, and lifecycle efficiency, while providing identity to the local community.



Context & Place

- Situated in Vancouver, on ancestral Tsawwassen land, within a marshland landscape oriented to the river.
- At the edge of TOA3 zoning, 15 minutes from rapid transit, shops, and
- Surrounded by a mono-residential neighbourhood needing diversity.

Opportunity


- Establish a community anchor that combines cultural, commercial, and public infrastructure.
- Create a safe, walkable hub that links housing with everyday services and sustainable transportation.
- Demonstrate a replicable model: by multiplying hubs like Co-rise across the neighbourhood, the area can evolve from mono-use suburbia into a connected, walkable, and identity-rich community.

Co-operative Housing Model

- · Resident-owned, ensuring long-term affordability.
- Flexible layouts and shared amenities build resilience.
- Prefabricated timber construction reduces costs, accelerates delivery, and supports sustainability.







1 Gateway Hub

Threshold location: Positioned between a local school and regional transit hub, linking education, mobility, and community life.

2 Village Heart

New plaza acts as a connective tissue, prioritizing pedestrian safety — especially for children walking to school — and reinforcing a village-like pattern of walkable proximity.

3 Ceremonial Spine

A strong north-south axis organizes the plan around a ceremonial procession, anchoring arrival at the street and extending toward the river. This movement establishes a cultural and spatial narrative that honours Tsawwassen ways of gathering and connecting to water.

Courtyard

A secondary east-west axis connects adjacent buildings into a shared open courtyard, creating permeability and reinforcing a sense of communal stewardship.

5 Longhouse

At the heart of the shared courtyard sits a timber community centre, imagined as a place of ceremony, shared meals, learning, and intergenerational connection- an integral part of Tsawwassen culture. Here, stories are passed on, neighbours gather, and community life unfolds in daily rituals and seasonal events.

6 Elders

Celebrates elders as cultural anchors within the community, placed in the most private and protected location of the neighbourhood.

Mobility Hub

A mobility hub with e-bikes and e-car rentals on site, encouraging alternative and sustainable modes of transportation.

8 River Connection

To the south, a pier extends toward the Fraser River, evoking Tsawwassen's deep connection to the water and its fishing culture. This water edge also offers future potential as a transportation node — linking the community with the broader region through ferries or river shuttles.





Commercial





Residential

BOH

Full Life Cycle

Architecture is no longer defined by the moment of construction, but by the entire life cycle of a building. Our proposal looks beyond completion, designing for how it is made, lived in, adapted, and ultimately disassembled. Every stage—from material sourcing to reuse—is considered, ensuring a system that delivers durability, carbon efficiency, and long-term value. This is not just a building—it's a circular framework for living.



1.Production Responsibly sourced FSC-certified timber

fied timber Prefabricated panels and components Digital material passport created for each unit





Refurbishment and reuse of components



On-site assembly of prefabricated panels and modules Just-in-time delivery minimizes staging and site waste Core poured on-site; rest dry-assembled



3. Use & Maintenance

Modular interior allows unit adaptability over time Exposed wood aging naturally—low maintenance




4. End of Life

Non-glued connections allow demounting Materials sorted for reuse and remanufacturing No mixed composite waste



Structure



We employ a hybrid timber structure-mass timber columns and beams with CLT floor panels-to reduce embodied carbon, paired with a concrete core to meet BC Building Code requirements for fire protection and seismic performance.





We utilize a 3.6 m structural span for residential units and a 7.2 m span for ground-floor commercial spaces, enabling both programmatic flexibility and efficient on-site delivery of prefabricated components. This span strategy also optimizes material use, reducing structural costs while supporting modular construction logic.







Facade

Modular: A single facade unit serves as the versatile base, adapting across the compound to create a unified yet diverse aesthetic full of personality.


Flexible: The same unit transforms—into window frames, shaded balconies, or striking geometric accents—tailoring to each space's needs.

For the elders' section, CNC machine technology carves intricate patterns, drawing inspiration from Tsawwassen art to honor cultural heritage.


Sustainable doesn't mean boring!



DTT-D-05
Units




The open structural grid supports highly adaptable layouts. By concentrating services within the first bay, the remaining unit space enjoys taller ceilings and a more generous interior atmosphere. With a compact core and a floorplate efficiency of 88.6%, the design maximizes usable area—supporting affordability, flexibility, and future-proof planning.



The modular grid enables a diverse mix of unit sizes—from compact 1-bedroom apartments to spacious 4-bedroom family homes—supporting intergenerational living and long-term adaptability.

From grid to home




The 3.6 m structural grid yields a 13 m² room—an ideal unit of space that balances livability with modular efficiency. This compact module serves as the foundation for all apartment layouts, easily configured as a bedroom, kitchen, or living room. Over time, the apartment can grow and adapt to evolving household needs—such as welcoming a new family member or shifting functions without structural changes. This diagram illustrates how a simple, repeatable unit becomes a richly programmed living environment through modular logic and off-site prefabrication.



System



Our system rethinks the high-rise as a low-carbon. This project demonstrates how a prefabricated mass timber system can deliver cost efficiency, carbon reduction, and architectural quality within a high-rise context. By carefully choosing our materials, we achieve a 60% reduction in embodied carbon and nearly 5% reduction in overall construction costs. Prefabrication shortens the construction schedule while enhancing precision and reducing waste. The result is a system that not only meets stringent code requirements but also sets a new benchmark for affordability, sustainability, and design excellence in tall timber construction.



Submission

Concrete baseline

CONSTRUCTION COSTS					
		Concrete		Submiss	ion
	Square				
	footage	\$/sq ft	Cost	\$/sq ft	Cost
Below grade	0	\$315	\$0	299	\$0
Base floor	5037.51	\$360	\$1,813,504	385	\$1,939,441
Above 1st storey	95712.691	\$385	\$36,849,386	409	\$39,146,491
	Quantity	\$/unit		\$/unit	
Balconies	114	\$25,000	\$2,850,000	\$7,300	\$832,200
	Cost per	#		#	
	month	Months	Cost	Months	Cost
Overhead)	\$50,000	18	\$900,000	12	\$600,000
TOTA	L		\$42,412,890		\$42,518,132


Interior surfaces are left exposed, eliminating the need for secondary finishes such as drywall and paint. The result is a clean, warm, and durable surface that performs as both structure and finish. This strategy alone leads to an estimated 5% reduction in total construction costs, while elevating spatial quality and

Prefabrication further enhances efficiency. Structural and envelope components are manufactured offsite under controlled conditions, then delivered and assembled with precision. This significantly reduces on-site labor and weather delays, contributing to a construction timeline up to six months shorter than conventional concrete systems.

EMBODIED CARBON			
		Concrete	Submission
		Embodi	Embodi
		ed	ed
		Carbon	Carbon Total
	Sq ft	kg/sq ft Total Carbo	n kg/sq ft Carbon
Total Building Sg Footage	258334	6.69 1728000.2	9 2.69 696000.475

Swapping concrete for CLT and glulam slashes embodied carbon by -42%—saving over 1,000 tonnes of CO2e. Our balcony system even stores more carbon than it emits.

Additionally, designed for disassembly, each system component can be reused or repurposed—supporting a truly circular building lifecycle.



Together, these design and delivery choices offset the material premium of mass timber with measurable gains in speed, performance, and lifecycle economy.

Materiality Structure



Cost ~ \$7,380

Carbon ~ 630 kgCO₂e





Cost ~ \$4,750

Carbon ~ 800 kgCO₂e

Envelope

-Cedar siding tinted black

- -50 mm Mineral Wool Rigid Insulation -Self-Adhered Membrane (AWB) -3-ply CLT Panel (90 mm)
- -Smart Vapor Retarder -Exposed CLT tinted black
- -Wood-Framed Windows, Triple Glazing



Balcony

-Timber structure + anchors -Waterproofing membrane -Wood decking -Glass railing system

Cost ~ \$5,500 / panel Carbon ~ 650 kgCO₂e per panel -18.8%

Cost ~ \$7,000/ unit -72% Carbon ~ -340 kg CO₂e -168%

(net carbon stored)

Cost ~ \$25,000 Carbon ~ 500 kgCO₂e

To meet BC Code requirements for fire safety in exposed timber, we apply a char-rated approach-carefully sizing structural members to maintain integrity under fire conditions-and integrate a high-performance

+39.6%



CO-RISE

A Prototype for Sustainable Living

Financial & Delivery

Co-rise is built on a cooperative ownership model where residents purchase shares that grant the right to occupy a unit. This structure removes the developer profit margin and ensures that any surpluses are reinvested directly into building upkeep, community amenities, or the creation of future cooperatives.

Affordability is further strengthened by reduced construction costs: prefabrication shortens the building schedule, lowering both interest and carrying costs.

A mixed-use strategy introduces commercial spaces at the ground floor, generating steady rental income that offsets annual maintenance and contributes to the reserve fund—building resilience against rising service charges.

Shared amenities such as community rooms, and a mobility hub reduce the need for larger private units. By encouraging resource sharing, Co-rise delivers smaller, more efficient apartments with lower construction and operating costs per household.

Finally, **delivery** is supported by a clear approvals pathway. The project fits within TOA3 zoning with only minor relaxations, following the standard sequence of rezoning, development permit, and building permit. Cooperative tenure is already recognized in BC law, meaning no new legal framework is required.

Height & Site Efficiency

Current BC regulations permit mass timber construction up to 19 storeys. Co-rise extends this to 20 storeys, a modest but impactful step that allows more efficient use of the site. By slightly increasing the tower height, we reduce the footprint of the high-rise portion, freeing land for complementary low-rise buildings that transition more gently to the surrounding neighbourhood. This strategy not only maximizes affordability through better land use, but also creates a more context-sensitive edge condition — balancing tall **timber innovation** with the smaller scale of adjacent residential fabric.

Submission Data

FSR	3
Lot size (sq ft)	86,111
Building sq ft Above Grade	258,334
Building efficiency (%)	88.6
non saleable/rentable (sq ft)	31,000
saleable/rentable (sq ft)	227,334
Total Stories above grade (#)	19
Total Stories (#)	20
Base floor (#)	1
Above 1st storey (#)	19
Stories below grade (#)	0
Units (#)	183
Bedrooms (#)	495
Amenity space (sq ft)	23,681
Non-residential (sq ft)	27,986





THROUGH OPTIMIZED LAYOUTS SPREAD ALONG A 8-16-24' GRID PATTERN THE PROJECT AIMS TO BE COMPLETED 100% PRE FABRICATED. REMOVING ANY BELOW GRADE ELEMENTS, ALIGNING THE STRUCTURE DIRECTLY ON GRADE, REDUCES CARBON FOOTPRINT AND CREATES A LIGHT ON THE LAND DESIGN.

REPLICABLE MODEL FOR HIGH-DENSITY HOUSING THAT IS BOTH BEAUTIFULLY BUILT AND A CATALYST FOR INDUSTRY WIDE CHANGE.

LOT SIZE = 87,250 SF
FSR = 4.8
MAX HEIGHT = 220 '
TOTAL BUILDING AREA = 416,000 SF
NUMBER OF UNITS = 280
NUMBER OF BEDS = 542
ESTIMATED COST PER SF = \$350
ESTIMATED PROJECT BUDGET = \$150,000,000

ANATO-MIZE

STRUCTURE

- EXPOSED MASS TIMBER SUPERSTRUCTURE WITH FIRE RESISTENT COATING BUILDING DESIGN ENSURES NO PUBLIC SPACE OR OPENING IS WITHIN 8 FEET OF STRUCTURAL TIMBER.
- STEEL PODIUM TO ALLOW FREE MOVEMENT ON THE LOWER LEVELS OF THE BUILDING.
- TIMBER AND STEEL ELEMENTS BASED ON A 17-6" GRID WITH CONSISTENT SIZING THROUGHOUT TO ALLOW EASIER PREFABRICATION.

FIRE RESISTENCE


- EACH UNIT COMPRISES OF A FULLY ENCLOSED 2 HOUR RATED MINIMUM RATING.
- INDIVIDUAL SYSTEMS MINIMIZE UNIT PENETRATIONS AND SIMPLE LAYOUTS ALLOW EASY FIRE SUPPRESSION.

SYSTEMS

- SELF CONTAINED ERV AND FAN COIL UNITS GIVE TOTAL CUSTOMIZATION TO THE UNIT AND ALLOW IT TO ACT STAND ALONE TO THE REST OF THE STRUCTURE. SIMILAR FOR HOT WATER SYSTEMS.

DESIGN FEATURES

- DESIGNED AS A WOOD FRAME BUILDING SITTING WITHIN A MASS TIMBER SUPERSTRUCTURE.
- LAYOUTS TAKE THE BENEFITS OF LOW RISE CONSTRUCTION, PREFABRICATION, AND STICK FRAMING TO STREAMLINE THE CONSTRUCTION PROCESS.
- STEEL PODIUM ALLOWS COMPLEX SITE LAYOUTS WITHOUT COMPROMISING FIRE RATINGS. WINDOW PLACEMENT ALLOWS EXPOSED MASS TIMBER
- STEEL PODIUM ALSO ALLOWS FLEXIBILITY WITHIN VARYING SITE CONSTRAINTS WHETHER ADDITIONAL VERTICAL NON COMBUSTABILITY, OR IRREGULAR STRUCTURAL SHAPES.



- INTUMESCENT COATED GLULAM TIMBER ELEMENTS

- STEEL CABLES CREATING A TENSILE TRIANGLE WITHIN THE SUPERSTRUCTURE

- TREATED GLULAM FINS TO REDUCE SOUTH FACING SUN EXPOSURE

- ASTM A572 GRADE 50 RATED
BOLTED STRUCTURAL
CONNECTIONS.
3 PLY CLT PANEL - EXPOSED FINISH
USED FOR UNIT ABOVE - 45 MIN. FIRE
- RATING ACHIEVED THROUGH
CHARRING.

- 2 LAYERS 5/8" TYPE-X GYPSUM WALL BOARD - 2 HOUR FIRE RATING

- FULLY ENCLOSED 2 HOUR OR BETTER FIRE RATED SYSTEM. 2 LAYERS 5/8" TYPE X GYPSUM TO ENAPSULATE EACH UNIT.

- SELF CONTAINED HIGH EFFICIENCY HRV UNIT

- HIGH EFFICIENCY FAN COIL UNIT PROVIDING HEATING AND COOLING

- OPTIMIZED RECTANGULAR LAYOUT
- MAXIMISING COMFORT AND COST

-ENCAPSULATED WINDOW COVERINGS PROVIDING AN 8' FIRE SEPERATION BETWEEN OPENINGS AND EXPOSED TIMBER

- HYBRID STEEL SYSTEM CONNECTING
THE TIMBER STRUCTURE TO THE
EARTH - ALLOWING MINIMAL
CLEARANCE FOR GROUND FLOOR USE

BORED PILES CONNECTING THE SUPERSTRUCTURE TO THE EARTH



8'



LOADING DIAGRAM

- THE DIAGRAM BELOW SHOWS THE POTENTIAL LOADING AMOUNTS OF PREFABRICATED ELEMENTS. THE DIAGRAM SHOWCASES HOW TYPICAL SIZING CAN BE EFFICIENTLY LOADED INTO A STANDARD FLATBED TRUCK. ADDITIONAL SAVINGS COMPARED TO CONCRETE.

		Concrete		Submission	
	Square footage	\$/sq ft	Cost	\$/sq ft	Cost
Below grade	0.0	\$0	\$0	\$0	\$0
Base floor	16000.0	\$360	\$5,760,000	\$400	\$6,400,000
Above 1st storey	400000.0	\$385	\$154,000,000	\$350	\$140,000,000
	Quantity	\$/unit		\$/unit	
Balconies	38	\$25,000	\$950,000	\$25,000	\$950,000
	Cost per month	# Months	Cost	# Months	Cost
Overhead)	\$50,000	18	\$900,000	12	\$600,000
TOTAL			\$161,610,000		\$147,950,000

		Concrete		Submission	
	Sq ft	Carbon	Total Carbon	Carbon	Total Carbon
Total Building Sq Footage	416000.0	6.69	2782632.32	2.69	1119040

SHIPPING ITEM COUNT + SURPLUS ESTIMATED LOADS 17'-6" GLULAM MEMBERS 56'-0" GLULAM MEMBERS 26 810 TYP. FLOOR PANELS 7.650 153 4,380 TYP. WALL PANELS

COST BASIS CALCULATION -

CONCRETE COMPARISON

CONSTRUCTION COSTS



56'LONG GLULAM VERTICAL MEMBERS - 32 PER LOAD - 3'LOAD OVERHANG



TYPICAL UNIT: PINE







TYPICAL SUPERSTRUCTURE


GLULAM TIMBER MANU-FACTURED IN 17'-6" LENGTHS. SEALED AND FINISHED IN SHOP. ASSUMED 24" x 24" GLULAM.



PLAN VIEW

8x10 'WALL/FLOOR PANELS - 9" THICK WALL ASSEMBLY - 50 PER LOAD






TYPICAL EXTERIOR SHELL

PRE FABRICATED WITHIN AN 8'GRID SYSTEM. FULL WALL ASSEMBLY PRE FABRICATED, LABELLED, AND LOADED TO MAXIMUM EFFICIENCY.





PLAN VIEW

53'-EXTENDED DECK

TYPICAL INTERIOR WALLS

FRAMED ON SITE AFTER SHELL HAS BEEN ERECTED - SITE FRAMING INTERIOR PANELS ALLOWS CONSTRUCTION TO CONTINUE IN OTHER PARTS OF THE BUILDING WHILE INSTALL OF PREFABRICATED ELEMENTS IS HAPPENING.



DESIGN-ATE

MAIN FLOORPLAN

- THE PRIMARY APPROACH TO THE MAIN RESIDENTIALM LAYOUT IS THE CONNECTION OF DIVERSITY THAT CAN BE ACHIEVED IN LARGE SCALE MULTI FAMILY BUILDINGS. EACH FLOOR CONTAINS THE ABILITY TO HOUSE SINGLE OCCUPANTS TO LARGER FAMILIES.
- CONNECTING THE DIVERSITY WITHIN THE FLOORPLAN IS A LARGE COMMUNAL SPACE THAT FEATURES A SHARED KITCHEN, BALCONY, LOUNGE SPACE AND DINING AREA. THIS SPACE ACTS AS A HUB FOR EACH LEVEL AS WELL AS AN EXTENSION TO EACH UNIT. ALSO PROVIDING AN OUTDOOR SPACE LARGE ENDI IGH TO HOLD MILLTIPLE PERSONS.
- LARGE COMMON CORRIDOR RUNNING ON THE EXTERIOR OF THE BUILDING ALLOWS THIS FLOORPLAN TO ACHIEVE LOWER SETBACK CLEARANCE FOR LIMITING DISTANCES. BY PLACING THE UNITS ON ONE SIDE OF THE BUILDING WE CAN FOCUS ON ONE COMMUNAL VISUAL ASPECT, WHICH IN THIS DESIGN IS THE BREEZEWAY THAT CONNECTS TO THE DIVER

TYPICAL UNITS

- THE TYPICAL UNITS, CREATED WITHIN THE 8 ' GRID AND A STANDARDIZED WINDOW OPENING LOCATION, MAXIMIZE SPACE NATURAL LIGHTING AND ELLIDITY
- REMOVING BALCONEYS FROM EACH UNIT LOWERS PER SQUARE FOOT COST PLACED ON THE OWNER AND ALLOWS AN EASIER FIRE SEPERATION FOR EXPOSED TIMBER.
- VERTICAL WALL FINS ENCAPSULATING THE OPERABLE WINDOWS ENSURE A MINIMUM 8 CLEARANCE IS ACHIEVED FROM OPENINGS TO EXPOSED TIMBER
- LAYOUTS CAN BE OPTIMIZED WITI INDIVIDUAL MECHANICAL SYSTEMS SUCH A HIGH FFFICIFNCY FRY LINITS AND FAN COILS



THE GROVE: COMMUNITY

SUBALPINE: 1BED 1BATH
ADA

550 SF

PINE: 2 BED 2 BATH

HEMLOCK: 4 BED 3 BATH

SPRUCE: 1BED1BATH

DOUGLAS FIR: 3 BED 2 BATH

TYPICAL RESIDENTIAL FLOORPLAN




SUBALPINE














1-AMENITY
2-FLEX
3-STORAGE
4-CRU
5-BIKE LOCKER
6-CRU
7-STORAGE
8-ENTRY
9-OFFICE
10-MECH.







MASS 1



CORRIDOR - REDUCING

LIMITING DISTANCE OPENINGS

FLOUR-ISH

MASSING

- PROGRESSING FROM ONE LARGE BUILDING
WITH A PODIUM TO A DECISIVE SEPERATION
DESIGNED TO MIMIC THE FLOW OF THE
SURROUNDING RIVER. CARBON SEQUESTRATION IS MAXIMIZED THROUGH THE
EXPOSED WOODEN MASSES.

SUN PATH

- SOUTH FACING WINDOWS ARE NATURALLY SHADED FROM EXPOSED TIMBER WALL FINS.

GROUND FLOOR

- THE BUILDING GROUND FLOOR IS COMPRISED OF STEEL I-BEAMS TO ENSURE FIRE RESISTENCE IS MET TO ENSURE FIRE RESISTENCE IS MET WITHIN CLOSE CONTACT PUBLIC SPACES.

- ENTRYWAYS, COMMERCIAL RENTAL UNITS, STORAGE, AND BIKE SPACES FILL THE MAIN FLOORPLAN. VOID SPACES WITHIN THE STEEL FRAME OFFER FUTURE DEVELOPMENTS THAT CAN ADAPT THE BUILDING THROUGHOUT ITS USE.
- PLANTERS MIMIC THE SHAPES OF RUGGED COASTAL ROCKS THAT PROTUDE INTO THE PATHS OF WATERS.
- SITE LAYOUT MAXIMIZES PUBLIC AND TENANT SPACES THROUGHOUT, CONNECTING THE STREET TO THE WATERFRONT

CALCU- REGUL-LATE **ATE**

DIAGRAM 1

- DIAGRAM 1 HIGHLIGHTS THE BENEFITS OF UTILIZING LOCALLY SOURCED, CERTIFIED, SUSTAINABLE MATERIALS.
- CURRENT EMBODIED CARBON HAS MET THE ACHIEVABLE EC TARGET.
- EMOBODIED CARBON IS SIGNIFICANTLY BELOW COMPARED TO A TYPICAL BUILDING
- THE REDUCTION OF CONCRETE TO FOUNDATIONAL PIERS HAS DRASTICALLY REDUCED THE EMBODIED CARBON IN THE PROJECT.

EXISTING

- THE DESIGN PUSHES THE CURRENT BOUNDARIES FOR MASS STRUCTURES IN ALL ASPECTS. SPECIFICALLY DUE TO EXPOSED MASS TIMBER ELEMENTS.
- THE INCREASED HEIGHT AND DENSITY WITHIN A TRADITIONAL LOW RISE AREA MAY NECESSITATE MORE NOVEL INTERPRE-TATIONS OR VARIANCES REGARDING SITE COVERAGE, SETBACKS, AND NEIGHBOUR-HOOD GUIDELINES.

Roofing

Foundations

PROPOSED DEVELOPMENT LOW RISE RESIDENTIAL PUSHING STEP CODE BOUN- PROVIDING A CATALYST OF NEIGHBOURING SITES **DARIES** SITE GREENSPACE TO DENSIFY WATERFRONT - THE MASS TIMBER STRUCTURE CONVERSION


- CONTRIBUTES TO A HIGH PERFORMANCE THERMAL ENVELOPE DUE TO THE WOODS INSULATING PROPERTIES AND CARBON SEOUESTRATION.
- EACH FLOORPLAN WILL NECESSITATE RIGOUROUS AIR TIGHTNESS TESTING, WITH MINIMAL OPENINGS ALLOWING A HIGHER STRUCTURES THAT ENSURE PROPER FIRE PERFORMANCE WALL ASSEMBLY.
- INDIVIDUAL EFFICIENCY **MECHANICAL** MINIMIZE SYSTEMS OPERATIONAL ENERGY CONSUMPTION. ALLOWING SOLAR TO PUSH ITS GRID USE.

COMPLIMENTING BC BUILDING CODE

- THE BUILDINGS DESIGN LEVERAGES RECENT BC BUILDING CODE AMENDMENTS THAT PERMIT INCREASED HEIGHT AND AREA FOR MASS TIMBER CONSTRUCTION.
- ENCAPSULATION AND ROBUST FIRE RATED SYSTEMS EXCEED STANDARD HIGH RISE FIRE PROTECTION FOR A BUILDING OF
- ACCESSIBLE UNITS ARE OPTIMIZED THROUGHOUT THE ENTIRITY OF THE DESIGN IN TIMBER CONSTRUCTION.

Net Zero EC

- THE PROJECTS APPROACH TO FULLY PREFABRICATING THE SUPERSTURCTURE AND ASSEMBLIES ALLOWS IT TO SCALE INTO VARIOUS SITUATIONS AND SITE BOUNDARIES.
- STEEL AND TIMBER HYBRID STURCTURE PRESENTS A FOUNDATIONAL WAY TO ACHIEVE LARGER MASS SEPERATION.
- THOUGHTFUL UNIT DESIGNS AND COMMUNAL SPACES CREATE A BLUEPRINT FOR DENSIFICATION THAT DOES NOT SUFFOCATE ITS OCCUPANTS.
- THIS DESIGN SETS A POWERFUL PROOF OF CONCEPT FOR THE USE OF MASS TIMBER IN HIGH RISE RESIDENTIAL CONSTRUCTION. THE TWO TOWER CONFIGURATION PUSHES THAT BOUNDARIES OF WHAT IS TECHNICALLY AND ECONOMICALLY FEASIBLE.
- BY SUCCESFULLY NEVIGATING THE COMPLEXITIES OF COMPLIANCE AND ENGINEERING REOUIREMENTS. PROJECT OPENS THE DOOR FOR OTHER DEVELOPERS TO REPLICATE THE TOWER




Substructure

SheathingPanels

Gypsum Gypsum BlownInsulation ReadyMix: Lightweight - No;

RebarSteel



longhouse echo

reimagining the longhouse in a timber tower community

Longhouse Echo is a project that brings a traditional form architecture to a contemporary setting by taking inspiration from and echoing the longhouse typology. Drawing from Tsawwassen First Nation values, the project envisions a culturally grounded, family focused and community oriented space where intergenerational living flourishes and deep connections to land and water are honored within higher-density housing forms.

The development intends to be a living expression of TFN's journey of renewal and self-determination. The core focus is creating a space that fosters collective well-being, ensuring that culture and community remain at the heart of daily life. By bringing together tradition with contemporary design practices, the project imagines a space that reflects the strength, unity, and vision of the Tsawwassen people.

concept diagram













LONGHOUSE TRANSCRIBE TYPOLOGY

ROTATE

EXTEND

SPREAD

echo of ideas


echo 1 - the symbolism

One symbol of the TFN is the eagle, both a protector and a unifier. To translate this idea architecturally: the body forms the central community space, while the wings form the residential aréas.



echo 2 - the site

The strategy for arranging the site was **increasing density** through verticality, **promoting** community in an activated central space, and connecting the land and water with the neighbourhood




DIVIDED individual lots and separate lives

the 3 lots into 1 one for higher density living

ACTIVATE central space with layered activity + shared resources

ARTICULATE 2 buildings are broken into tower



STACK extend towers to increase density



OFFSET and stagger the blocks to soften the verticality



assemblies

CONNECT the neighbourhood to the water and land with an activated green corridor

echo 3 - the values

The programming, materiality and spatial planning of the space is informed by TFN cultural values. The spaces are designed with sustainability, sharing and socializing in mind



SUSTAINABILITY & **ENVIRONMENTAL STEWARDSHIP**

is achieved through mass timber construction, vertical gardening and dedicated green spaces



SHARING OF RESOURCES. **KNOWLEDGE & SPACE**

is encouraged through communal art studios and galleries, designated workshop spaces for cultural activities.



COMMUNITY AS ONE BIG **FAMILY**

is about providing the community kitchen, dining hall and courtvard firepit as spaces to socialize and gather

business plan

Executive Intent

The development program includes a variety of integrated community components designed to generate revenue and foster community engagement:

Diversified Micro-Revenue Strategy: The financial resilience of the project is built on a "diversified micro-revenue strategy that mitigates risk and ensures long-term stability." This includes:

Development program

- Below Market Affordable (18 units)
- Mid-Affordable (30 units)
- Near-Market (18 units)
- · 25% Market Rate (30 únits)





DTT-D-07

Operating Model (Financial Proforma)

Gross Potential Income (GPI) = Effective Gross Income = Operating Expenses = NOI Lifecycle Value: Reduced Carbon deduction 50-25% vs. Concrete lows Processes directly = efficient prefabrication, law-form, and reliable lifecycle value.

Governance & Partnerships

Land & Operations: Community. Land Trust model. Tsawwassen First Nation (TFN)



Systemization & Cost Strategy

Mass Timber prefabrication – standardized wall and floor panels produced regionally Mass Timber = lower Carbon Footprint

Modular kiosks and maker space's adaptable to different sites. Vertical Garden = Food Production = total Rough annual yield by crop type per building Typology

Leafy greens (lettuce, kale, salad mix): \sim 25–50 kg/m²/yr = 1,800–3,600 kg/yr total (≈ 24,000–48,000 salad servings, at 75 g/serving)

Tomatoes (greenhouse): $\sim 40-60 \text{ kg/m}^2/\text{vr} = 2.880-4.320 \text{ kg/vr total}$ (≈ 19,200–28,800 servings, at 150 g/serving) · Outdoor field range: 8–15 kg/m²/season \rightarrow 576–1,080 kg/yr



Systemization & Cost Strategy

Short-Term Activation

Market kiosks provide immediate community engagement and early revenue.

Expansion through CSA programs, cafés, and youth programs, reinforcing food security, local economy, and cultural vibrancy.

Long-Term Resilience

Fully occupied housing and a self-sustaining community economy complete the integrated cycle, ensuring affordability and stability over time.







a day in our community

The central piazza is the beating heart of daily life—radiating warmth and activity. Around its edges, residents flow between a communal kitchen, creative workshops, and a lively art gallery. These shared spaces spark chance encounters, invite collaboration, and nurture a deeper sense of belonging. The piazza becomes more than just a gathering space—it is the stage where community life unfolds, weaving together culture, creativity, and connection.



1 community kitchen

Ben and Maya plan a surprise retirement dinner for their dad. They book the community kitchen, and neighbours roll in with aprons chopping, stirring, and prepping side by side until the tables fill with the meals they've made together.



2 vertical garden

Elliot and his friends love filling baskets with fresh vegetables and fruit. One afternoon he shares a crate with the neighbours. They love it and ask to join him, turning the garden into a shared harvest.

3 daycare +playground

Day care in their building makes Olivia and Jack's day easy: lift down, quick hand-off, lift up and no commute detours. Noon peek, five-o'clock hugs, everything is closer and calmer.





courtyard firepit

Maya, Liam and Mark gather at the firepit courtyard as Grandma Edith and Grandpa Walter share the community's history and traditions. By dusk, the kids carry the traditions and history lessons home.



4 workshops


With Grandma Edith and Grandpa Walter leading, neighbors learned cedar weaving, traditional salmon prep, and community songs with drumbeat, turning a simple workshop into a celebration.



5 art studio + gallery

Mike is an artist moved in recently and rented the corner gallery on ground level. By the weekend he hung his work and started drop-in classes, turning the place into the neighborhood's little art room.







through the longhouse

The sectional view reimagines the longhouse concept of arranging communal activities at the core and private life around the center. The section shows one possible stacking strategy of the units, with other variations adaptable to evolving community needs. The flexible framework balances privacy with collective belonging, allowing residents to live independently while remaining connected to their neighbours. Within this vertical environment, generations grow together, learning traditions and history, strengthening cultural roots and sustaining a connection with the land.



























perspective unfolded

The views illustrate how daily life flourishes through community. Shared spaces foster traditions, celebrations, and everyday exchanges, where residents gather to learn, trade, and connect. Locally owned businesses and gardens sustain the neighbourhood, offering fresh produce and meaningful work. Spaces for communal yoga and meditative practice further strengthen bonds, nurturing well-being alongside cultural continuity. At its core, the design champions community, family, and culture as the true foundations of a thriving society.
































Things



alling




Structure + Ramp + Laneway Houses


+ Nature + Culture


= Healing
Machine













Inspired by true stories, Where Streets is a collab between digital agency AP and EG UrbanLab. Where Streets highlights how local modular timber construction of laneway houses may address both the housing and opioid crises. With community as method, Healing Machine houses diverse treatment approaches beneath two wings centering culture as medicine.

Acknowledgments

Much work were completed on the unceded territories of the kwikwaλam First Nation. Team Lead **DG** thanks Dene Elder Joe, and Elders Yoshi and Dr Martin for their friendship and wisdom. All cultural annotations are suggestions subject to decisions by sćawaθen Nation. Lead Architect: LM UDMH Intern: LK


Stats: Site Area: 8,112.57 sqm 219 x2-storey units of 800 sqft (1-3 bdrm) Commercial/culture: 1,457sqm x4 storeys Shared residential spaces: 1,597 sqm Total: 23,688 sqm over 17 storeys Floor-Area Ratio (FAR): **2.92**

Heartwood

How can a modular manufacturing of timber building enrich the community?


'Heartwood' is named after the core of the wood that provides strength. It envisions a co-living community by a prefabricated core and composite floor system. Its modular construction ensures efficient delivery, rapid assembly, and minimal disruption. It reimagines collective living through the warmth and resilience of timber.

With a simple yet robust structure as its foundation, community space drives the design, shaping the building's elevation and creating a portal that connects people to the river and park. Respecting the Tsawwassen First Nation's inclusion in the area, shared halls and open community spaces close to the ground form the heart of the project. These spaces welcome ceremonies, exhibitions, and communal meals, extending memories and cultural exchange from residents to the wider neighborhood.




Context

A school in front and riverside in the back, the site works as an important connector between culture and nature.



Reverence

With the co-op residential over 3rd floor, two floors of open community space will work as a portal between the city and riverside.



Community

Front of the building becomes a core community space, with a shared hallway lounge and open canopies for residents facing the wide garden open to the public.



DTT-D-09

Decoding Core


How do you unitize on-site built timber structure while provide flexibility in space usage?

The design of Heartwood began with understanding the building's core. While many high-rise timber buildings rely on concrete for structural stability, our goal was to create a timberbased core. This is achieved through a modular, prefabricated timber core system with minimal additional steel components.

on-site construction through precise assembly, reducing construction time by up to 50%. Its offsite fabrication minimizes waste and emissions, while the natural materials provide durability. thermal efficiency, and a significantly lower environmental impact—offering up to 170% carbon benefit compared to traditional concrete cores. Engineered for safety, the timber core achieves a two-hour fire rating and resists seismic and wind forces up to 120 mph. The modular system can be stacked floor by floor, supporting up to 12 stories.

The prefabricated timber core allows rapid The timber supply comes from multiple sources. including forests, wood waste, and charred wood from wildfires. Each material undergoes a digital milling and detailing process, where smaller pieces are transformed into fingerjointed members for structural components using CNC technology. These elements are then delivered to form the timber core. Combined with the composite floor system, this approach reduces the total number of members required for the entire building.


Finally, the combined structural system, anchored by the timber core, informs how the building is occupied and operated. Its clarity allows easy adaptation to diverse site conditions. Whether in a dense urban setting or a natural landscape, the system can scale from a micro-housing unit with a single core to a multi-family high-rise with numerous units. Using Site D as a baseline, this approach offers Vancouver residents a new way of living in residential buildings.



Social Lounge

Inspired by the longhouse system, a symbol of shared wealth for the Tsawwassen First Nation. our design reinterprets this tradition through a generous, shared community hall. This space allows residents to gather and engage with one another, fostering a sense of belonging. Rather than duplicating corridors to maximize units, we prioritized communal space, embracing a reduction in marketable area to honor cultural values and strengthen social connections. In this way, Heartwood celebrates community over profit, offering a residential experience rooted in shared life and human connection.

Outside homes, certain cores are dedicated to circulation, while others function as a shared kitchen that act as a hub of the community life. These kitchens are more than functional spaces. They honor the Tsawwassen First Nation, enabling residents to continue cherished traditions of trade and barter. They also recognize the cultural and spiritual importance of foods such as salmon, crab, and eulachon, creating opportunities for intergenerational exchange, storytelling, and the preservation of community heritage within the building.



Roof Plan

- 1. Roof Lounge
- 2. Central Stair / Elevator
- 3. MEP / Storage 4. Egress Stair



Typical Floor Plan A (4F, 6F, 8F)

- 1. Studio Unit 5. Central Stair / Elevator 9. Egress Stair
- 2. Bathroom 6. Shared Kitchen
- 3. Kitchen 7. 2 Bedroom Unit
- 4. MEP / Storage 8. 1 Bedroom Unit

		6	2 7 0 4		2 2 7 8 8 8
2	5				

Typical Floor Plan B (3F, 5F, 7F)

- 5. MEP / Storage 1. Studio Unit
- 6. Central Stair / Elevator 2. Social Lounge
- 7. Shared Kitchen 3. Bathroom
- 8. Egress Stair




Flexible Home


Heartwood offers multiple housing types that flexibly expand according to family size. A studio unit occupies one core, while family units can occupie multiple cores, depending on the desired area and layout.

Each core works purely functional. It contains storage, MEP, bathroom and kitchen, allowing the spaces in between to become loftstyle rooms that can be freely furnished. Residents could add extra partitions for optimal use, enabling full customization of their living environment.


Pro Forma						
			BASE CASE		S	UBMISSION
FSR:			5			3
Lot Size:			25,540 ft ²			87,375 ft ²
Building Area above	Grade:		127,700 ft ²			105,820 ft ²
Building Efficiency (%):		85%			78%
Total Stories above	Grade:		18			8
Total Stories:			21			9
Stories below Grad	e:		3			1
Units:			86			61
Bedrooms:			178			64
Amenity Space Are	a:		850			1,290
Non-residential Are	a:		3,000			23,380
Construction Cost						
			Mass Timber		1	Mass Timber
	ft ²	\$/ ft2	Cost	ft ²	\$/ ft ²	Cost
Below Grade:	75,000	\$299	\$22,425,000	6,940	\$299	\$2,075,060
Base Floor:	8,700	\$403	\$3,506,000	20,660	\$403	\$8,325,980
Above 1st Storey:	119,000	\$431	\$51,289,000	85,150	\$431	\$36,699,650
	Quantity	\$/Unit		Quantity	\$/Unit	
Balconies:	86	\$25,000	\$2,150,000	64	\$25,000	\$1,600,000
	Cost per	Months		Cost per	Months	
Schedule Costs:	\$50,000	16	\$800,000	\$50,000	8	\$400,000
Total	ŕ		\$80,170,100			\$49,110,690
Embodied Carbon						
	ft²	Embodied	Total	ft²	Embodied	Total
Building Area:	202,700	2.69	542,112.31	114,737	2.49	285,695.13




Studio Unit Area: 575 sqft Count: 52




1 Bedroom Unit Area: 860 sqft Count: 6




2 Bedroom Unit Area: 1150 sqft














Reverencing Land

How do you connect with the land?

Respecting the site as sacred ancestral land for the Tsawwassen First Nation, the building is lifted and the ground level becomes an open portal connecting the park at the front with the riverside at the back. Composite floors and columns create shaded areas for rest and enjoying the landscape.

The ground level of the raised garden bed features ceremonial firepits and natural play areas for all ages, while also serving as an all-day resting space. The second floor platform functions as a public art space and other outdoor public events and performances, with office, retail, and amenity areas for management and revenue. These shared spaces provide the residents opportunities to share the lifestyle while creating a buffer between private and public realms.



Ground Floor / L2 Plan

- 1. Residential
- 2. Retail and Amenity space
- 3. Indoor Social / Gallery
- 4. Outdoor Social / Gallery
- 5. Recreation Court
- 6. Garden
- 7. Courtyard
- 8. Peristyle

9. Underground Parking Lot Entry (80 Lots)
10. Front Gardeen



Social Community

Open, low, outdoor spaces are central to Heartwood, celebrating the community and those who will live within it. The residential units are organized as compact, core-based apartments with shared corridor lounges, fostering daily interaction. Opposite these intimate living areas, public spaces unfold into a wide, square-shaped courtyard, creating a communal heart where residents can gather, connect, and engage with the environment.

This low-rise public courtyard is a place where people all meet along, and where the public is introduced the culture. The evenly spaced cores open into flexible communal spaces where residents can gather, celebrate, and engage in everyday life. These spaces flow naturally into the riverside garden, creating a seamless connection between indoor and outdoor environments. Heartwood fosters cultural enhancement, storytelling, and collective memory, allowing both residents and the public to experience and participate in a living cultural landscape.





























BASIC PLAN

Communal living, mix of flexible rooms that can be addapted to 1BR, 2BR, 3BR and Family living. Thanks to the linear floor plan the arrangement between sites can be different, thus permiting modularity, replicability and catalyst for housing change with MPP or CLT. Long corridors connecting community spaces and public gathering areas among neighbouts while inside the housing the mirrored wider corridor becomes a service patio also symbolizing a longhouse. Structure in shear walls is strong enough to cantiliver the two corridors.

(1) Washer Dryer Station


CONFIGURATION FLEXIBILITY




THE TOWERS

Two mirrored towers of housing









FUTURE BUILD

Future ammenities in an orthagonal modular grid in order to continue using MPP or CLT system




Three independent buildings with more housing and allocation of community program troughout the buildings






HYBRID SYSTEM

Hybrid construction system with two independent articulation structure in this case concrete







(5) PLAYGROUND

(6) GARDENING BEDS

(7) CAR SHARE FOR TENANTS

(8) SALISH ECOSYSTEM SANCTUARY

(1) WOOD WORKSHOP

- (2) AMPHITHEATER
- (4) COMMUNITIES SUPERMARKET

LEVEL 1 AND 2


1 BEDROOM 6 2 BEDROOM 8 **FAMILY**

NORTH AMMENITY

Double height canoe making workshop. Where the Tsawwassen community can gather to venerate the ancestry art of canoe making and or families can leart to build wooden furniture for ther houses. Where we are laso proposing a connection directly to the river for them to fish and try the canoes. This space also connects to an amphitheater for community assemblies.

SOUTH AMMENITY

Double height supermarket and storage for anything the communit grows in the gar-dens or fish with their canoes in the river. Something to give back to the community where neighboors and school can buy.



(1) LIBRARY AND CLASSROOMS (2) CLINIC

(3) CHILD CARE (4) GYM

(5) OUTDOOR SPACE

LEVEL 3 AND 4

1 BEDROOM 8 2 BEDROOM 6 3 BEDROOM 4 **FAMILY**

NORTH AMMENITY

Double height library, classroom and reading spaces plus exterior terraces.

SOUTH AMMENITY

General medicine consultations for the community and daycare plus a indoor gym.

LEVEL 5


1 BEDROOM 11 2 BEDROOM 3 BEDROOM 5

AMMENITY


Outdoor terraces and future units



Its very important to mention that for sealing system and envelope enclosure we are using a system of insulation attached to the facade of the unit with reclaimed plywood and reclaimed wooden slats arragend in different modules along the height of the facade. All exteriors are as much reclaimed wood as possible. For ventilation and ilumination as our section depicts we have a ventilation systems with jalousie windows on the interior patios permiting cross ventilation system.




All housing is modular with our MPP Manufacturer having panel dimensions of 42FT X 12FT we divided our floor panl in 21FTX12FT giving us a basic module of 3FT which in case of metric 3FT is 0.9144m the closest module to 1m so it could be easily replicated to other countris with metric manufacturers. Then the H structure shear wall system is 10ft wide by 10ft tall wich comes from a panel of 60ftx10ft giving us 6 panels and lastly our H shorter walls being 6ft wide by 10ft tall. All our facade modules being a multiple of 3 mainly being 6ft or 3ft troughtout the whole project.





We ended up doing the cost analysis with MPP from Freres since its more affordable than CLT and a Pacific North West unique modular material. Its more flexible in basis of design than CLT but our proposal could be analyzed with both materials.


								DT.	Γ-D-1	0
COST BASE CASE ANALYSIS	BASE CASE					Həńgəminəm				•
FSR	5					2.19				
Lot Size	25,540 SF					87,337 SF				
Building Area Above Grade	127,700 SF					191,425 SF				
Building Efficiency	85%					85%				
Non Saleable/Rentable	19,155					28,714				
Saleable/Rentable	108,545					162,711				
Total Stories Above Grade	18					5				
Total Stories	21					5				
Base Floor	1					1				
Above 1St Storey	17					4				
Stories Below Grade	3					-				
Units	86					88				
Bedrooms	178					158				
Amenity Space	850 SF					28,514 SF				
Non-Residential	3,000 SF					3,000 SF				
CONSTRUCTION COSTS		CONCRETE		MASS TIMBER			CONCRETE		MPP	
Below Grade	75,000 SF	\$315	\$23,625,000	\$299	\$22,425,000	0 SF	\$315	\$0	\$300	\$0
Base Floor	8,700 SF	\$360	\$3,132,000	\$403	\$3,506,100	38,285 SF	\$360	\$13,782,600	\$350	\$13,399,750
Above 1st Storey	119,000 SF	\$385	\$45,815,000	\$431	\$51,289,000	153,140 SF	\$385	\$58,958,900	\$255	\$39,050,700
Balconies	86	\$25,000	\$2,150,000	\$25,000	\$2,150,000	0	\$25,000	\$0	\$25,000	\$0
Schedule Costs (Overhead/Construction Time)	\$50,000 / Mo.	18 Months	\$900,000 / Mo.	16 Months	\$800,000	\$50,000 / Mo.	18 Months	\$900,000	12 Months	\$600,000
TOTAL			\$75,622,000		\$80,170,100			\$73,641,500		\$53,050,450
EMBODIED CARBON		CONCRETE		MASS TIMBER			CONCRETE		MPP	
ELIBODIED ONIDOIT	Area		Total		Total	Area			Embodied C1	otal Carbon
	A100		1000			AICU		000 4451 405		







We believe elders should live mixed troughout the building not segregated in their own corner. Also not necesarilly living in 1 Bedroom unit where they live solo, instead they can live in families and there fore we have considered a four bedroom unit. The Tsawwassen venerate they elderly as we all should.











Unit Plans and Flexibility


The irony is that keeping to a rigid 12' x 12' point-load column grid allows for more flexibility for interior layouts.


- Each apartment needs to have at least one first row 12' x 12' square for entry and at least one second row square for kitchens and washrooms.
- Demising walls are always placed along the column grid. They may jog vertically and horizontally or may be removed to fit growing families overtime.
- External circulation lowers long-term maintenance and occupancy costs and creates spaces for neighbourly interactions.
- The squares are sold with minimal finishes, with exposed timber CLT ceilings, concrete floors and either roughed-in plumbing for residents to finish or a basic washroom and kitchen unit that can be included to meet occupancy requirements.

















PREFAB HYBRID TIMBER AND STEEL STRUCTURE COMPONENTS

- 12'x 12' floor panel (7-ply CLT with a concrete topping and acoustic matt) achieves the fire, acoustic requirements.
- Proposing industry-standardized CLT floorplate
 either 10'x10' or 12'x12', 5-ply or 7-ply to correspond to
 the preferred grid sizes 3-3.5m.
- 8'-8" steel HSS flat plate post with intumescent paint finish. Point load, no beams, so services can run in either direction for best efficiency. Steel makes for smaller posts and reduces risk of rotting from flooding.
- 12' x 19'-6" prefab envelope (one square wide, two squares high) with external braced exo-skeleton frame for lateral loading. Complete with factory-installed strip windows, exterior doors, cladding and insulation.
- Envelope panels can follow one floor behind the structure (to meet code requirement of enclosing at least every fourth floor of wood construction)
- 12' x 8'-8" prefab demising wall and 8'-8" high prefab internal unit walls in 4', 6' and 10' lengths.
- 12' wide bolt-on steel walkways
- 24' wide steel truss bridge
- External steel stair
- Concrete elevator core

SQUARES

48 SQUARES per floor = up to 24 PEOPLE in 2 to 12 APARTMENTS.



3 floors and a shared internal and external space make a BLOCK = 72 people


TOWERS


4 stacked BLOCKS create a 12-storey
TOWER


= 288 PEOPLE (432 people in 18-stories)


COMMUNITIES

TOWERS can stand alone or, on larger sites, they can be connected laterally into COMMUNITIES









Site Plan


Site D is on Tsawwassen First Nation land. The brief asked for living spaces for youth, families and Elders (fully-accessible) in a variety of unit sizes gathered around community spaces. Core community values of intergenerational living, gathering, and maintaining connection with the lands and waters are to be honoured.

Our design was developed to support intergenerational living or found family groups as well as providing options for individuals, couples, single parents and nuclear family arrangements.


Larger social events for all the blocks can take place on the ground level which can have raised garden beds, natural playscapes, ceremonial fires and a dock on the river for fishing excursions. The parking lot can double as a space for basketball, pickleball, or learning to bike.

ADAPTABILITY

The block module is flexible for different scales of sites and lends itself to development over time on a larger parcel such as Site D.







Regulatory Considerations

SUGGESTED CHANGE 1:

Increase the maximum height for wood structures from 138ft (42m) to 143 feet (43.6m). Reason: to accommodate 12 stories with the switch from 8" concrete slab to a 7-ply CLT floor assembly with a typical 8'-8" clear height in each suite.

SUGGESTED CHANGE 2:

Increase the maximum stories from 12 to 18 with a corresponding 215 feet (65.4m) height allowance.

Fire and acoustic ratings are achieved through encapsulated timber (max 30% exposed). Only the ceiling is exposed timber. The 7-ply floor assembly gives a 2-ply char layer and assists with meeting the acoustic rating.

Moisture control is achieved by (1) having no timber exposed on the exterior, (2) envelope panels can follow every two floors of structure to enclose (every 4 floors is required) and (3) CLT panels to have a factory-applied top-coat and edge sealer.


Bridge Connections

The block arrangements make for smaller, secure groupings within a larger tower model so that connections are developed at a scale where block residents know each other and can connect on the bridge to share childcare, perform daily activities and host regular gatherings.

Development Types

The design can support owned or rented market or non-market housing, co-housing or mixed-use buildings, but co-operative housing may be the best fit, as the ownership model would allow each 12' x 12' square to be purchased as a share.

Owners can add or remove (purchase or sell) squares over time.



Pro-Forma

To reduce the cost premium for prefab hybrid (20-25% more than a concrete tower for an irregular design, according to BTY) we propose a rectangular building mass with a regular grid, no larger spans and no internal core.

The construction schedule of a hybrid mass timber-steel structure with a steel core is 20% shorter than concrete, but a steel core is larger and more costly. In our design, the concrete elevator core is separated from the timber-steel structure, connected by external bolt-on steel walkways. The core can be completed in parallel to the main building to further reduce construction time.

Buildings can have smaller foundations because the proposed hybrid assembly is lighter than a ooncrete frame. Hybrid lends itself to the methods and skills of the existing steel industry including fabrication through 3D models, prefabrication shops, certified installers and proficiency in meeting tolerances.

Same steel trade can handle steel posts, walkways and stairs, mass timber floors and exterior wall assembly. Interior wall assembly could also be by the same trade with prefab modular wall panels in CLT or stick frame.

The exposed timber ceilings will have a premium for visual grade but the alternate would be 5-ply CLT with two layers of GWB on an acoustic channel, which requires another trade. The exposed wood provides a connection to nature.

COST BASE CASE ANALYSIS

FSR	5	
Lot size (sq ft)	65,340	
Building sq ft Above Grade	331776.0	
Building efficiency (%)	100	External circulation
Non saleable/rentable (sq ft)	0	
Saleable/rentable (sq ft)	331776	
Total Stories (#)	12	
Stories below grade (#)	0	
Base floor (#)	1	
Above 1st storey (#)	11	howards.
Units (#)	264	
Bedrooms (#)	704	
Amenity space (sq ft)	13824	
Non-residential (sq ft)	3456	

Construction costs Concrete Block Party Square \$/sqft Cost \$/sqft Cost footage Below grade 0.0 \$315 \$0 \$0 Base floor 27648.0 \$360 \$9.953.280 \$403 \$11,142,144 304128.0 \$405 \$123,171,840 \$431 \$131,079,168 Above 1st storey \$/unit Quantity \$/unit 352 \$25,000 \$8.800.000 \$25,000 \$8.800.000 **Balconies** Cost per # Months Cost # Months Cost month Schedule Costs (Monthly \$50,000 \$900.000 \$600,000 Overhead) TOTAL \$142,825,120 \$151,621,312

Embodied Carbon									
		Со	ncrete	Block Party					
	Sq ft	Embodied Carbon kg/sq ft	Total Carbon	Embodied Carbon kg/sq ft	Total Carbon				
Total Building Sq Footage	408960.0	6.69	2735541.619	3	1226880				




Floating Village

A timber structure lifted to embrace water, culture, and community.

Our design journey began with a simple but ambitious idea: "the building as a park, and the park as a building." To achieve this, we approached the park not as a collection of disconnected features - paths, trees, benches - but as a living system. Using a process of deconstruction, transformation, and reconstruction, we distilled its essential characteristics: cohabitation, redundancy, adaptation, complexity, modularity, and multi-layered structure. A park, like nature, is not static; it is dynamic, resilient, and inherently


This understanding led us to see nature as a series of building blocks that are replicable. Just as all life on earth is formed from four base components, our design sought to reclaim urban land through a similarly modular system. The concept evolved into an inverted pyramid structure inspired by the ancient Chinese architectural element 斗拱 (dougong). By breaking this traditional system apart, we identified our own "DNA" for the vertical village: the beam and the bracket - structural elements that, when multiplied and layered, create a new architecture of community and resilience.

Massing Reference




Schematic diagram of the abstract form of larger bracket as column capital replaced by interlocking self-similar smaller brackets to increase the stiffness as well as to transfer the roof and beam load sequentially to the column.







Massing Diagram









Dou-Gong Interlocking Method





Using the Lifted-up Method to give the land back to the community













Both dou and gong are strategically staggered vertically, horizontally, and in depth to ensure privacy and minimize direct views between units. The resulting offsets create voids and terraces, providing residents with access to outdoor green spaces within the vertical village.







Sustainable Diagram



Air Quality

The staking and shifted staggered design creats a lot of pocket areas, that brings fresh air in and out the units. The greenery decorates the building also improve the air quality



Solar Panel

Installing solar panels on the roof generates renewable energy, reduces operating costs, lowers the building's carbon footprint, and contributes to long-term sustainability goals.



Water Recycle Reuse system

Integrating water recycle-reuse systems conserves freshwater resources, reduces utility costs, supports sustainable stormwater management



Greenroof

A green roof enhances building performance by reducing stormwater runoff, improving insulation and energy efficiency, and contributing to urban biodiversity and occupant well-being.



Chimney Effect

The circulation of cold and hot air strengthen the natural ventilation and also reduce the active cooling and heating in the some extreme weather in Metro Van




Bird Migration Nests

Incorporating bird migration nests on the roof supports urban biodiversity, provides safe habitats for migratory species, and strengthens the project's ecological and sustainability credentials.


The Construction Material Pyramid



Construction Details,













Base Case Analysis

BASE CASE		
FSR	5	
Lot size (sq ft)	25,540	
Building sq ft Above Grade	127700.0	
Building efficiency (%)	85	
non saleable/rentable (sq ft)	19155	
saleable/rentable (sq ft)	108545	
Total Stories above grade (#)	18	
Total Stories (#)	21	
Base floor (#)	1	
Above 1st storey (#)	17	
Stories below grade (#)	3	
Units (#)	86	
Bedrooms (#)	178	
Amenity space (sq ft)	850	
Non-residential (sq ft)	3000	

CONSTRUCTION COSTS					
		Concrete		Mass Timbe	r
	Square footage	\$/sq ft	Cost	\$/sq ft	Cost
Below grade	75000.0	\$315	\$23,625,000	\$299	\$22,425,000
Base floor	8700.0	\$360	\$3,132,000	\$403	\$3,506,100
Above 1st storey	119000.0	\$385	\$45,815,000	\$431	\$51,289,000
	Quantity	\$/unit		\$/unit	
Balconies	86	\$25,000	\$2,150,000	\$25,000	\$2,150,000
	Cost per month		# Months		
Schedule Costs	\$50,000	18	\$900,000	16	\$800,000
TOTAL	=		\$75,622,000		\$80,170,100

EMBODIED CARBON					
		Concrete		Mass Timbe	er
	Sq ft	Embodied	Total Carbon	Embodied	Total Carbon
Total Building Sq Footage	202700.	0 6.69	1355864.354	2.69	546112.31

FLOATING VILLAGE		
FSR	3.143072401	
Lot size (sq ft)	88,465	
Building sq ft Above Grade	278053	
Building efficiency (%)	85	
non saleable/rentable (sq ft)	41707.95	
saleable/rentable (sq ft)	236345.05	
Total Stories above grade (#)	10	
Total Stories (#)	10	
Base floor (#)	1	
Above 1st storey (#)	9	
Stories below grade (#)	0	
Units (#)	370	
Bedrooms (#)	458	
Amenity space (sq ft)	46084	
Non-residential (sq ft)	18256	

CONSTRUCTION COSTS						
		Concrete			Mass Timbe	er
	Square footage	\$/sq ft	Cost		\$/sq ft	Cost
Below grade	0.0	\$315		\$0	\$299	\$0
Base floor	9128.0	\$360		\$3,286,080	\$403	\$3,678,584
Above 1st storey	268925.0	\$405		\$108,914,625	\$431	\$115,906,675
	Quantity	\$/unit			\$/unit	
Balconies		\$25,000		\$0	\$25,000	\$0
	Cost per month	# Months	Cost		# Months	Cost
Schedule Costs (Monthly	\$50,000	18		\$900,000	16	\$800,000
TOTAL	_			\$113,100,705		\$120,385,259

EMBODIED CARBON							
	Concrete				Mass Timber		
	Sq ft		Embodied	Total Carbon	Embodied	Total Carbon	
Total Building Sq Footage		278053.0	6.69	1859902.078	2.69	747962.57	